

ADDENDUM NO. 1

Market Street Storm Main Rehabilitation Project City of Kirkland Job Number 20-18-PW

Date: June 12, 2018
To: All Plan and Specification Holders
From: Aparna Khanal, P.E.
Subject: Market Street Storm Main Rehabilitation Project
Date of Bid Opening: June 19, 2018

Notice to all Plan Holders:

This Addendum No. 1, containing the following revisions, additions, deletions, and/or clarifications dated June 12, 2018, is hereby made part of the Plans and Specifications (Contract Documents) for the Market Street Storm Main Rehabilitation Project –City of Kirkland Job Number 20-18-PW. Bidders shall take this Addendum into consideration when preparing and submitting their bids.

Contractors shall acknowledge receipt of this Addendum in the place provided on Bid Proposal Page 2. Failure to do so may disqualify the Bidder from consideration of its bid.

All other requirements of the contract documents remain in effect.

A. Bid Schedule

- 1) Name of Schedule A is revised to read "Market Street Storm Main Rehabilitation".

B. Revisions to the Specifications

- 2) Revision to Section 7-05.3, **Installer Experience and Qualifications**. Second sentence of paragraph is revised to read "... minimum of 1-year of manhole rehabilitation experience totaling at least 1,500 vertical feet or greater of manhole rehabilitations".

- 3) Revision to Section 7-05.3, **Testing**. All five paragraphs are deleted and replaced with the following:


"All finished manhole rehabilitation work shall provide a watertight surface.

After the manhole rehabilitation work has been completed, the manhole shall be inspected by the Contractor in the presence of the Owner and the work shall be accepted if found satisfactory to the Owner. No evidence of visible leaks shall be allowed. Non-uniformity, sagging, or other defects will be cause for rejection of the surfacing. All surfaces shall be tested for the presence of holidays and pinholes via spark testing at 100-volts per millimeter. The Contractor shall provide the testing equipment and perform the testing in the presence of the Owner. Any holidays or pinholes found during the testing shall be repaired and the surface re-tested until the surfaces are completely free of holidays and pinholes."

- 4) Revision to Section 7-16.3, Table for videos of the television inspection is deleted and replaced with the following:

Storm Drain Segment	Location	Video Link
CIPP Run #1 (SDCB 5110 to SDCB 5095)	Market Street	• CIPP#1-SDCB5110-SDCB5095 (https://youtu.be/_NXkBJv9I5o)
CIPP Run #2 (SDCB 5095 to SDCB 5090)	Market Street	• CIPP#2-SDCB5095-SDCB5090 (https://youtu.be/1hHgelBfsGQ)
CIPP Run #3 (SDCB 5090 to SDCB 5085)	Market Street	• CIPP#3-SDCB5090-SDCB5085 (https://youtu.be/6oNH6hVscaw)
CIPP Run #4 (SDCB 5085 to SDCB 5080)	Market Street	• CIPP#4-SDCB5085-SDCB5080 (https://youtu.be/ik5qJbAZeRQ)
CIPP Run #5 (SDCB 5080 to SDCB 5073)	Market Street	• CIPP#5-SDCB5080-SDCB5073 (https://youtu.be/G8q5wH4garU)
CIPP Run #6 (SDCB 5073 to SDCB 5070)	Market Street	• CIPP#6-SDCB5073-SDCB5070 (https://youtu.be/ubSpcwVLkwQ)
CIPP Run #7 (SDCB 5070 to SDCB 5061)	Market Street	• CIPP#7-SDCB5070-SDCB5061 (https://youtu.be/nsFhsPYpv64)
CIPP Run #8 (SDCB 5061 to SDCB 5056)	Market Street	• CIPP#8-SDCB5061-SDCB5056 (https://youtu.be/2beFTJKpp7Y)
CIPP Run #9 (SDCB 5056 to SDCB 5052)	Market Street	• CIPP#9-SDCB5056-SDCB5052 (https://youtu.be/eJYqtao5tvq)
CIPP Run #10 (SDCB 5052 to SDCB 5049)	Market Street	• CIPP#10-SDCB5052-SDCB5049 (https://youtu.be/nz-v6qTC1-0)

Sincerely,


Aparna Khanal, P.E., Sr. Project Engineer



Dave Snider, P.E., Capital Project Manager