INVITATION TO BID

Notice is hereby given that the City of Kirkland will receive sealed bids in the office of the Purchasing Agent, City Hall, 123 Fifth Avenue, Kirkland, Washington, at 11:00am, local time on March 13, 2013, for the project hereinafter referred to as:

TOTEM LAKE TWIN 42-INCH CULVERT REPLACEMENT PROJECT

JOB NO. 02-13-PW

At said time all bids will be opened and publicly read aloud. Each bid shall be accompanied by a bid proposal deposit in the form of a cashier's check or a bond issued on a form acceptable to your surety made payable to the City of Kirkland for a sum of not less than five percent (5%) of the total bid amount. No bid shall be considered unless accompanied by such bid proposal deposit. Incomplete proposals and proposals received after the time stated above will not be considered. Faxed or emailed responses are not acceptable.

The work to be performed under these specifications consists of furnishing all labor, tools, materials, and equipment necessary for construction of the **TOTEM LAKE TWIN 42-INCH CULVERT REPLACEMENT PROJECT**. Specific work includes, but is not limited to, removing approximately 362 linear feet of twin 42-inch corrugated metal pipe culvert and constructing along the same alignment an 8-foot span x 3-foot rise concrete box culvert gravity storm drain, constructing approximately 374 linear feet of 8-foot span x 3-foot rise concrete box culvert gravity storm drain, removing and abandoning approximately 120 linear feet of twin 42-inch corrugated metal pipe culvert, removing sediment from approximately 400 linear feet of open drainage channel, 2 precast panel vault junction structures, connection of existing storm drains to the new facilities, modifying an existing storm water settling basin, removing and restoring pavement and other existing surface features and improvements, removing and restoring an existing traffic signal, furnishing and operating a temporary traffic signal and controller, temporary and permanent erosion and sediment control, temporary traffic control, and other work. The City will furnish the box culvert sections, junction structures components, and certain appurtenant items. To determine the full scope of work under the Contract or any part of it, coordinate the applicable information in the several parts of the Plans, Specifications, and Contract Documents. The estimated cost for this project is in a range of $2,480,000 to $3,160,000.

The City will not sell bid packages. Plans, specifications, and addenda may be viewed and obtained online at *www.bxwa.com*. Click on: "Posted Projects"; "Public Works", "City of Kirkland". The Bidders List is maintained by the Builder's Exchange of Washington, Inc. Registration for the bidder's list may be made online, by phoning (425) 258-1303, or at Builder's Exchange of Washington located at 2607 Wetmore Ave, Everett, WA.

Questions regarding this project shall be submitted in writing to Noel Hupprich, P.E. **via fax** (425) 587-3844. **Questions via phone or email will not be accepted.** Bidders shall submit questions no later than 5 days prior to bid opening, due by 1:00 pm on March 6, 2013.

The City reserves the right to reject any and all bids, and to waive any informalities in the bidding, and to make the award to the lowest, responsive, responsible bidder as best serves the interests of the City.

No bids may be withdrawn within forty-five (45) days after the actual date of the bid opening.

Barry L. Scott, C.P.M.
Purchasing Agent

Published: Daily Journal of Commerce – **February 25, 2013, March 4, 2013**