



Construction phases will be staggered to minimize traffic congestion and reduce construction impacts.

Winter Spring Summer Fall

[illegible]

Intersection Improvements

✓ **Complete:** Install additional southbound 114th Ave NE to eastbound NE 85th St left turn lane. Upgrade traffic signal controller equipment to connect to new computer network for remote monitoring and control.

- Add traffic island at NE 124th Ave NE for future eastbound to northbound turn lane. Upgrade traffic signal controller equipment to connect to new computer network for remote monitoring and control.
- Add northbound 132nd Ave to eastbound NE 85th St right turn lane. Upgrade traffic signal controller equipment to connect to new computer network for remote monitoring and control.

Undergrounding Utility Wires

- **Nearing Completion:** Underground utility wires along NE 85th St from 120th Ave NE to 128th Ave NE.
- **Complete:** Install conduit for future undergrounding of utility wires along NE 85th St from 128th Ave NE to 132nd Ave NE.

Sidewalks with landscape planter strips where there are none

- Under construction: Install sidewalks (where there are none) on both sides of 124th Ave NE between NE 80th St and NE 90th St. Include landscaped planter strips between road and sidewalk where possible.
- Install sidewalk (where there are none) on both sides of NE 85th St between 120th Ave NE and 132nd Ave NE. Include landscaped planter strips with trees between road and sidewalk where possible. Install energy efficient street lighting. Construct detention and sediment control facility. Install new watermain along NE 85th Street from 132nd Ave NE to I405.

Resurface Street

- Preserve the City's infrastructure and reduce costly repairs by overlaying entire NE 85th St Corridor from 114th Ave NE to 132nd Ave NE.

