

CITY OF KIRKLAND
83rd Ave NE Pipe Replacement Project
JOB NO. 26-23-PW NO. SDC1510000
ADDENDUM NO. 1

TO THE PLANS, SPECIFICATIONS, PROPOSAL AND CONTRACT

Issued This Date: Thursday, February 15, 2024
Bid Opening: **Unchanged – February 22, 2024**
Place of Opening: City Hall, Council Chambers, posted online

Notice to All Plan holders:

This Addendum No. 1, containing the following revisions, additions, deletions, and/or Clarifications, is hereby made part of the Plan and Contract Documents for the abovenamed project. Bidders shall take this Addendum into consideration when preparing and submitting their bids and it shall be attached to the Contract Documents.

Contractors shall acknowledge receipt of this Addendum in the place provided on Proposal page 8. Failure to do so may disqualify the Bidder from consideration of its bid.

This addendum contains 7 pages, including this page.

All other requirements of the contract documents remain in effect.

Item 1:

Location: Bid Proposal, Bid Schedule

Description: a new lump sum bid item B10, General Restoration has been added to Schedule B. A revised Bid Schedule reflecting and highlighting these changes is attached to this Addenda and shall replace all previous versions.

Item 2:

Location: Appendix B - NUD Special Provisions and Standard Specifications

Description: Section 4, *Measurement and Payment* of the Northshore Utility District Engineering Specifications and Special Provisions shall be appended to include the following item description as also shown on the attached replacement page MP15-16:

General Restoration

The lump sum price bid for General Restoration shall constitute full compensation for all labor, material, tools and equipment necessary and incidental to restore disturbed ground surfaces and existing improvements to their pre-construction condition or better, not including work covered by other bid items. This item shall include, but not be limited to, the following:

1. Furnishing and placing of new topsoil, sod, bark, decorative rock or other surface treatment consistent with the adjacent undisturbed ground surface.
2. Excavation, grading and preparation of the areas to be restored.
3. Removal, storage and replacement of any existing decorative shrubs, hedges or trees.
4. Restoration of fences, rockeries, utilities or other structures.
5. Protection or replacement of existing culverts and asphalt lined ditches.
6. Protection of existing trees and improvements not to be removed.
7. Hydroseeding, seeding, mulching, plantings or other erosion control measures as required in rights-of-way, easement, or landscaped areas.
8. Asphalt or concrete pavement required beyond the limits allowed for payment described herein.
9. Removal and replacement of existing landscaping or irrigation system as required.

Payment shall be based on completion of the restoration satisfactory to the individual property owners or agency having jurisdiction over the affected property.

Item 3:

Location: Appendix B - NUD Special Provisions and Standard Specifications

Description: Section 4, *Measurement and Payment* of the Northshore Utility District Engineering Specifications and Special Provisions shall be amended to replace the following section for "Additional Potholing, If Required" in its entirety with the following:

Additional Potholing, If Required


Potholing is incidental to all other bid items. However, when located utilities are not found within the standard locating limits (2' on either side of the locate mark) or there are other utilities located that are not shown on the contract plans, the Engineer may authorize additional potholing and that authorized work shall be paid for under this bid item. The unit price bid for each "Additional Potholing, If Required", shall constitute full compensation for all labor, materials, tools and equipment necessary and incidental to pothole and record depths of the underground existing utilities in these circumstances, and the subsequent furnishing, handling, hauling, placing and mechanical compaction of foundation gravel, trench backfill and all other crushed rock or gravel material, native or imported. Engineer shall approve any work to be considered for payment under the item "Additional Potholing, If Required" prior to any such work commencing. No payment shall be made for potholing efforts that are not approved by Engineer.

An amended copy of page MP15 of Section 4 of Appendix B of the Specifications is attached to this Addendum and shall replace all previous versions.

Sincerely,

A handwritten signature in black ink, appearing to read "Indulekshmi", written over a horizontal line.

Indulekshmi, PE
Project Engineer

A handwritten signature in black ink, appearing to read "Rod Steitzer", written over a horizontal line.

Rod Steitzer, PE
Capital Projects Manager

Attachments: Bid Schedule (Bid Proposal replacement pages 10-11)

Appendix B – Section 4, *Measurement and Payment* page 10 (replacement page M15-M16)

CITY OF KIRKLAND

BID SCHEDULE A

City of Kirkland 83rd Ave NE Pipe Replacement Project JOB NO. 26-23-PW

Note: Unit prices for all items, all extensions, and the total amount of the bid must be shown. All entries must be typed or entered in ink.

Item No.	Item Description	Spec. Ref.	Est. Qty	Unit	Unit Price	Amount
1	Minor Changes	1-04	1	FA	\$5,000	\$5,000
2	Record Drawing (Minimum Bid \$1,000)	1-05	1	LS		
3	Construction Surveying	1-05	1	LS		
4	SPCC Plan	1-07	1	LS		
5	Mobilization (10%)	1-09	1	LS		
6	Project Temporary Traffic Control	1-10	1	LS		
7	Remove Existing Catch Basin	2-02	2	EA		
8	Removal of Existing Storm drain	2-02	100	LF		
9	Removing Asphalt Conc. Pavement	2-03	481	SY		
10	Structure Excavation Class B Incl. Haul	2-09	505	CY		
11	Shoring or Extra Excavation Class B	2-09	3050	SF		
12	Crushed Surfacing Base Course	4-04	109	TN		
13	HMA CL. 1/2" PG 64-22	5-04	184	TN		
14	Asphalt Berm	5-04	156	LF		
15	Solid Wall PVC Storm Sewer Pipe 24 In Diam.	7-04	311	LF		
16	Solid Wall PVC Storm Sewer Pipe 12 In Diam.	7-04	13	LF		
17	Catch Basin Type 2 48 In Diam.	7-05	4	EA		
18	Manhole 60 In. Diam. Type 1	7-05	1	EA		
19	Adjust Catch basin	7-05	1	EA		
20	Plugging Existing Pipe	7-08	8	EA		
21	Plugging and Abandon Catch Basin	7-08	3	EA		
22	Erosion Control and Water Pollution Prevention	8-01	1	LS		
23	Landscape Restoration	8-02	1	LS		
24	Additional Potholing, If Required	8-05	4	EA		
25	Cement Conc. Driveway Entrance	8-06	24	SY		
26	Green MMA Bike Marking	8-22	10	SF		


**CITY OF KIRKLAND
BID SCHEDULE B**

City of Kirkland 83rd Ave NE Pipe Replacement Project JOB NO. 26-23-PW

Note: Unit prices for all items, all extensions, and the total amount of the bid must be shown. All entries must be typed or entered in ink.

Item No.	Item Description	Spec. Ref.	Est. Qty	Unit	Unit Price	Amount
1	Removal of Existing Water Main	NUD	298	LF		
2	Removing Asphalt Conc. Pavement	NUD	51	SY		
3	Trench Safety Systems	NUD	1	LS		
4	Imported Foundation Gravel (If Required)	NUD	10	TN		
5	Crushed Surfacing Base Course	NUD	19	TN		
6	Crushed Surfacing Top Course	NUD	230	TN		
7	Asphalt Trench Patch	NUD	32	TN		
8	8" CI 52 DI Water Main	NUD	298	EA		
9	Connect to Existing Water System	NUD	3	EA		
10	Additional DI Fittings	NUD	500	LBS		
11	Remove and Replace Valve Box	NUD	3	EA		
12	Gate Valve Assembly - 8"	NUD	3	EA		
13	1" Water Service and Reconnection	NUD	4	EA		
14	1" Private PRV (if required)	NUD	4	EA		
15	Remove and Replace Manhole Frame and Cover	NUD	2	EA		
16	Additional Potholing, If Required	NUD	2	EA		
17	General Restoration	NUD	1	LS		

TOTAL COMPUTED BASE BID PRICE (A+B): \$ _____



6. Re-stripping of the traffic lanes, including thermoplastic striping and all road lines and arrows, and replacement of signs and traffic buttons, if any, outside of the Asphalt Overlay area.
7. Top seal in areas not located in Asphalt Overlay area.
8. Contractor to provide truck tickets to District.

Payment will be made based on the actual number of tons of asphalt pavement placed. Any other asphalt damaged by the Contractor's operations will be the Contractor's responsibility and will be considered incidental to water pipe construction and must be restored by the Contractor to the satisfaction of the governing jurisdiction.

Crushed rock base for trench patch will be measured and paid for under the bid item for crushed rock.


Additional Potholing, If Required

Potholing is incidental to all other bid items. However, when located utilities are not found within the standard locating limits (2' on either side of the locate mark) or there are other utilities located that are not shown on the contract plans, the Engineer may authorize additional potholing and that authorized work shall be paid for under this bid item. The unit price bid for each "Additional Potholing, If Required", shall constitute full compensation for all labor, materials, tools and equipment necessary and incidental to pothole and record depths of the underground existing utilities in these circumstances, and the subsequent furnishing, handling, hauling, placing and mechanical compaction of foundation gravel, trench backfill and all other crushed rock or gravel material, native or imported. Engineer shall approve any work to be considered for payment under the item "Additional Potholing, If Required" prior to any such work commencing. No payment shall be made for potholing efforts that are not approved by Engineer.

General Restoration

The lump sum price bid for General Restoration shall constitute full compensation for all labor, material, tools and equipment necessary and incidental to restore disturbed ground surfaces and existing improvements to their pre-construction condition or better, not including work covered by other bid items. This item shall include, but not be limited to, the following:

1. Furnishing and placing of new topsoil, sod, bark, decorative rock or other surface treatment consistent with the adjacent undisturbed ground surface.
2. Excavation, grading and preparation of the areas to be restored.



3. Removal, storage and replacement of any existing decorative shrubs, hedges or trees.
4. Restoration of fences, rockeries, utilities or other structures.
5. Protection or replacement of existing culverts and asphalt lined ditches.
6. Protection of existing trees and improvements not to be removed.
7. Hydroseeding, seeding, mulching, plantings or other erosion control measures as required in rights-of-way, easement, or landscaped areas.
8. Asphalt or concrete pavement required beyond the limits allowed for payment described herein.
9. Removal and replacement of existing landscaping or irrigation system as required.

Payment shall be based on completion of the restoration satisfactory to the individual property owners or agency having jurisdiction over the affected property.