LAST REVISED: 01/2022 3' - 4' ADJACENT ROLLS SHALL TIGHTLY ABUT 10'-25' DEPENDENT ON SOIL TYPE AND SLOPE STEEPNESS SEDIMENT, ORGANIC MATTER, AND NATIVE SEEDS ARE CAPTURED BEHIND THE ROLLS. 8" - 10" DIA. 1"x1" STAKE LIVE STAKE

**NOTES** 

 STRAW ROLLS SHALL BE PLACED ALONG SLOPE CONTOURS.

- 2. STRAW ROLL INSTALLATION REQUIRES THE PLACEMENT AND SECURE STAKING OF THE ROLL IN A TRENCH, 3"-5" DEEP, DUG ON CONTOUR. RUNOFF MUST NOT BE ALLOWED TO RUN UNDER OR AROUND ROLL.
- 3. DRIVE STAKE THROUGH MIDDLE OF WATTLE, LEAVING 2"-3" OF STAKE PROTRUDING ABOVE WATTLE.

NOT TO SCALE

CITY OF KIRKLAND

PLAN NO. CK - E.10



STRAW WATTLES