

Special Human Services Commission Meeting

Date: February 22, 2022

Time: 6:30 p.m.

Place: Virtual Zoom Meeting - **Webinar ID:** https://kirklandwa-

gov.zoom.us/j/95665567758?pwd=eEhGaEYraThBbnlhUTdzUWVCa3c5dz09

Passcode: 862999

The commission is directed by the City Council to advise the Parks and Community Services Department, City Manager, and City Council in leading the City's efforts to support a socially sustainable community through health and human services and programs that fulfill the basic needs of all people and enhance the quality of life in our city now and into the future.

AGENDA

Estimated Time

- 1. CALL TO ORDER
- 2. ROLL CALL
- 3. LAND ACKOWLEDGMENT
- 4. APPROVAL OF MINUTES

5 minutes

- a. January 25, 2022
- 5. ITEMS FROM THE AUDIENCE

5 minutes

- 6. NEW BUSINESS
 - PROS Plan ADA Transition Plan Stakeholder Session

45 minutes

- 7. OLD BUSINESS
 - a. CDBG Recommendationsb. 2023-2024 Human Services Grant Application Process

30 minutes 20 minutes

8. COMMUNICATIONS

15 minutes

- a. Commissioner Reports
- b. Staff Reports and Announcements
- 9. ADJOURNMENT

Estimated meeting completion: 8:30 p.m.

Upcoming Commission Activities:

March 22, 2022 – Human Services Commission Meeting

Alternate Formats: Persons with disabilities may request materials in alternative formats. Persons with hearing impairments may access the Washington State Telecommunications Relay Service at 711.

Title VI: Kirkland's policy is to fully comply with Title VI of the Civil Rights Act by prohibiting discrimination against any person on the basis of race, color, national origin or sex in the provision of benefits and services resulting from its programs and activities. Any person who believes his/her Title VI protection has been violated, may file a complaint with the City.

To request an alternate format, file a complaint or for questions about Kirkland's Title VI Program, contact the Title VI Coordinator at 425-587-3011 or titlevicoordinator@kirklandwa.gov.

The City of Kirkland strives to accommodate people with disabilities. Please contact the City Clerk's Office at 425.587.3190, or for TTY Services call 425.587.3111 (by noon the work day prior to the meeting) if we can be of assistance. If you should experience difficulty hearing the proceedings, please bring this to the attention of the Chairperson by raising your hand.

CITY OF KIRKLAND HUMAN SERVICES COMMISSION Minutes Commission Meeting January 25, 2022

1. CALL TO ORDER

Meeting was called to order at 6:32 p.m.

2. ROLL CALL

Members Present: Laney Brackett, Vice Chair Jonathan Stutz, Gabriela Lopez Vazquez, Michelle Alten-Kaehler, Antonio Avila, Marjorie Carlson, Jory Hamilton, Chair Gildas Cheung

Staff Present: Antoinette Smith, Human Services Coordinator, Leslie Miller Human Services Supervisor, Jen Boone, Human Services Coordinator

Meeting Recorder: Regi Schubiger, Youth Services Coordinator

3. LAND ACKNOWLEDGEMENT

4. APPROVE MINUTES

Chair Gildas Cheung requested a motion to approve the December 21, 2021 minutes as presented. Moved by Commissioner Jory Hamlin, seconded by Comissioner Jonathan Stutz.

Motioned carried (Yes: 7 No: 0) Comissioner Marjorie Carlson abstained.

5. ITEMS FROM THE AUDIENCE

None

6. SPECIAL PRESENTATION

a. Racism is a Public Health Crisis

Matías Valenzuela, Director, Office of Equity & Community Partnerships for Public Health – Seattle & King County presented and took commission member questions regarding Racisim as a Public Health Crisis.

7. OLD BUSINESS

a. Identifying the Next Funding Priorities

Commission members reviewed the discussion notes from the December 2021 meeting regarding identifying funding priorities.

b. 2023-2024 Human Services Grant Application Calendar Discussion Comission members discussed possible meeting dates and agency presentations over the coming months.

8. Communications

a. Commissioner Reports

Chair Gildas Cheung traveled to Olympia as a part of his volunteer advocacy work with community health centers. His group shared their health related needs with State officals.

b. Staff Report None

7. ADJOURNMENT

Chair Gildas Cheung asked for a motion to adjourn. Commissioner Jory Hamilton motioned Vice Chair Jonathan Stutz seconded. The meeting was adjourned at 8:36 p.m.



CITY OF KIRKLAND Department of Parks and Community Services 123 Fifth Avenue, Kirkland, WA 98033 425.587.3300 www.kirklandwa.gov

MEMORANDUM

To: Human Services Commission

From: Lynn Zwaagstra, Director of Parks and Community Services

Mary Gardocki, Park Planning and Development Manager

Date: February 17, 2022

Subject: 2021 PARKS, RECREATION AND OPEN SPACE PLAN – ADA TRANSITION PLAN

RECOMMENDATION

That the Human Services Commission receives the draft Americans with Disabilities Act (ADA) Transition Plan and provides feedback to staff and GreenPlay LLC (now BerryDunn) and Bureau Veritas, consultants for the PROS Plan.

BACKGROUND DISCUSSION

Comprehensive Planning

The PROS Plan is a six-year guide and strategic plan for managing and enhancing park and recreation services in Kirkland. It provides a vision for Kirkland's park and recreation system and establishes a path forward for providing high-quality, community-driven parks, trails, open spaces and recreational opportunities. The PROS Plan creates a framework that will allow the City to respond to new opportunities as they arise, and to ensure that parks, facilities and recreation programs meet the needs of Kirkland's residents, employees and visitors now and into the future. A complete background was provided in August 2021 and the packet information can be found here.

ADA Transition Plan

As a critical component in the Plan, an Americans with Disabilities Act (ADA) evaluation was performed by <u>Bureau Veritas</u> using methods and procedures consistent with good commercial and customary practice for assessing compliance with the <u>Title II provisions of the ADA</u> and applicable state and local requirements. Per Department of Justice guidelines, people with disabilities should be able to arrive on the site, approach the facility and its amenities, and enter as freely as everyone else. This information informs the Transition Plan which identifies and prioritizes current barriers to participation, provides a schedule for barrier removal, as well as establishes procedures for addressing future accessibility issues. The ADA Transition Plan serves as a pragmatic application tool that will identify existing and future accessibility needs, document accessibility facility standards, and provide design criteria for future facilities development.

Accessibility assessment reports for each site surveyed include:

- Summary of findings for all primary features (parking stalls, curb ramps, paths of travel, restrooms, etc.)
- Individual barriers with digital photos
- Geocode references for the location of barriers
- Applicable ADA and state regulatory references
- Recommendations for corrective measures
- Order of priority cost estimates for each

This draft ADA Transition Plan will also be presented at the March 1 City Council meeting as well as the March 9, 2022 Park Board meeting.

NEXT STEPS:

Staff recommends that Human Services Commission provide feedback based on the following framework:

- Provide input and specific comments on the Transition Plan and priorities
- Provide the Transition Plan to local advocacy groups and partners
- Encourage local advocacy groups and partners to comment during the public comment period during March 2022

As a reminder, staff has set up the webpage <u>kirklandwa.gov/PlayItForward</u> where commissioners can direct the community for additional information as well as sign up for the <u>PROS Plan email list</u> to receive updates. There is a dedicated email, <u>playitforward@kirklandwa.gov</u> and a phone line, 425-587-3315. Commissioners are encouraged to ask community members to reach out to the PROS Plan team to provide input or feedback.

Attachment A: Draft ADA Transition Plan

ADA TITLE II TRANSITION PLAN

B U R E A U
VERITAS

prepared for

City of Kirkland Parks & Community Services 123 Fifth Avenue Kirkland, Washington 98033 Ms. Mary Gardocki



ADA TITLE II TRANSITION PLAN

OF

CITY OF KIRKLAND PARKS AND COMMUNITY SERVICES 123 FIFTH AVENUE KIRKLAND, WASHINGTON 98033

PREPARED BY:

Bureau Veritas 10461 Mill Run Circle, Suite 1100 Owings Mills, Maryland 21117 800.733.0660 www.us.bureauveritas.com

BV CONTACT:

Matthew F Anderson

Program Manager 800.733.0660 x7613 matt.anderson@bureauveritas.com

BV PROJECT #:

148970.21R000-000.303

DATE OF REPORT:

To Be Filled In By CD

ON-SITE DATE:

June 7-July 26, 2021 & November 30 – December 3, 2021

TABLE OF CONTENTS

1.	CERTIFICATION	2
2.	PURPOSE AND SCOPE	3
	2.1 Overview of the City of Kirkland	
	2.2 Purpose of the Transition Plan	6
	2.3 Basis for Probable Costs	7
	2.4 Scope of Work	7
	2.5 Physical Barrier Assessments	7
3.	ACCESSIBILITY REQUIREMENTS	9
4.	COMPLIANCE STRATEGY	
5.	PRIORITIES	11
٠.	5.1 Facility Priorities	
	5.2 Barrier Priorities	11
6.		
7.		
٠.	7.1 Overview	
	7.2 System Barrier Summary	
	7.3 Barrier Removal Strategy	19
	7.4 Conclusion	18
Q	APPENDICES	19



1. CERTIFICATION

Bureau Veritas has completed a Comprehensive Accessibility Evaluation of the City of Kirkland properties in King County, Washington, in accordance with the requirements of 28 CRF Part 35, the 2010 Americans with Disability Act (ADA) Design Standards for Accessible Design, and the State of Washington Building Code sections related to accessibility.

The conclusions and recommendations presented in this report are based on the evaluations of properties under the jurisdiction of the City of Kirkland, associated documentation related to the properties, and input from the City of Kirkland staff.

Accessibility evaluations were conducted by Bureau Veritas Project Architects and Project Engineers during site visits to individual properties. Project Architects' and Engineers' observations were made during site visits conducted between June 7- July 26, 2021 and November 30 – December 3, 2021. Cost estimates for barrier removal are planning level cost estimates based on Bureau Veritas's experience with similar properties.

The assessments were performed at the Client's request using methods and procedures consistent with good commercial and customary practice for assessing compliance with the Title II provisions of the ADA, including the requirements of 28 CRF Part 35, and applicable state requirements. Accessibility barriers in areas which were not readily accessible, and/or may not have been visible, may exist. Individual facility reports describe property conditions at the time that the observations and research were conducted. The individual facility reports are not an engineering evaluation of physical conditions. The Self-Evaluation did not include engineering evaluations or engineering calculations to determine the adequacy of the park or facility's original design or to determine engineered cost estimates.

The opinions Bureau Veritas expresses in this report were formed utilizing the degree of skill and care ordinarily exercised by any prudent architect or engineer in the same community under similar circumstances. Bureau Veritas assumes no responsibility or liability for the accuracy of the information contained in this report, which has been obtained from the Client or the Client's representatives, from other interested parties, or from the public domain. The conclusions presented represent Bureau Veritas's professional judgment based on information obtained during the course of this assignment. The conclusions presented are based on the data provided, observations made, and conditions that existed specifically on the date of the assessments of individual properties.

Bureau Veritas certifies that Bureau Veritas has no undisclosed interest in the subject property, Bureau Veritas' relationship with the Client is at arms-length, and that Bureau Veritas' employment and compensation are not contingent upon the findings or estimated costs to remedy any deficiencies.

This report has been prepared on behalf of and exclusively for the use of the City of Kirkland for the purposes stated herein. The purpose for which this report shall be used shall be limited to the use as stated in the contract between the client and Bureau Veritas.

This report, or any of the information contained therein, is not for the use or benefit of, nor may it be relied upon by any other person or entity, for any purpose without the advance written consent of Bureau Veritas. Any reuse or distribution without such consent shall be at the client's or recipient's sole risk, without liability to Bureau Veritas.

If you have any questions regarding this report, please contact Bryon Scott, Senior Engineering Consultant, (800) 766-0660 x 6625.

Certified by:	
Bryon Scott, ADAC Bryon.Scott@BureauVeritas.com	



2. PURPOSE AND SCOPE

2.1 Overview of the City of Kirkland

The mission statement of the City of Kirkland's Parks and Community Services

is:

"To support a healthy and sustainable community by providing high quality parks and recreation services, ensuring a collaborative community response to basic human needs, and protecting our natural areas."

In the process of achieving its mission, the Park Board shall:

- Be knowledgeable about existing PCS programs and facilities throughout the City;
- Review the Department's Comprehensive Park, Recreation and Open Space Plan, Capital Improvement Program and other pertinent planning documents and become familiar with them;
- Review policy related reports prepared by the staff of the PCS and provide input on them;
- Seek public input on matters relevant to the provision of recreation services, especially in areas where levels of service could be impacted;
- Assist with the acquisition and development of facilities and programs which will be required as a result of growth in the community and recommend ways and means for accommodating such demands;
- Meet on an as-needed basis with volunteer groups, neighborhood and civic organizations to determine community-wide recreation needs and assist in identifying strategic solutions; and
- · Undertake other assignments as may be requested by City Council.

The City of Kirkland encompasses:

- King County District 1
- King County District 6
- 1st, 45th, and 48th State Legislative Districts
- 1st Congressional District

The City of Kirkland is governed by the City Council and is comprised of seven nonpartisan members who are elected by the registered voters of Kirkland to serve "at large." Councilmembers are elected every two years to serve four-year terms. The Mayor and Deputy Mayor are elected among the members to serve two-year terms.

The current governing body of the City Council is comprised of the following Councilmembers:

- Mayor Penny Sweet
- Deputy Mayor Jay Arnold
- Councilmember Neal Black
- Councilmember Kelli Curtis
- Councilmember Amy Falcone
- Councilmember Toby Nixon
- Councilmember Jon Pascal



City Council Meetings

There are two types of City Council meetings, both of which are open to the public. Regular meetings are those in which the Council makes local laws, policies, and basic decisions relating to the City. Study sessions are public meetings in which the Council conducts more informal and in-depth discussions of special projects and issues of interest. No official action may be taken by the City Council at a study session.

The City of Kirkland is committed to sustaining strong relations with neighborhood associations and residents. Kirkland neighborhood associations serve as an important communications link between the City and its residents. They also provide an effective way for neighbors to improve the quality of life in Kirkland neighborhoods. There are currently 11 associations meeting on a regular basis.

Kirkland operates under the "council-manager" form of government which means all legislative and policy-making powers are vested in the City Council. Policy-making often takes the form of passing ordinances or resolutions. The Council employs a professionally trained public administrator, the City Manager, to carry out the policies it develops. In a "council-manager" form of government, the Mayor's responsibilities are primarily to preside over the Council meetings and act as head of the City for ceremonial purposes and for purposes of military law. The Mayor votes as a Councilmember and does not have any veto power.

.The City of Kirkland Parks and Community Service facilities occupies 625.8 acres.

Physical amenities currently available within the CITY OF KIRKLAND system are:

AMENITY SUMMARY							
FACILITY	AMENITIES						
132 nd Square Park	Soccer and baseball player fields, playground, restrooms, picnic shelter						
2 nd Avenue South Dock	Dock	1.1					
Brookhaven Park	Interpretive walk, picnic tables, trail	0.9					
Bud Homan	Trail	2.2					
Carillon Woods	Picnic tables, playground, restoration area, trail	8.7					
Cedar View Park	Playground, picnic tables	0.2					
Cotton Hill Park	Cotton Hill Park Interpretive walk, restoration area, trail, wildlife viewing						
Crestwood's Park	Crestwood's Park Baseball/Softball/Basketball, outdoor exercise equipment, picnic area, playground, parking lot, restoration area, trail, wildlife viewing						
David E Brink Park	Boat launch, dock, picnic tables	0.9					
Doris Cooper Houghton Beach Park	Boat launch, dock, picnic area, playground, swimming beach, volleyball, wildlife viewing	3.8					
Edith Moulton Park	Dog park, picnic area, picnic tables, playground, restoration area, restrooms, trail, wildlife viewing	26.7					
Everest Park	Baseball/softball/pickleball, picnic area, picnic tables, playground, parking lot, restoration area, restrooms, trail, wildlife viewing	23.2					
Forbes Creek Park Basketball, picnic tables, playground, tennis, trail		2					

AMENITY SUMMARY								
FACILITY	AMENITIES	ACREAGE						
Forbes Lake Park	Fishing, restoration area, wildlife viewing	8.8						
Hazen Hills Park	Restoration area	1.3						
Heritage Hall & Park	Interpretive walk, picnic tables, playground, parking lot, tennis, trail, wildlife viewing	10.1						
Heronfield Wetlands	Dog park, trail, wildlife viewing	28.1						
Highlands Park	Baseball/softball, basketball, picnic tables, playground, soccer fields	2.7						
Josten Park	Playground, restoration area	0.9						
Juanita Bay Park	Interpretive walk, picnic tables, parking lot, restoration area, restrooms, trail, wildlife viewing	110.8						
Juanita Beach Park	Baseball/softball, boat launch, fishing, interpretive walk, picnic area, picnic tables, playground, parking lot, public art, restoration area, restrooms, swimming beach, tennis, trail, volleyball	21.9						
Juanita Heights Park	Restoration area, trail, wildlife viewing	6.1						
Kingsgate Park	Restoration area, trail, wildlife viewing	6.9						
Kirkland Teen Union Building *	Parking lot, building with common areas, kitchen, restrooms, signage, drinking fountians							
Kiwanis Park	Picnic tables, restoration area, trail	2.6						
Lake Avenue W Street End Park	Boat launch	0.3						
Marina Park	Boat launch, dock, picnic area, parking lot, public art, restrooms	3.6						
Mark Twain Park								
Marsh Park	Boat launch, drinking fountain, fishing, interpretive walk, picnic tables, parking lot, public art, restrooms	4.1						
McAuliffe Park	Community garden, playground, parking lot, restoration area	11.6						
North Kirkland Community Center and Park	Basketball, drinking fountain, picnic tables, playground, parking lot, restrooms	5.5						
North Rose Hill Woodlands Park	Picnic area, picnic tables, playground, restoration area, restrooms, trail	20.9						
O. O. Denny Park	Barbecue, picnic tables, playground, fishing, bike racks, boat launch, parking lot, picnic area, restoration area, restrooms, trail, wildlife viewing							
Ohde Avenue Pea Patch	Community garden, parking lot, restrooms	0.9						
Peter Kirk Park Baseball/softball, basketball, bike racks, drinking fountain, picnic tables, playground, parking lot, public art, restrooms, skate parks, soccer fields, swimming pool, tennis								

AMENITY SUMMARY								
FACILITY	FACILITY AMENITIES							
Phyllis A. Needy Houghton Neighborhood	Picnic tables, playground, restrooms	0.5						
Reservoir Park	Bike racks, picnic tables, playground	0.6						
Rose Hill Meadows	Picnic area, picnic tables, playground, parking lot, restoration area, restrooms	4.1						
Settler's Landing	Dock, fishing	0.1						
Snyder's Corner	Wildlife viewing	4.5						
South Norway Hill Park	Mountain bike course, restoration area, trail, wildlife viewing	9.8						
South Rose Hill Park	Basketball, drinking fountain, picnic tables, playground, parking lot, restoration area, restrooms, trail, wildlife viewing	2.2						
Spinney Homestead Park	Basketball/softball, drinking fountain, picnic tables, playground, parking lot, restrooms, soccer fields	6.5						
Street End Park	Picnic tables, wildlife viewing	0.1						
Terrace Park	Basketball, picnic tables, playground, parking lot, restrooms, soccer fields	1.8						
Tot Lot & Pea Patch	Community garden, picnic tables, playground, restrooms	0.5						
Totem Lake Park	Drinking fountain, picnic tables, playground, restoration area, restrooms, trail, wildlife viewing	17.2						
Van Aalst Park	Basketball, pickle ball, picnic tables, playground	1.6						
Watershed Park	Interpretive walk, restoration area, trail, wildlife viewing	75.5						
Waverly Beach Park	Barbecue, dock, drinking fountain, fishing, picnic area, picnic tables, playground, parking lot, restoration area, restrooms, swimming beach	2.8						
Windsor Vista Park	Playground, restoration area	4.8						
Yarrow Bay Wetlands								
Total Number of Acres		625.8						

^{*}Kirkland Teen Union Building – Is leased by an agency outside of the City of Kirkland, who may have part or all the responsibility for removing the barriers to accessibility. The building is located within the Peter Kirk Park.

2.2 Purpose of the Transition Plan

The purpose of this Transition Plan is to plan accessibility compliance for the City of Kirkland with the requirements of Title II of the Americans with Disabilities Act (ADA) and applicable state regulations contained in the accessibility and related chapters of the Washington Building Code. The Transition Plan is part of the Self-Evaluation process required of Title II entities (state and local public agencies).

2.3 Basis for Probable Costs

The estimates for the repair and capital reserves items noted within this report are summarized in Section 3, and individual observation details are provided in Appendix A.

The estimates are based on invoice or bid documents provided either by the Owner/facility and construction costs developed by construction resources such as *R.S. Means* and *Marshall & Swift*, Bureau Veritas' experience with past costs for similar properties, city cost indexes, and assumptions regarding future economic conditions. Typically, barrier-removal allowances are based upon the removal of the specific element being evaluated (for example, parking stalls, curb ramps, ramps). Grading plans based on field surveys using land surveyor instrumentation could result in significantly different material quantities and subsequent higher project costs. Bureau Veritas has no control over the final scope of work, pricing methods, and costs associated with a contractor constructing the project. The opinion of probable costs within this report cannot guarantee that the costs will accurately reflect the actual bids for construction.

2.4 Scope of Work

A Self-Evaluation is a governmental organizations' evaluation of its current services, policies and practices, and all physical facilities. The Self-Evaluation comprises three components:

- Data gathering: Assessments of individual physical properties and internal reviews of public services and programs, communications, and employment practices
- Transition Plan based on the physical and programmatic assessments
- Action necessary to make required additions or modifications to non-compliant elements

This Transition Plan represents the planned modifications to programs and physical facilities provided by the City of Kirkland. The Transition Plan is a summation and analysis of the barriers to use of facilities.

2.5 Physical Barrier Assessments

A Bureau Veritas Subject Matter Expert visited each property within the City of Kirkland to evaluate the facilities in accordance with the ADA and State of Washington Building Code and assess the existing property improvements' compliance with the Title II provisions of the Americans with Disabilities Act (ADA) and applicable state requirements.

The field observer conducted a thorough review of the facility to observe and identify barriers to accessibility and formulate recommendations to remedy the physical barriers. As a part of the review, the field observer met with a property representative with specific knowledge of the facility to gain a clear understanding of overall features, public use patterns, and relevant historical data. All features of the property are subject to observation, which includes, but is not limited to: parking lots, sidewalks, access ramps, and all common areas accessible to the public, as well as employee areas.

During the site walk-through, the field observer followed a Survey Form that meets or exceeds the current Americans with Disabilities Act Accessibility Guidelines (ADAAG) format and utilized a digital level, measuring tape, pressure gauge, and digital camera. The field observer identified and prioritized any existing improvements not in accordance with the applicable ADA requirements in the order of preference as set out by the Department of Justice (DOJ) in general categories, and refined by Bureau Veritas.



The Bureau Veritas team assessed exterior and interior in order to identify existing conditions that are not in accordance with the applicable regulations. Examples of elements required to be accessible are:

- Parking: Adequacy as to automobile number, van accessible number, signage, and markings
- Parking and passenger loading zones
- Accessible routes: Sidewalks and paths, interior routes
- Space allowance and ranges
- Protruding objects
- Ground and floor surfaces
- Curb and other ramps; size, distance, slope, rails, and surface finishes
- Exterior and interior common stairs
- Platform lifts (wheelchair lifts)
- Entrances and exits to common areas and employee areas.
- Handrails and grab bars
- Alarms (visual and audible) and warnings
- Signage, Braille, and visual
- Switches and outlets

Individual assessment reports for each property surveyed included:

- Summary of Findings for all amenity features (parking stalls, curb ramps, paths of travel, etc.)
- Individually recorded barriers
- Digital photos of observed deficiencies and representative photos of elements observed to be in compliance
- Geocode GPS references for the location of observed deficiencies
- Applicable ADA and State of Washington regulatory references
- Recommendations for viable corrective measures necessary to comply with regulations
- Planning level cost estimates for each barrier

Assessment results were tabulated into an ADA database using AssetCALC™, an online interactive database created by Bureau Veritas to manage ADA and state accessibility code information. The AssetCALC™ asset management database used by Bureau Veritas establishes an online database in www.Assetcalc.net, which is used to compile records of all deficiencies and accessibility barriers, store photos, and documents related to the individual facilities, and create reports. AssetCALC™ provides the ability to list, prioritize, query, and track accessibility barrier removals. Cost data in the database is calculated using rounding. Any minor discrepancies in the costs shown in this report are the result of rounding.



3. ACCESSIBILITY REQUIREMENTS

The Americans with Disabilities Act (ADA) of 1990 provides comprehensive, wide-ranging rights and protections to individuals with disabilities in the areas of employment, public accommodations, state and local government services, and telecommunications. Many consider it one of the most important civil rights laws since the Civil Rights Act of 1964. The goal of the ADA is to help ensure equality of opportunity, full participation, and independent living to all individuals, including those with disabilities; it expressly prohibits all state and local governments and most private businesses from discriminating on the basis of disability. The ADA provides a clear and comprehensive national mandate for the elimination of discrimination against individuals with disabilities. The ADA includes the definition of a disability, and in 2008, the ADA Amendments Act expanded and better defined the definition of a disability.

The ADA defines a disability, with respect to an individual, in one of three ways: a physical or mental impairment that substantially limits one or more major life activities; a record or history of such impairment; or regarded as having such as an impairment. Major life activities include, but are not limited to, caring for oneself, performing manual tasks, seeing, hearing, eating, sleeping, walking, standing, lifting, bending, speaking, breathing, learning, reading, concentrating, thinking, communicating, and working.

The ADA is divided into five Titles: Employment, Public Services, Public Accommodations and Commercial Facilities, Telecommunications, and Miscellaneous Provisions. This report focuses on the Title II requirements.

The DOJ is responsible for the enforcement of the provisions of the ADA other than employment policy related issues. The United States Department of Justice's regulations implementing Title II of the ADA dictate that local governments and public agencies such as City of Kirkland must evaluate their services, programs, policies, and practices and identify barriers that may limit accessibility for individuals with disabilities and develop transition plans describing how they will address identified barriers.

In 2010, the Department of Justice issued revised and expanded ADA regulations. The new regulations revised and updated earlier standards as well as included new standards for various recreational uses such as play equipment, amusement rides, fishing piers, etc. These are collectively called the 2010 ADA Standards for Accessible Design (the "2010 Standards"). These new standards guide all new park construction and renovation projects. All facilities and parks have been evaluated and audited using the 2010 Standards.

Generally, Title II of the Americans with Disabilities Act (ADA) prohibits discrimination by public entities to access and use of on the basis of disability. In addition, public agencies must provide program access to all programs of the agency. Program, as used in the phrase "program access," is defined by the Department of Justice as "programs, facilities, and activities" of the public agency. Regardless of their age, programs, facilities, and activities must be maintained and operated to comply with the ADAAG, and applicable state and local accessibility regulations.

Buildings completed and occupied after January 26, 1992, are required to comply fully with ADAAG. Existing facilities constructed prior to this date are held to the lesser standard of complying to the extent allowed by structural feasibility and the financial resources available, or a reasonable accommodation must be made. However, program access by the public is still required.

A full explanation of the ADA is located in Appendix A.



4. COMPLIANCE STRATEGY

The proposed strategy for ADA compliance is a multi-phase approach for facility access as well as programmatic access. The goal of this strategy is to help ensure that the programs, services, and opportunities offered by City of Kirkland are accessible to the citizens of the Kirkland community, regardless of abilities, yet provide a realistic plan for barrier removal, which is within the fiscal capabilities of the City of Kirkland.

The provision of facility access is proposed to be based on a park level, with the initial focus on the highest use properties. As its foundation, the proposed strategy is to help ensure amenities which are in highest demand are accessible, subject to various limitations such as technically infeasible conditions and funding limitations. The strategy takes into account numerous factors such as population density, usage levels, amenity uniqueness, and other factors. This strategy will enable the best use of available funds to provide the optimal facility access to the park programs for all citizens.

Programmatic access will be an ongoing effort. The City of Kirkland will initiate efforts to improve facility access, develop, and expand its review of its many programs with a focus on policy initiatives, inclusion, and reasonable accommodation needs. Not all barriers must be removed, as long as the disabled community is accommodated, and the unique programs, facilities, and services of the City are made available for disabled users. Selected recurring amenities will be made barrier-free, so that at least one of each type of amenity is accessible.

The level of funding is expected to continue at the same level going forward. Therefore, the majority of barrier removal is not anticipated to be funded as a separate initiative, but rather as part of larger capital projects. Barrier removal must be accomplished in phases, as funding becomes available.



5. PRIORITIES

5.1 Facility Priorities

The City of Kirkland has established an accessibility priority rating for facilities using public usage criteria. Usage rates were determined by general visual observation by City of Kirkland staff.

The number of amenities, services, and programs available at a facility are primary factors affecting facility usage levels. Distance required to travel from residences, proximity to public transportation, and safety are secondary factors affecting usage.

5.2 Barrier Priorities

The scope of the individual assessments was limited to exterior site features and amenities, specifically accessible parking and exterior accessible pedestrian paths of travel to and from all amenities and features provided at each site. Elements assessed included amenities such as parking, playgrounds, and restroom interiors. Bureau Veritas prioritized each of the captured barriers based on Department of Justice (DOJ) criteria focusing on the primary scope of work. Interior spaces, such as common corridors, public restrooms, and other interior elements along the common path of travel, such as water fountains, that are the responsibility of the property owner, were included.

Per DOJ Guidelines, people with disabilities should be able to arrive on the site, approach the building or facility and its amenities, and enter as freely as everyone else.

The following priority levels have been used to assign priorities to barriers within each property and facility.

Priority 1: Path of Travel-

Accessible Van Parking – Access to a public facility begins with accessible parking. Van accessible parking is deemed the most important barrier. Those with the most severe disabilities tend to require a van accessible space to accommodate their vehicle and mobility device. In addition, when only the minimum number of accessible spaces is required, it must be a van accessible space. This priority includes all barriers associated with the compliance of a van accessible space including signage, restriping, constructing or reconfiguring the pavement to accommodate the required number of spaces.

Accessible Car Parking – Access to a public facility begins with accessible parking. Car accessible parking is deemed the second most important barrier. This priority includes all barriers associated with the compliance of a van accessible space including signage, restriping, constructing or reconfiguring the pavement to accommodate the required number of accessible spaces.

Accessible Approach and Entrances – A public agency is required to take measures to provide access to a place of public accommodation and employee areas from public sidewalks, parking, or public transportation. The DOJ dictates the minimum width, cross and running slope, signage, and handrail requirements associated with pedestrian accessible routes of travel. These measures include, for example, installing an entrance ramp, correcting tripping hazards, or lessening the slope of a curb ramp. At least one route of travel to each amenity or feature should be safe and accessible for everyone, including people with disabilities.

Priority 2: *Elements used for programs, services, and activities* – Barriers may include play equipment, picnic tables, public counters, benches, and trash receptacles.



Priority 3: *Restrooms, Signage* – Barriers may include widening of toilet stalls, installation of grab bars, and lowering lavatories and mirrors.

Priority 4: Access to Auxiliary Features and Amenities –A public agency is required to take measures to provide access to auxiliary features and amenities along paths of travel, for instance, kiosks, water fountains, and kitchen appliances.

Priority 5: *Employee-only Areas* – Employee-only areas are required to have accessible entrances and exits, and accessible paths of travel within interior work areas and work stations. Corridors in employee-only areas, employee-only restrooms, employee-only kitchens, and employee-only break rooms are considered public areas (rather than employee-only areas) under the ADA, and therefore, are required to fully comply with accessibility regulations governing those types of areas.

Employee areas have been set as the lowest priority because the total estimated cost for barrier removal in public areas is the more pressing need.

Some of the existing accessibility barriers require a minimal amount of effort or expense to remove, and are found throughout the system. These types of barrier removals are called "low hanging fruit," or easy barrier removal. "Low hanging fruit" is defined as accessibility barrier removal that can be incorporated into recurring work being completed on a life cycle basis, and which is relatively low in cost.



6. CITY OF KIRKLAND FUNDING LEVELS

The City of Kirkland has a 2021-2022 Budget of \$812,490,448.

Within the City's Budget, Parks and Community Services had a budget of \$20,895,117. This figure does not include any capital expenditures. It include \$6,742,225 for park operation and maintenance.

The City of Kirkland, in conjunction with the Parks and Community Services, will need to identify future funding sources. This may include budget line items, creating additional sources of income, or passing a bond resolution. This list is not all inclusive, nor is the list required means to develop the funds to remove barriers to accessibility.

The Transition Plan is broken into six phases, based on priority ad severity of the barriers. Each phase does not have a time frame to start or complete, the time will be based on the City's ability to fund these projects. Barriers may also be removed in conjunction with the Parks and Community Services, Play it Forward Master Plan.

As part of the annual review of the Transition Plan by the ADA Coordinator, the work may be shifted and adjusted based on changing needs within the community.



7. TRANSITION PLAN COMPONENTS

7.1 Overview

The Transition Plan is a snapshot in time to evaluate and prioritize accessibility barrier removal throughout the City of Kirkland Parks and Community Service Facilities system. The Transition Plan will be a living document and not a static view of the existing state of ADA compliance at the City of Kirkland. As such, it can be modified and updated on a periodic basis to reflect barrier removal efforts, changes in economic conditions, new and revised strategies, and future public input.

The Transition Plan is a flexible document, as strategies, priorities, and funding opportunities change. City of Kirkland demographics may vary from the current demographic composition of King County. Public preferences for recreational types may change, while funding priorities and funding levels may change as well.

The Transition Plan will require modification as conditions and priorities are changed, new ADA requirements are issued by DOJ, and/or unanticipated policy or fiscal needs shifts occur.

As the ADA Coordinator Truc Dever, for City of Kirkland, is responsible for overseeing and updating, the City of Kirkland's Transition Plan. At a minimum of at least once a year, the Transition Plan should be updated, noting the barriers removed and any changes to the funding noted. Truc Dever can be reached at 425-587-3221 and/or ADACoordinator@kirklandwa.gov.

7.2 System Barrier Summary

The removal of all identified physical accessibility barriers in the system is estimated to cost \$5.392.278. The existing barrier planning level cost estimate totals are summarized in Table 7.2 below:



- div / - d ti	Priority		Priority		Priorit		Priority		Priority 5		
Facility / Building	Est. Cost	Items			Est. Cost				Est. Cost Item		Items
132nd Square Park	\$184,370	86	\$8,413	17	\$14,720	31	\$8,000	1		\$215,503	
2nd Avenue South Dock	\$175,848	8	\$16,730	1						\$192,578	
Brookhaven Park	\$15,158		\$1,300	1			4			\$16,458	
Bud Homan Park	\$12,017	5					\$1,300	1		\$13,317	
Carillon Woods	\$15,291	6	\$6,534	4	\$282	1				\$22,106	
Cedar View Park	\$17,864	6	\$1,150	4			\$1,300	1		\$20,314	
Cotton Hill Park											(
Crestwoods Park	\$209,478	67	\$15,329	10	\$11,139	29	\$12,720	6		\$248,666	113
David E. Brink Park	\$54,724	10			\$810	2	\$8,238	2		\$63,772	2 14
Doris Cooper Houghton Beach Park	\$300,614	15	\$4,638	5	\$8,604	11				\$313,856	31
Edith Moulton Park	\$79,926	30	\$1,135	4	\$1,836	4	\$14,900	3		\$97,797	42
Everest Park	\$253,558	63	\$6,335	15	\$17,855	15	\$8,238	2		\$285,985	95
Forbes Creek Park	\$33,162	17	\$1,060	4			\$1,300	1		\$35,522	2 22
Forbes Lake Park	\$36,388	2								\$36,388	3 2
Hazen Hills Park	\$15,295	7			\$238	1				\$15,533	3 8
Heritage Hall & Park	\$299,164	33	\$6,329	8	\$3,932	14	\$500	2		\$309,925	5 57
Heronfield Wetlands									\$71,872	7 \$71,872	2 8
Highlands Park	\$22,924	7	\$8,100	6			\$16,052	3		\$47,076	5 16
Josten Park	\$30,827	16	\$24,220	4			\$1,300	1		\$56,347	2:
Juanita Bay Park	\$449,069	45	\$400	2	\$7,781	22	\$8,000	1	\$6,300	1 \$471,550	
Juanita Beach Park	\$213,404		\$1,240	6	\$14,718	8	, ,			\$229,362	_
Juanita Heights Park	\$22,251	3	7-,- 10		¥=.,.==	_				\$22,251	
Kingsgate Park	\$16,285	7	\$160	1						\$16,445	
Kirkland Teen Union Building	\$41,897	12	\$4,240	8	\$7,184	18	\$15,880	2		\$69,201	
Kiwanis Park	\$12,763		\$1,000	1	77,104	10	Ģ13,000			\$13,763	
Lake Ave W Street End Park	\$13,343	3	31,000	1						\$13,703	
Marina Park	\$68,774	25	\$4,054	2	\$3,004	7	\$8,000	1		\$83,832	
Mark Twain Park	\$182,516			11	\$3,004	- /	\$1,300	1			
			\$8,746	11	će 220	7		4		\$192,562	
Marsh Park	\$88,439	14	ĆE 020		\$8,329	7	\$16,358			\$113,126	
McAuliffe Park	\$70,461	30	\$5,939	8	\$14,771	7	\$8,000	1		\$99,171	
North Kirkland Community Center and Park	\$363,778		\$21,888	20	\$23,700	46	\$21,977	5		\$431,343	
North Rose Hill Woodlands Park	\$200,419	68	\$58,639	15	\$3,120	2	\$13,320	6		\$275,497	
O. O. Denny Park	\$76,038		\$2,925	4	\$4,056	10	\$5,440	1		\$88,459	
Ohde Avenue Pea Patch	\$18,199				\$3,000	1				\$21,199	
Peter Kirk Park	\$279,805	67	\$56,356	34	\$49,728	48	\$34,925	7		\$420,814	
Phyllis A. Needy Houghton Neighborhood	\$49,195	9	\$2,791	5	\$1,545	6	\$8,000	1		\$61,531	
Reservoir Park	\$23,291	8	\$25,659	5			\$1,300	1		\$50,250	
Rose Hill Meadows	\$79,058		\$4,315	7	\$3,211	2	\$7,500	3		\$94,084	
Settler's Landing	\$9,594	4								\$9,594	1 4
Snyders Corner											(
South Norway Hill Park	\$13,588	3								1 \$13,588	3 4
South Rose Hill Park	\$19,957	7	\$5,760	4	\$1,017	5	\$8,238	2		\$34,972	2 18
Spinney Homestead Park	\$111,325	43	\$8,230	5	\$3,108	2	\$22,538	6		\$145,201	L 50
Street End Park	\$2,400	1								\$2,400) :
Terrace Park	\$77,266	9	\$8,066	2	\$4,091	2				\$89,424	13
Tot Lot & Pea Patch	\$27,233	14	\$18,338	9	\$3,323	3	\$280	1		\$49,174	2
Totem Lake Park	\$39,109	18	\$25,093	3	\$4,396	14				\$68,598	3 35
Van Aalst Park	\$18,145			5			\$6,300	2		\$45,365	
Watershed Park			-				-				(
Waverly Beach Park	\$59,967	13	\$1,936	3	\$9,279	15	\$8,000	1		\$79,182	
Windsor Vista Park	\$21,583			4	,		,			\$23,983	
Yarrow Bay Wetlands	Ç 22,303		72,700							Ģ25,505	
Grand Total	\$4,425,762	1015	¢200.266	247	\$228,775	222	\$269,203		\$78,172	9 \$5,392,278	

NOTE: Due to rounding, the totals shown in this table and the individual tables in the Appendices differ from Table 7.2, System Barrier Summary, and the tables in the AssetCalc management database by approximately \$15.



For the accessibility summaries of individual facilities, see Appendix B.

7.3 Barrier Removal Strategy

The City of Kirkland has adopted a multi-phase strategy using the ranking criteria of facility usage levels to determine the phases for barrier removal. The long-term goal is to make all unique amenities and at least one of each type of recurring amenity accessible. In order to meet the programmatic requirement for accessibility of programs, facilities, and services to the disabled by local agencies, the District will make accommodations for the disabled when requested. For further explanation of the obligations of a public agency, see Appendix A, section 1.2.1.

The planned phases for barrier removal are:

- Phase One
 - o 132nd Square Park
 - Crestwood Park
 - o David E. Brinks Park
 - Edith Moulton Park
 - Everest Park
- Phase Two
 - Heritage Hall & Park
 - o Juanita Bay Park
 - o Juanita Beach Park
 - North Rose Hill Woodlands Park
- Phase Three
 - Brookhaven Park
 - Bud Homan Park
 - Carillon Woods
 - Cedar View Park
 - Hazen Hill Park
 - Mark Twain Park
 - North Kirkland Community Center and Park
 - Spinney Homestead Park
- Phase Four
 - Forbes Creek Park
 - Forbes Lake Park
 - Hazen Hill Park
 - McAuliffe Park
 - Peter Kirk Park
 - Kirkland Teen Union Building
 - Rose Hill Meadows
- Phase Five
 - 2nd Ave South Dock
 - Doris Cooper Houghton Beach Park
 - o Heronfield Wetlands
 - Highlands Park



- Josten Park
- o Juanita Heights Park
- Kingsgate Park
- Kiwanis Park
- Lake Ave West Street End Park
- Marina Park
- o Phyllis A. Needy Houghton Neighborhood Park

Phase Six

- o Cotton Hill Park
- Marsh Park
- o O. O. Denny Park
- o Ohide Avenue Pea Patch
- o Reservoir Park
- o Settler's Landing
- o Snyder's Corner
- South Norway Hill Park
- South Rose Hill Park
- Street End Park
- Terrace Park
- o Tot Lot and Pea Patch
- Totem Lake Park
- Van Aalst Park
- Watershed Park
- Waverly Beach Park
- Windsor Vista Park
- Yarrow Bay Wetlands

The planning level cost estimates for each phase are summarized below:

Phases	Estimated Cost	Barriers
One	\$911,728	399
Two	\$1,286,337	279
Three	\$841,304	270
Four	\$770,713	337
Five	\$892,895	159
Six	\$689,316	239
Totals	\$5,392,293	1680

See Appendix C for the full listing of barriers in each phase.



7.4 Conclusion

The establishment of planned phases for barrier removal is determined by the criteria adopted by City of Kirkland's Parks and Community Services, the regulations of the Americans with Disabilities Act, and by the necessity to schedule barrier removals within an established framework. The timing of the completion of each phase of barrier removal is subject to a number of factors. The framework timeline will be determined by the following factors, as well as potential unknown additional factors, which will determine any changes to and specificity of the Transition Plan, which may be required in future years:

- Funding sources and funding timelines
- Level of ADA barrier removal, with the highest ranking given to the highest use areas
- Opportunity to combine ADA barrier removal with scheduled capital improvements, such as playground replacements, parking lot renovations, restroom repairs or park reconstruction
- Development of a work program to eliminate "low hanging fruit" (easily removed barriers)
- Realistic time frame for accomplishment based on fiscal capability
- Demographic distributions
- Input from the community

Planning level estimated values for barrier removal will change over time due to inflation, changes in construction practices and materials, and unanticipated changes or additions to accessibility regulations. It is expected that the total cost of required accessibility barrier removal will change over time due to the completion of individual barrier removal efforts and due to funding of capital projects which incorporate barrier removal in the immediate and distant future.



8. APPENDICES

Appendix A - ADA Title II Requirements

Appendix B - Accessibility Summaries by Facility

Appendix C - Barriers by Transition Plan Phase



APPENDIX A ADA TITLE II REQUIREMENTS

The Americans with Disabilities Act

With the passage of the Americans with Disabilities Act in 1990, people with disabilities were, for the first time, assured of access to all programs and services provided by state and local government agencies. Previously, under Section 504 of the Rehabilitation Act of 1973, as amended, only those public entities that receive federal funding were explicitly prohibited from discriminating on the basis of disability. Title II of the Americans with Disabilities Act applies Title I regulations to most public entities and became effective on January 26, 1992.

The Americans with Disabilities Act is divided into five areas, Titles I through V.

<u>Title I- Employment</u>: Title I of the Americans with Disabilities Act prohibits all employers, including government agencies, from discriminatory practices in the hiring, training, advancement, compensation, or discharge of any employee, or in any terms, conditions, and rights of employment.

<u>Title II- Public Services</u>: Title II of the American Disabilities Act, which governs state and local government entities, prohibits all public entities, even those completely independent from federal funding, from discriminating against people with disabilities. Generally, Title II of the Americans with Disabilities Act (ADA) prohibits discrimination by state and local government entities to access and use of "areas of public accommodations" and "public facilities" on the basis of disability.

<u>Title III- Public Accommodations and Commercial Facilities</u>: Title <u>III requires</u> places of public accommodation (privately funded and operated facilities) and commercial facilities that serve the public to be accessible to and usable by people with disabilities.

<u>Title IV- Telecommunications</u>: Title IV covers private telecommunication carriers offering services to the public to increase the availability of interstate and intrastate telecommunication relay services to individuals with hearing and speech impairments.

<u>Title V- Miscellaneous Provisions</u>: Title V contains miscellaneous provisions, including construction standards and practices, provisions for attorneys' fees, and technical assistance provisions.

Terms such as "Public Entity" and "Governmental Agency" are applicable to Title II entities, which are defined as state and local governments.

The Department of Justice (DOJ) is tasked with enforcement of the ADA.

Scope of Title II

Title II is divided into two subtitles. This discussion focuses only on Subtitle A, which is implemented by the Department of Justice's Title II regulation at 28 CFR § Part 35. Subtitle B covers public transportation and is implemented by the Department of Transportation's regulation. Subtitle B provisions are not applicable to this report, since parks are not a mode of public transportation. The use of the term "Title II" anywhere in the Transition Plan report refers only to Subtitle A.

28 CFR §35.102 Application

(a) Except as provided in paragraph (b) of this section, this part applies to all services, programs, and activities provided or made available by public entities.



(b) To the extent that public transportation services, programs, and activities of public entities are covered by Subtitle B of Title II (42 U.S.C.12141) of the ADA, they are not subject to the requirements of this part.

The obligation to comply with Title II extends to all public entities, including:

- Any state or local government
- Any department, agency, special purpose district, or other instrumentality of a state or local government

All local agencies, including municipalities, are required to comply with Title II because they are considered "instrumentalities" of the state government. All programs, activities, and services of local government, including municipalities, must be in compliance with Title II. Examples of activities covered include:

- The operation of all services and programs offered by the entity;
- All aspects of the employment relationship; and
- Services carried out by contractors.

Title II covers any and all events the local government system offers, for example, any public meetings, entertainment or lecture series, all events offered by the school system including after-school activities and social events, festivals or other special events, and all services provided for the public or staff. Services provided by any private contractors on behalf of the municipal system must also comply fully with relevant provisions of Title II.

Under Title II, a public entity (i.e. governmental agency) shall operate each service, program, or activity so that the service, program, or activity, when viewed in its entirety, is readily accessible to and usable by individuals with disabilities. The local government may not deny the benefits of its programs, activities and services to individuals with disabilities because its facilities are inaccessible.

Public meeting rooms must be accessible to people with disabilities. Buildings where public meetings, services, programs or activities take place must provide access to telephones and restrooms, if provided, for people with disabilities as well as the general public. When a program, service or activity is scheduled in an inaccessible location and a person with a disability notifies the agency of their desire or need to participate, that program, service or activity must be moved to an accessible location.

The government must maintain equipment and features of facilities in working order, if those features and equipment are required to provide ready access to individuals with disabilities. Isolated or temporary interruptions in access due to maintenance and repair of accessible features are not prohibited. For example, where the governmental agency must provide an accessible route, the route must remain accessible and not blocked by obstacles such as furniture, filing cabinets, or potted plants. An isolated instance of placement of an object on an accessible route, however, would not be a violation if the object is promptly removed. Similarly, accessible doors must be unlocked when the governmental agency's offices are open for business.

Mechanical failures in equipment such as elevators or automatic doors will occur from time to time. The obligation to help ensure that facilities are readily accessible to and usable by individuals with disabilities would be violated if repairs are not made promptly or if improper or inadequate maintenance causes repeated failures.



However, this does not --

- (1) Necessarily require a public entity to make each of its existing facilities accessible to and usable by individuals with disabilities;
- (2) Require a public entity to take any action that would threaten or destroy the historic significance of an historic property; or
- (3) Require a public entity to take any action that it can demonstrate would result in a fundamental alteration in the nature of a service, program, or activity or in undue financial and administrative burdens. In those circumstances where personnel of the public entity believe that the proposed action would fundamentally alter the service, program, or activity or would result in undue financial and administrative burdens, a public entity has the burden of proving that compliance with 35.150(a) of this part would result in such alteration or burdens. The decision that compliance would result in such alteration or burdens must be made by the head of a public entity or his or her designee after considering all resources available for use in the funding and operation of the service, program, or activity, and must be accompanied by a written statement of the reasons for reaching that conclusion. If an action would result in such an alteration or such burdens, a public entity shall take any other action that would not result in such an alteration or such burdens but would nevertheless help ensure that individuals with disabilities receive the benefits or services provided by the public entity.

In summary, Title II requires state, county, and city governments to help ensure that all of their programs, services, and activities, when viewed in their entirety, are accessible to people with disabilities. Program access is intended to remove physical barriers to state, county, and city services, programs, and activities, but it generally does not require that a government agency make each facility, or each part of a facility, accessible. For example, all restrooms in a facility may not be accessible. However, signage directing people with disabilities to the accessible features and spaces in a facility, including at least one accessible restroom, should be provided.

Program accessibility may be achieved in a variety of ways. State, county, and city governments may choose to make structural changes to existing facilities to achieve access, or can pursue alternatives to structural changes to achieve program accessibility. For example, governments can move public meetings to accessible buildings, or can relocate services for individuals with disabilities to accessible levels or sections of buildings. When choosing between possible methods of program accessibility, governments must give priority to the choices that offer services, programs, and activities in the most integrated setting appropriate. [28 C.F.R. § 35.149, 35.150, 35.151, 35.163]

Definition of Disability

The ADA stipulates a three-pronged definition of disability. Disability is defined as an individual who:

- Has a physical or mental impairment that substantially limits one or more major life activities; or
- Has a record or history of such an impairment; or
- Is perceived or regarded as having such an impairment;
- Major life activities encompasses activities such as caring for oneself, performing manual tasks, walking, seeing, hearing, speaking, breathing, learning and working. [28 CFR § 35.104]

Human Resources

The ADA requires equal opportunity for the disabled in all areas of employment practices, including the application process, interviewing, testing, hiring, job assignment, evaluation, discipline, medical examinations, compensation, promotion, on-the-job training, layoff/recall, termination, leave and benefits such as health insurance. The nondiscrimination requirement applies to the hiring process, as well as employees.

The ADA requires that all employees be provided equal access to benefits, such as health insurance, regardless of disability. However, the regulations also indicate that certain restrictions, such as preexisting condition waiting periods or caps on particular types of services, such as out-patient physical therapy, are permissible unless proven to be a subterfuge for discrimination.

The ADA requirements for the hiring protocol and all areas of responsibility of the human resources department extend to seasonal workers, workers covered by collective bargaining agreements and works who may be hired through outside agencies. Volunteers, interns or student teachers who may be placed at an agency program or recruiters are not necessarily defined as government employees.

An important factor in the Self-Evaluation process is the identification of unionized employees and the terms of union agreements. For example, the terms of a collective bargaining agreement may include job restructuring or reassignment requests, which may affect seniority provisions. If the granting of requests would create an undue hardship, the Equal Employment Opportunity Commission (EEOC) has the authority to determine on a case-by-case basis whether the claim of undue hardship is valid.

Employment regulations treat alcohol and drug use differently. Alcoholism is recognized as a disability under the ADA; however, employers do not have to tolerate poor work performance due to alcoholism. If a person with alcoholism is provided only one paid leave for treatment of the alcoholism, while persons with different diseases are provided multiple paid leave, then such a provision is a violation of the ADA.

The ADA does not protect an individual currently engaging in the illegal use of drugs. However, a person with a history of drug addiction who (1) has been successfully rehabilitated or is participating in a drug rehabilitation program and (2) is not engaging in the illegal use of drugs is protected if the person is a qualified individual with a disability. An individual who is erroneously regarded as being a drug addict is also protected. [28 CFR § 35.104, 131]

Communications

People who have disabilities that affect hearing, seeing, speaking, reading, writing or understanding may use different ways to communicate than people who do not. Governmental agencies are required to take steps to help ensure that the agency's communications with people with disabilities are as effective as communications with others. [28 CFR § 35.160(a)(1)]

This effective communication requirement applies to all members of the public with disabilities, including job applicants, program participants, and even people who simply contact state or local government agencies seeking information about programs, services, events or activities. The requirement applies to all agencies and to all modes of communication including written, spoken, telecommunications, television and video. Specifically, where the governmental agency communicates by telephone with applicants and any other person, text phones (TTY's) or equally effective telecommunications systems are required to be used for individuals who are deaf, hard of hearing, or have speech impairments. [28 CFR § 35.161]



When the government uses an automated-attendant system, including, but not limited to, voice mail and messaging, or an interactive voice response system, for receiving and directing incoming telephone calls, that system must provide for real-time communication with individuals using auxiliary aids and services, including TTY's and all forms of FCC-approved telecommunications relay system, including Internet-based relay systems. [28 CFR § 35.161]

Under 28 CFR § 35.161, the ADA requires that all Public Safety Answering Points (PSAPs) provide direct and equal access to their services for people with disabilities who use text phones (TTYs). All basic emergency services are included in this requirement. Both primary and secondary PSAPs have the same responsibilities under the ADA. To be in compliance, every call-taking position within the PSAP must have its own TTY or TTY-compatible equipment.

Additionally, telephone emergency services, including 911 services, shall provide direct access to individuals who use telecommunication devices for the deaf (TDD's) or computer modems. [28 CFR § 35.162]

The governmental agency must provide equal access to the programs, services and activities available on the agency's website(s). This can include making websites accessible to people with disabilities, or providing an alternative format for people to access the information, programs and services available through the web. In order to aid development of a government website which is accessible, the web administrator can consult the Web Content Accessibility Guidelines, developed by the Web Content Accessibility Working Group, which is part of the World Wide Web Consortium Web Accessibility Initiative, and available at http://www.w3.org/TR/WCAG20.

When an auxiliary aid or service is requested, the Department must provide an opportunity for the requester to specify aids or services of their choice, and that choice must be given primary consideration. There are many types of auxiliary aids and services that may be used to provide effective communication for people with disabilities, but not all ways work for all people or even for people with the same type of disability. The law does not require the agency to provide every one of these aids and services, but it does require that each person who interacts with the agency receives effective communication. [28 CFR § 35.160]

Requirements for an ADA Coordinator

A Title II entity with more than 50 employees must designate an ADA Coordinator who coordinates agency efforts to comply with and carry out the responsibilities of the ADA. The coordinator provides a single point of contact for members of the public about ADA and the agency. In order to help ensure that individuals can easily identify the ADA Coordinator, the governmental agency must provide the ADA Coordinator's name, office address, and telephone number to all interested individuals [28 CFR § 35.107].

The ADA Coordinator facilitates compliance with the ADA and provides expertise regarding the American Disability Act and ADA Standards. The ADA coordinator receives and investigates complaints related to discrimination on the basis of disability.

Under 28 CFR § 35.107, a grievance procedure is required for public entities of 50 or more employees. Title II entities are required to adopt and publish grievance procedures providing for prompt and equitable resolution of complaints alleging any action that would be prohibited by 28 CFR § 35.

New Construction and Alterations



A public Title II entity may not deny the benefits of its programs, activities, and services to persons with disabilities because its existing facilities are inaccessible. Thus, it is the general availability of a program to persons with disabilities that must be evaluated, not compliance with facility standards developed for new construction and alterations.

While state and local governments may wish to measure the accessibility of their existing buildings against the scoping and technical provisions in the 2010 Standards, program accessibility may be achieved without making every existing facility - or every part of an existing building - accessible. Alternatives to building retrofit can include the temporary relocation of an activity to an accessible facility or the delivery of the service or benefit by other means. In many cases, however, permanent construction that provides physical access may be the most efficient and economical approach to program access, particularly when life cycle costs are considered.

Although physical changes are required only when there is no other feasible way to make a program accessible, public entities are nevertheless required to give priority to methods that result in the most integrated setting appropriate. The program access obligation is limited: title II entities do not have to take actions that they can demonstrate would result in a fundamental alteration in the nature of a program or that would impose undue financial or administrative burdens.

In compliance with 28 CFR §35.151 (c), if new construction and alterations to a facility were begun prior to September 15, 2010, then the facility or portion of the facility that is affected by the alteration shall comply with the 1991 standards. If new construction and alterations to a facility were begun on or after September 15, 2010, and before March 15, 2012, then either the 1991 standards or the 2010 ADA Standards for Accessible Design are applicable. For all new construction or alterations begun on or after March 15, 2012, the 2010 ADA Standards for Accessible Design if begun on or after March 15, 2012.

The DOJ definition of the commencement of construction is the establishment of a physical object, such as a foundation wall, rather than the groundbreaking first shovel and initial grading of the site.

Existing facilities (including all buildings, exterior facilities, and the on-site access to them) constructed prior to January 26, 1992, and not altered in any way since that date, are held to the lesser standard of complying, with the extent allowed by structural feasibility and the financial resources available, or when a reasonable accommodation can be made.

If the cost of providing a path of travel to an altered facility is more than 20% of the cost of the alteration to the primary function area, then the cost is disproportionate to the overall area and therefore not required. Costs that may be considered as part of the cost of providing an accessible path of travel may include: (1) the costs associated with providing an accessible entrance and an accessible route to the altered area, for example, the cost of widening doorways or installing ramps; (2) costs associated with making restrooms accessible, such as installing grab bars, enlarging toilet stalls, insulating pipes, or installing accessible faucet controls, if the restroom is not the primary function of the area (e.g. the restroom is not in a highway rest area); (3) costs associated with providing accessible telephones, such as relocating the telephone to an accessible height, installing amplification devices, or installing a text telephone (TTY); and (4) costs associated with relocating an inaccessible drinking fountain. [28 C.F.R. § 35.151(b)(4)(iii)]



When the cost of alterations necessary to make the path of travel to the altered area fully accessible is disproportionate to the cost of the overall alteration, the path shall be made accessible to the extent that it can without incurring disproportionate costs. In choosing which accessible elements to provide, priority should be given to those elements that will provide the greatest access, in the following order: (1) an accessible entrance; (2) an accessible route to the altered area; (3) at least one accessible restroom for each sex or a single unisex restroom; (4) accessible telephones; (5) accessible drinking fountains; and (6) when possible, additional accessible elements such as parking storage and alarms. [28 CFR § 35.151(b)(4)(iv)] A series of smaller alterations cannot be used to evade the requirement if the alterations are served by a single path of travel. [28 C.F.R. § 35.151(b)(4)(v)]

Safe Harbor

The 2010 ADA Standards for Accessible Design use the terms incremental change and supplemental change. Incremental changes are those elements which were requirements under the 1991 standards, but which were changed in some way under the 2010 standards. Supplemental changes are those regulations or regulatory areas which were not included in the 1991 standards, but are included in the 2010 standards.

"Safe harbor" is the term used in the 2010 ADA Standards to describe situations where the 2010 incremental changes to the ADA regulations are not required if alterations to the building or facility are not made. Specifically, "safe harbor" applies to a path of travel. "A 'path of travel' includes a continuous, unobstructed way of pedestrian passage by means of which the altered area may be approached, entered, and exited, and which connects the altered area with an exterior approach (including sidewalks, streets, and parking areas), an entrance to the facility and other parts of the facility. "[28 CFR § 35.151(b)(4)(ii)] "An accessible path of travel may consist of walks and sidewalks, curb ramps and other interior or exterior pedestrian ramps; clear floor paths through lobbies, corridors, rooms, and other improved areas; parking access aisles; elevators and lifts; or a combination of these elements. For the purposes of the section the term' path of travel' also includes the restrooms, telephones and drinking fountains serving the altered area." [28 C.F.R. § 35.151(b)(4)(ii)(B)]

Safe harbor applies only if a building or facility built after July 26, 1992 was compliant with the 1991 standards prior to the enforceable date of the 2010 regulations, which is March 15, 2012. "Safe harbor" is granted to facilities or buildings if and only if the facilities are fully in compliance with the 1991 standards prior to March 15, 2012. However, if alterations are made after March 15, 2012, the alteration of the building or facility must fully comply with the 2010 standards, and any other portions of the existing building or facility that are substantially affected by the alteration in terms of their use, must also comply with the 2010 standards. "Safe harbor" does not apply to areas of supplemental change. For instance, the 2010 standards include regulations for exercise equipment or exercise areas, play areas, recreational boating, mini-golf, swimming pools, bowling, and court sports, but those regulations are not governed by "safe harbor." Other supplemental changes not enumerated here are also not covered by "safe harbor". [28 C.F.R. § 35.151(b)(4)(ii)(c)]

For example, one of the regulated areas where "safe harbor" makes an impact is in a single occupant restroom. The 2010 ADA Standards for Accessible Design require a clear floor space next to the water closet, while the 1991 ADAAG allows the lavatory to overlap the clear space. The intent of the new provisions is to allow space for a side transfer to the water closet. The 2010 ADA Standards allow the door to swing into the bathroom as long as there is a clear floor space past the swing of the door, so that a person can enter the room, shut the door and then maneuver. The 1991 ADAAG does not allow the door swing and the clear floor space to overlap for any of the fixtures. While the 2010 standards do not allow clear space overlap in multi-stall bathrooms, overlap is allowed in single occupant bathrooms.



Undue Burden

A public entity must operate each service, program, or activity so that when viewed in its entirety, the service, program, or activity is readily accessible to and usable by individuals with disabilities. This does not necessarily require the public entity to make each of its facilities accessible to and usable by individuals with disabilities. Additionally, a public entity is not required to take any action that would threaten or destroy the historical significance of an historic property.

If the state or local government agency can demonstrate that an action would result in a fundamental alteration in the nature of a service, program, or activity or in undue financial and administrative burdens, then the decision must be made in a written statement describing the reason for the conclusion, and the decision must be made by the head of the government agency, or his or her designee after considering all resources available for use in the funding and operation of the service, program, or activity. The public entity has the burden of proof that compliance with 28 CFR § 35.151 would result in such alterations or burdens.

If an action would result in a fundamental alteration of the service, program, or activity or in undue financial and administrative burdens, the Title II entity shall take any other action to help ensure that individuals with disabilities receive the benefits or services provided by the state or local government agency.

Self-Evaluation Requirements

A Self-Evaluation is a governmental organizations' evaluation of its current services, policies and practices, and all physical facilities. The Self-Evaluation comprises three components: 1. Data gather/assessments/internal reviews, etc., 2. The Transition Plan, and 3. Action to make necessary modifications. A government entity is required to conduct a Self-Evaluation within one year of the effective date of 28 CFR § 35.105, the effective date being March 15, 2011. All governments were required to complete a Self-Evaluation of their facilities, programs, policies, and practices by January 26, 1993. The evaluation required by March 15, 2012 is required to cover any and all areas that were not covered under the previous Self-Evaluation, including any programs or facilities that were altered since the previous Self-Evaluation. If a previous self-evaluation was not conducted, then the Self-Evaluation required by March 15, 2012 must include all facilities, services, policies, and practices.

The Self-Evaluation identifies and corrects those policies and practices that are inconsistent with Title II's requirements. Self-Evaluations should consider all of a local government's programs, activities, and services, as well as the policies and practices that a governmental agency has put in place to implement its various programs and services. Remedial measures necessary to bring the programs, policies, and services into compliance with Title II should be specified -- including, but not limited to: (1) relocation of programs to accessible facilities; (2) offering programs in an alternative accessible manner; (3) structural changes to provide program access; (4) policy modifications to help ensure nondiscrimination; and (5) auxiliary aids needed to provide effective communication. [28 CFR §§ 35.105, 35.150(d)] The Self-Evaluation process identifies those policies and practices that are inconsistent with the requirements of Title II of the ADA. As part of the Self-Evaluation, the governmental agency is required to:

- A. Identify all of its programs, activities, and services.
- B. Review all the policies and practices that govern the administration of the governmental agency's programs, activities, and services.
- C. Examine each program to determine whether any physical barriers to access exist, including whether



- individuals with mobility impairments are provided access to public meetings.
- D. Review its policies and practices to determine whether any have the effect of excluding or limiting the participation of individuals with disabilities in the governmental agency's programs, activities, or services. The Self-Evaluation should provide justification for any agency policy that creates a barrier for people with disabilities that will not be modified.
- E. Review its policies to assess whether communications with persons with disabilities are as effective as its communication with others.
- F. Review its policies for responding to requests for accommodations to help ensure such requests are responded to expeditiously.
- G. Review its employment practices to assess whether they comply with other applicable nondiscrimination requirements, including Section 504 of the Rehabilitation Act and the ADA regulations issued by the Department of Justice.
- H. Review its building and construction policies to assess whether construction of each new facility or part of a facility, or alteration of existing facilities, conforms to the standards designated under the Title II regulations.
- Provide the opportunity to interested persons, including individuals with disabilities or organizations
 representing individuals with disabilities, to participate in the Self-Evaluation process by submitting
 comments.

In addition, a public entity that employs 50 or more persons shall for at least three years following completion of the Self-Evaluation maintain on file and make available for public inspection: (1) a list of the interested persons consulted; (2) a description of areas examined and any problems identified, and (3) a description of any modification made.

Transition Plan Requirements

If a state or local government that employs 50 or more persons decides to make structural changes to achieve program access, it must develop a transition plan that identifies those changes and sets a schedule for implementing them. Transition plans must be available to the public.

28 CFR §35.150 (d) Transition plan: (1) In the event that structural changes to facilities will be undertaken to achieve program accessibility, a public entity that employs 50 or more persons shall develop, within six months of the effective date of this part, a transition plan setting forth the steps necessary to complete such changes. A public entity shall provide an opportunity to interested persons, including individuals with disabilities or organizations representing individuals with disabilities, to participate in the development of the transition plan by submitting comments. A copy of the transition plan shall be made available for public inspection.

- (2) If a public entity has responsibility or authority over streets, roads, or walkways, its transition plan shall include a schedule for providing curb ramps or other sloped areas where pedestrian walks cross curbs, giving priority to walkways serving entities covered by the Act, including State and local government offices and facilities, transportation, places of public accommodation, and employers, followed by walkways serving other areas.
- (3) The plan shall, at a minimum -
- (i) Identify physical obstacles in the public entity's facilities that limit the accessibility of its programs or activities to individuals with disabilities;
- (ii) Describe in detail the methods that will be used to make the facilities accessible;



- (iii) Specify the schedule for taking the steps necessary to achieve compliance with this section and, if the time period of the transition plan is longer than one year, identify steps that will be taken during each year of the transition period; and
- (iv) Indicate the official responsible for implementation of the plan.

28 CFR §35.151(b)(4) path of travel requirements apply only to alterations undertaken solely for purposes other than to meet program accessibility requirements of 28 CFR §35.150 provides additional guidance regarding the duty to provide accessible features in the event of disproportionality of the cost to make corrections to barriers with the overall project costs. In the event of disproportionality, 28 CFR §35.151 (b) (4) Path of Travel (iv) states that when the cost of alterations necessary to make the path of travel to the altered area fully accessible is disproportionate to the cost of the overall alteration, the path of travel shall be made accessible to the extent that it can be made accessible without incurring disproportionate costs. Additional guidance supplied in relation to choosing which accessible elements to provide, priority should be given to those elements that will provide the greatest access, in the following order—

Priority 1: An accessible entrance;

Priority 2: An accessible route to the altered area;

Priority 3: At least one accessible restroom for each sex or a single unisex restroom;

Priority 4: Accessible telephones

Priority 5: Accessible drinking fountains; and

Priority 6: When possible, additional accessible elements such as parking, storage, and alarms

These priorities are provided for guidance only. The individual Title II entity can develop its own priorities to provide reasonable accommodation.



APPENDIX B ACCESSIBILITY SUMMARIES BY FACILITY

	Dui auitu (1		Duiauitus	•	Duiauitu	•	Duianitu	4 Duianitus F	Tatal	
Facility / Building	Priority 1 Est. Cost		Priority Est. Cost 1		Priority Est. Cost		Priority Est. Cost	4 Priority 5 Items Est. Cost Ite	Total ms Est. Cost	Items
132nd Square Park							200. 0000	200 200 110		
132nd Square Park	\$184,370	86	\$8,413	17	\$14,720	31	\$8,000	1	\$215,503	135
Subtotal	\$184,370	86	\$8,413	17	\$14,720	31	\$8,000	1	\$215,503	135
2nd Avenue South Dock										
2nd Avenue South Dock	\$175,848	8	\$16,730	1					\$192,578	9
Subtotal	\$175,848	8	\$16,730	1					\$192,578	9
Brookhaven Park										
Brookhaven Park	\$15,158	7	\$1,300	1					\$16,458	8
Subtotal	\$15,158	7	\$1,300	1					\$16,458	8
Bud Homan Park										
Bud Homan Park	\$12,017	5					\$1,300	1	\$13,317	6
Subtotal	\$12,017	5					\$1,300	1	\$13,317	6
Carillon Woods										
Carillon Woods	\$15,291	6	\$6,534	4	\$282	1			\$22,106	11
Subtotal	\$15,291	6	\$6,534	4	\$282	1			\$22,106	11
Cedar View Park	647.064		Ć4 450				¢4.200		620.244	44
Cedar View Park Subtotal	\$17,864 \$17,864	6 6	\$1,150 \$1,150	4 4			\$1,300 \$1,300	1	\$20,314 \$20,314	11 11
Juntotal	717,804		71,130				31,300	1	320,314	- 11
Cotton Hill Park										
Cotton Hill Park										1
Subtotal										1
Crestwoods Park	6200 470	67	645 220	40	644 420	20	642 720	6	¢2.40.666	442
Crestwoods Park Subtotal	\$209,478 \$209,478	67 67	\$15,329 \$15,329	10	\$11,139 \$11,139	29 29	\$12,720 \$12,720	6 6	\$248,666 \$248,666	113 113
	4 200,0		120,020	13	¥==,==0		¥//		4 2.0,000	
David E. Brink Park										
David E. Brink Park	\$54,724	10			\$810	2	\$8,238	2	\$63,772	14
Subtotal	\$54,724	10			\$810	2	\$8,238	2	\$63,772	14
B. S. G. C. C. H. C. H. C. B. C. B. C.										
Doris Cooper Houghton Beach Park	¢200.014	15	¢4 C20	-	¢0.004	11			¢212.0FC	21
Doris Cooper Houghton Beach Park Subtotal	\$300,614 \$300,614	15 15	\$4,638 \$4,638	5 5	\$8,604 \$8,604	11 11			\$313,856 \$313,856	31 31
	1117		. , ,		1 -7				,	
Edith Moulton Park										
Edith Moulton Park	\$79,926	30	\$1,135	4	\$1,836	4	\$14,900	3	\$97,797	42
Subtotal	\$ 79,92 6	30	\$1,135	4	\$1,836	4	\$14,900	3	\$97,797	42
Everest Bark										
Everest Park Everest Park	\$253,558	63	\$6,335	15	\$17,855	15	\$8,238	2	\$285,985	95
Subtotal	\$253,558	63	\$ 6,335	15	\$17,855 \$17,855	15	\$8,238	2	\$285,985	95
Forbes Creek Park										
Forbes Creek Park	\$33,162	17	\$1,060	4			\$1,300	1	\$35,522	22
Subtotal	\$33,162	17	\$1,060	4			\$1,300	1	\$35,522	22
Forbes Lake Park										
Forbes Lake Park	\$36,388	2							\$36,388	2
Subtotal	\$36,388	2							\$36,388	2
Hazen Hills Park	645.205	_			6220				645 500	_
Hazen Hills Park	\$15,295	7			\$238	1			\$15,533	8
Subtotal	\$15,295	7			\$238	1			\$15,533	8

Heritage Hall & Park

	Priority	1	Priorit	y 2	Priority	/ 3	Priority	4	Priorit	y 5	Total	
Facility / Building	Est. Cost						Est. Cost			•	Est. Cost	
Heritage Hall	\$185,129	18	\$4,877	5	\$2,524	11	\$500	1			\$193,030	
Heritage Park	\$114,035	15	\$1,452		\$1,408	3		1			\$116,895	
Subtotal	\$299,164	33	\$6,329	8	\$3,932	14	\$500	2			\$309,925	57
Heronfield Wetlands												
Heronfield Wetlands									\$71,872	7	\$71,872	8
Subtotal									\$71,872	7	\$71,872	8
Highlands Park Highlands Park	\$22,924	7	\$8,100	6			\$16,052	3			\$47,076	16
Subtotal	\$22,924	7	\$8,100	6			\$16,052	3			\$47,076	
Josten Park Josten Park	\$30,827	16	\$24,220	4			\$1,300	1			\$56,347	21
Subtotal	\$30,827	16	\$24,220	4			\$1,300	1			\$56,347	
Juanita Bay Park EXTERIOR	\$448,237	39			\$1,584	5	\$8,000	1	\$6,300	1	\$464,121	46
RESTROOMS	\$448,237 \$832	39 6	\$400	2	\$1,584	5 17	000,6¢	1	0,300	1	\$464,121	
Subtotal	\$449,069	45	\$400	2	\$7,781	22	\$8,000	1	\$6,300	1	\$471,550	
Juanita Beach Park Juanita Beach Park	\$213,404	46	\$1,240	6	\$14,718	8					\$229,362	60
Subtotal	\$213,404 \$213,404	46	\$1,240 \$1,240	6	\$14,718	8					\$229,362 \$229,362	
Juanita Heights Park	ć22.2F1	2									ć22 2F4	2
Juanita Heights Park Subtotal	\$22,251 \$22,251	3									\$22,251 \$22,251	
Jubiotal	J22,231	,				-					722,231	,
Kingsgate Park												
Kingsgate Park	\$16,285	7	\$160								\$16,445	
Subtotal	\$16,285	7	\$160	1							\$16,445	9
Kirkland Teen Union Building												
EXTERIOR	\$5,471	6	\$800	1							\$6,271	7
INTERIOR	\$36,426	6	\$3,440	7	\$7,184	18	\$15,880	2			\$62,930	
Subtotal	\$41,897	12	\$4,240	8	\$7,184	18	\$15,880	2			\$69,201	40
Kiwanis Park												
Kiwanis Park	\$12,763	2	\$1,000	1							\$13,763	3
Subtotal	\$12,763	2	\$1,000	1							\$13,763	
Lake Ave W Street End Park												
Lake Ave W Street End Park	\$13,343	3									\$13,343	3
Subtotal	\$13,343	3									\$13,343	
Marina Dark												
Marina Park Marina Park	\$68,774	25	\$4,054	2	\$3,004	7	\$8,000	1			\$83,832	35
Subtotal	\$68,774	25	\$4,054 \$4,054		\$3,004 \$3,004	7	\$8,000	1			\$83,832	
Mark Twain Park	4										.	
Mark Twain Park	\$182,516	45 45	\$8,746				\$1,300	1			\$192,562	
Subtotal	\$182,516	45	\$8,746	11			\$1,300	1			\$192,562	57
Marsh Park												
Marsh Park	\$88,439	14			\$8,329	7	1 1	4			\$113,126	
Subtotal	\$88,439	14			\$8,329	7	\$16,358	4			\$113,126	25
McAuliffe Park												
East Community Garden	\$42,454	24	\$1,300	1	\$14,771	7	\$8,000	1			\$66,525	33
Play Area	\$14,167	2	\$4,479	6							\$18,646	8

	Priority	1	Priority	/ 2	Priority	v 3	Priorit	v 4	Priority 5	Total	
Facility / Building	-					="		•	Est. Cost Items	Est. Cost	
West Community Garden	\$13,839	4	\$160	1						\$13,999	į
Subtotal	\$70,461	30	\$5,939	8	\$14,771	7	\$8,000	1		\$99,171	46
North Kirkland Community Center and Park											
North Kirkland Community Center	\$108,844	17	\$16,469	15	\$21,420	38	\$13,977	4		\$160,709	74
North Kirkland Park	\$254,935	30	\$5,419	5	\$2,281	8	\$8,000	1		\$270,634	
Subtotal	\$363,778	47	\$21,888	20	\$23,700	46	\$21,977			\$431,343	
North Book (Players House Book											
North Rose Hill Woodlands Park	¢200 440	60	ć=0.630	45	62.420	2	642.220	-		6275 407	0.
North Rose Hill Woodlands Park	\$200,419	68	\$58,639	15	\$3,120	2	\$13,320	6 6		\$275,497	
Subtotal	\$200,419	68	\$58,639	15	\$3,120	2	\$13,320	ь		\$275,497	9:
O. O. Denny Park											
EXTERIOR	\$74,944	19	\$2,725	3	\$387	1				\$78,057	2.
RESTROOMS	\$1,094	2	\$200	1	\$3,669	9	\$5,440	1		\$10,403	1
Subtotal	\$76,038	21	\$2,925	4	\$4,056	10	\$5,440	1		\$88,459	
Olida Avanua Da Salala											
Ohde Avenue Pea Patch	640.40-	_			40.00-					40	
Ohde Avenue Pea Patch Subtotal	\$18,199 \$18,199	3			\$3,000 \$3,000	1				\$21,199 \$21,199	
Justicial	V10,133				\$5,000					722,133	
Peter Kirk Park											
General Site	\$107,192	34			\$70	1		•		\$107,263	3
Peter Kirk Community Center	\$9,497	7	\$21,914	21	\$13,083	22	\$16,420	4		\$60,913	5
Peter Kirk Park	\$163,116	26	\$31,142	9	\$13,514	6	\$18,505	3		\$226,277	4
Restrooms			\$3,300	4	\$23,061	19				\$26,361	2
Subtotal	\$279,805	67	\$56,356	34	\$49,728	48	\$34,925	7		\$420,814	156
Phyllis A. Needy Houghton Neighborhood											
Phyllis A. Needy Houghton Neighborhood	\$49,195	9	\$2,791	5	\$1,545	6	\$8,000	1		\$61,531	2:
Subtotal	\$49,195 \$49,195	9	\$2,791	5	\$1,545 \$1,545	6	\$8,000	1		\$61,531	
Reservoir Park											
Reservoir Park	\$23,291	8	\$25,659	5			\$1,300	1		\$50,250	
Subtotal	\$23,291	8	\$25,659	5			\$1,300	1		\$50,250	14
Rose Hill Meadows											
Rose Hill Meadows	\$79,058	51	\$4,315	7	\$3,211	2	\$7,500	3		\$94,084	63
Subtotal	\$79,058	51	\$4,315	7	\$3,211	2	\$7,500	3		\$94,084	
		7									
Settler's Landing											
Settler's Landing	\$9,594	4								\$9,594	
Subtotal	\$9,594	4								\$9,594	4
Snyders Corner											
Snyders Corner											:
Subtotal											:
South Norway Hill Park	642 525	_							-	640 -0-	
South Norway Hill Park	\$13,588	3							1	\$13,588	
Subtotal	\$13,588	3							1	\$13,588	4
South Rose Hill Park											
South Rose Hill Park	\$19,957	7	\$5,760	4	\$1,017	5	\$8,238	2		\$34,972	18
Subtotal	\$19,957	7	\$5,760	4	\$1,017	5	\$8,238	2		\$34,972	
Spinney Homestead Park	****		Ac	_	Ac		400	_		A	_
Spinney Homestead Park	\$111,325	43	\$8,230	5	\$3,108	2	\$22,538	6		\$145,201	
Subtotal	\$111,325	43	\$8,230	5	\$3,108	2	\$22,538	6		\$145,201	56

	Priority	1	Priority	/ 2	Priorit	y 3	Priorit	y 4	Priority 5	Total	
Facility / Building	Est. Cost	Items	Est. Cost	Items	Est. Cost	Items	Est. Cost	Items	Est. Cost Items	Est. Cost	Item
Street End Park											
Street End Park	\$2,400	1								\$2,400	
Subtotal	\$2,400	1								\$2,400	
Terrace Park											
EXTERIOR	\$77,266	9	\$8,066	2	\$4,091	2				\$89,424	1
Subtotal	\$77,266	9	\$8,066	2	\$4,091	2				\$89,424	1
Tot Lot & Pea Patch											
Tot Lot & Pea Patch	\$27,233		\$18,338	9	\$3,323	3	\$280			\$49,174	
Subtotal	\$27,233	14	\$18,338	9	\$3,323	3	\$280	1		\$49,174	2
Totem Lake Park											
Totem Lake Park	\$39,109	18	\$25,093	3	\$4,396	14				\$68,598	3
Subtotal	\$39,109		\$25,093	3	\$4,396	14				\$68,598	
	455,265	-10	Ģ 23,033		ψ-1, 3 30					700,550	J.
Van Aalst Park											
Van Aalst Park	\$18,145	5	\$20,920	5			\$6,300	2		\$45,365	1
Subtotal	\$18,145		\$20,920	5			\$6,300			\$45,365	
Watershed Park											
Watershed Park											
Subtotal											
Waverly Beach Park											
Waverly Beach Park	\$59,967	13	\$1,936	3	\$9,279	15	\$8,000	1		\$79,182	3
Subtotal	\$59,967	13	\$1,936	3	\$9,279	15	\$8,000	1		\$79,182	3
Windsor Vista Park											
Windsor Vista Park	\$21,583		\$2,400	4						\$23,983	
Subtotal	\$21,583	7	\$2,400	4						\$23,983	1
Yarrow Bay Wetlands											
Yarrow Bay Wetlands											
Subtotal		W									
Grand Total	¢4.425.763	1015	¢200.200	247	Ć220 77F	าาา	¢200,202	C 0	679 173 0	ĆF 202 270	1.00
Grand Total	\$4,425,762	1012	\$390,366	247	\$228,775	333	\$269,203	69	\$78,172 9	\$5,392,278	108

APPENDIX C BARRIERS BY TRANSITION PLAN PHASE

				Pł	nase 1				
ld Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
240962	132nd Square Park	Exterior Access Route	Curb Ramp	1	The curb ramp landing is not level. The slope of the curb ramp landing exceeds the maximum allowable 1:48 (2.08%). WASHINGTON: A car stall, access aisle, and	Curb Ramp 1 (CR1)	ADA	304; 406.4 WA Bldg Code 51-	\$1,289 x
240963	132nd Square Park	Accessible Parking	Parking Space-Car	1	signage are not provided and the slope and/or ground surface is/are not compliant.	Parking Lot	State of Washington	50 WAC 1101; ADA 502.4, 502.5 502.6; WA Bldg	\$11,300 x
240964	132nd Square Park	Accessible Parking	Parking Space - Van	1	WASHINGTON: Compliant signage is not provided at the van space or access aisle. The parking space slope is greater than 1:50	Accessible Parking Space 1 (P1)	ADA	Code 51-50 WAC 1101.2.6	\$280 x
240965	132nd Square Park	Accessible Parking	Parking Space - Van	1	(2%). WASHINGTON: The van access aisle signage is	Accessible Parking Space 1 (P1)	ADA State of	502.4 WA Bldg Code 51-	\$6,300 x
240966	132nd Square Park	Accessible Parking	Parking Space - Van	1	not compliant or not provided.	Access Aisle Serving P1 and P2	Washington	50 WAC 1101	\$280 x
240967	132nd Square Park	Accessible Parking	Parking Space - Van	1	The access aisle slope is greater than 1:50 (2%). WASHINGTON: Compliant signage is not	Access Aisle Serving P1 and P2	ADA	502.4 502.6; WA Bldg Code 51-50 WAC	\$5,000 x
240968	132nd Square Park	Accessible Parking	Parking Space - Van	1	provided at the van space or access aisle. The parking space slope is greater than 1:50	Accessible Parking Space 2 (P2)	ADA	1101.2.6	\$280 x
240969	132nd Square Park	Accessible Parking	Parking Space - Van	1	(2%). The van stall and/or access aisle has openings in	Accessible Parking Space 2 (P2)	ADA	502.4	\$6,300 x
240970	132nd Square Park	Accessible Parking	Parking Space - Van	1	ground surfaces greater than 1/2" wide.	Accessible Parking Space 2 (P2)	ADA	302.3	\$600 x
								WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2	
240971	132nd Square Park	Exterior Access Route	Curb Ramp	1	WASHINGTON: The slope of the curb ramp run is not compliant.	Curb Ramp 1 (CR1)	State of Washington	thru 405.5; Table 405.2; 403.5.1 WA Bldg Code 51-	\$1,750 x
240972	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. Sidewalk has areas of vertical level changes in	Walkway from Curb Ramp 1 (CR1) to Stair 1 (ST1) Walkway from Curb Ramp 1 (CR1)	State of Washington	50 WAC 1101.2.1; 403.3	\$600 x
240973	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	to Stair 1 (ST1)	ADA	303	\$60 x
240974 240975	132nd Square Park 132nd Square Park	Exterior Access Route Exterior Access Route	Stairs Stairs	1 1	Handrails are not compliant or are not provided. Handrail extensions are not compliant.	Stairs 1 (ST1) Stairs 1 (ST1)	ADA ADA	505 505.1 WA Bldg Code 51-	\$3,260 x \$326 x
240977	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The curb ramp landing is not level. The slope of the curb ramp landing exceeds the maximum	Walkway from Stair 1 (ST!) to Curb Ramp 2 (CR2)	State of Washington	50 WAC 1101.2.1; 403.3	
240978	132nd Square Park	Exterior Access Route	Curb Ramp	1	allowable 1:48 (2.08%).	Curb Ramp 2 (CR2)	ADA	304; 406.4	\$1,289 x

					Pł	nase 1				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
240979		132nd Square Park	Exterior Access Route	Curb Ramp	1	WASHINGTON: The slope of the curb ramp run is not compliant.	s Curb Ramp 2 (CR2)	State of Washington	WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2 thru 405.5; Table 405.2; 403.5.1	\$1,750 x
						WASHINGTON: The curb rapp width is less than		State of	WA Bldg Code 51- 50 WAC 1101.6.6; ADA 406; 405.2	
240980		132nd Square Park	Exterior Access Route	Curb Ramp	1	WASHINGTON: The curb ramp width is less than 44".	Curb Ramp 2 (CR2)	State of Washington	thru 405.5; Table 405.2; 403.5.1 WA Bldg Code 51-	\$0 x
240981		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route has gaps in the surface	Walkway from Curb Ramp 2 (CR2) to Women's Restroom Walkway from CR2 to Women's	State of Washington	50 WAC 1101.2.1; 403.3	
240982		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide.	Restroom	ADA	302.3 WA Bldg Code 51-	\$600 x
241002		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Women's Restroom to Men's Restroom	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$1,427 x
241003		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The clear width of the exterior accessible route is less than 44".	Walkway from Women's Restroom to Men's Restroom	State of Washington	50 WAC 1101.2.1; 403.3	\$1,427 x
241022		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	The accessible route has gaps in the surface greater than 1/2" wide.	Walkway from Women's Restroom to Men's Restroom	ADA	302.3	\$72 x
					X			6	WA Bldg Code 51- 50 WAC 1101.6.6; ADA 406; 405.2	
241023		132nd Square Park	Exterior Access Route	Curb Ramp	1	WASHINGTON: The curb ramp width is less than 44".	Curb Ramp 3 (CR3)	State of Washington	thru 405.5; Table 405.2; 403.5.1	\$1,750 x
241024		132nd Square Park	Exterior Access Route	Curb Ramp	1	The curb ramp surface has vertical height changes greater than 1/4" that are not ramped.	Curb Ramp 3 (CR3)	ADA	303, 403.4	\$0 x
241026		132nd Square Park	Exterior Access Route	Protruding Object	1	Protruding objects in the 27" to 80" range above finished floor protrude more than 4" into the circulation path along the accessible route.	Prinking Fountain 1 (DF1)	ADA	307.2	\$728 x
241030		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Drinking Fountain 1 (DF1) to Baseball Diamond	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3	\$1,080 x
241031		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway to Baseball Field	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3	

					Ph	ase 1				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
						WACHINGTON: The plants of the systemics		C+-+ f	WA Bldg Code 51-	
241032		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	South Baseball Diamond	State of Washington	50 WAC 1101.2.1; 403.3	\$2,500
241032		132110 Square Fark	Exterior Access route	Exterior Accessible Route	1	Sidewalk has areas of vertical level changes in	South Baseban Diamond	wasiiiigtoii	403.3	\$2,300
241033		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	South Baseball Diamond	ADA	303	\$0 :
									WA Bldg Code 51-	
						WASHINGTON: The slopes of the exterior	Walkway from South to North	State of	50 WAC 1101.2.1;	
241035		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Baseball Diamond	Washington	403.3	\$4,550
241036		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	The accessible route has gaps in the surface greater than 1/2" wide.	Walkway from South to North Baseball Diamond	ADA	302.3	\$100
241030		13211a Square Fark	Exterior Access Noute	Exterior Accessible Route	-	greater than 1/2 wide.	Basebali Blamona	ADA	WA Bldg Code 51-	7100 /
						WASHINGTON: The slopes of the exterior		State of	50 WAC 1101.2.1;	
241037		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	North Baseball Diamond	Washington	403.3	\$3,100
									WA Bldg Code 51-	
						WASHINGTON: The clear width of the exterior		State of	50 WAC 1101.2.1;	
241039		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	accessible route is less than 44".	North Baseball Diamond	Washington	403.3	\$720
241040		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	Sidewalk has areas of vertical level changes in excess of 1/4" that are not ramped.	North Baseball Diamond	ADA	303	\$50
-41040		13211a Square Fark	Exterior Access Noute	Exterior Accessible Route	-	excess of 1/4 that are not rumped.	North Basesan Blamona	ADA	WA Bldg Code 51-	,50
						WASHINGTON: An exterior accessible route is		State of	50 WAC 1101.2.1;	
241041		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	not provided.	North Baseball Diamond	Washington	403.3	\$1,434
									WA Bldg Code 51-	
		400 10 0 1				WASHINGTON: The slopes of the exterior	Walkway from Restroom to Play	State of	50 WAC 1101.2.1;	4
241043		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Area	Washington	403.3	\$4,800
						WASHINGTON: The slopes of the exterior	Walkway from Restroom to Play	State of	WA Bldg Code 51- 50 WAC 1101.2.1;	
241044		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Area	Washington	403.3	\$960
						,		, , , , , , , , , , , , , , , , , , ,	WA Bldg Code 51-	,
						WASHINGTON: The slopes of the exterior	Walkway from Restroom to Play	State of	50 WAC 1101.2.1;	
241045		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Area	Washington	403.3	\$1,200
						The accessible route has areas of vertical level				
241046		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	changes in excess of 1/4" that are not beveled o ramped.	r Walkway from Restroom to Play Area	ADA	303	\$60
241040		132110 Square Fark	Exterior Access Route	Exterior Accessible Route	1	rampeu.	Alea	ADA	WA Bldg Code 51-	300
						WASHINGTON: The slopes of the exterior	Walkway from Restroom to Play	State of	50 WAC 1101.2.1;	
241047		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Area	Washington	403.3	\$480
									WA Bldg Code 51-	
						WASHINGTON: The slopes of the exterior	Walkway from Restroom to Target	State of	50 WAC 1101.2.1;	
241048		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Range	Washington	403.3	\$5,200
						WASHINGTON: The clear width of the exterior	Walkway from Restroom to Target	State of	WA Bldg Code 51- 50 WAC 1101.2.1;	
241049		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	accessible route is less than 44".	Range	Washington	403.3	\$0 :
					_		5 -		WA Bldg Code 51-	+ 0 .
						WASHINGTON: The slopes of the exterior	Walkway from Restroom to Target	State of	50 WAC 1101.2.1;	
241050		132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Range	Washington	403.3	\$1,600

				Ph	ase 1				
Id Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
241051	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	The accessible route has areas of vertical level changes in excess of 1/4" that are not beveled or ramped.	Walkway from Restroom to Target Range	ADA	303 WA Bldg Code 51-	\$100 x
241052	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The clear width of the exterior accessible route is less than 44". The accessible route has gaps in the surface	Target Range	State of Washington	50 WAC 1101.2.1; 403.3	\$2,509 x
241053	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide.	Target Range	ADA	302.3	\$250 x
241054	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Target Range to Play Area	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$3,200 x
241055	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The clear width of the exterior accessible route is less than 44".	Walkway from Target Range to Play Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$0 x
241056	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Target Range to Play Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$1,500 x
241057	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Target Range to Play Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$160 x
241058	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. Sidewalk has areas of vertical level changes in	Walkway to Playground	State of Washington	50 WAC 1101.2.1; 403.3	\$2,378 x
241059	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Walkway to Playground	ADA	303 WA Bldg Code 51-	\$79 x
241061	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Soccer Field	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$13,619 x
241062	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. Sidewalk has areas of vertical level changes in	Walkway from Target Range to Loop Walk Walkway from Target Range to Loop	Washington	50 WAC 1101.2.1; 403.3	\$2,400 x
241063	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Walk	ADA	303 WA Bldg Code 51-	\$60 x
241064	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	North Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$2,400 x
241065	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route does not have 80" vertical	North Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3	\$900 x
241066	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	clearance.	North Loop Walk	ADA	307.4 WA Bldg Code 51-	\$200 x
241067	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	North Loop Walk to 131 St	State of Washington	50 WAC 1101.2.1; 403.3	\$3,600 x

				Ph	ase 1				
ld Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
241068	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The clear width of the exterior accessible route is less than 44".	North Loop Walk to 131 St	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$0 x
241069	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	North Loop Walk to 131 St	State of Washington	50 WAC 1101.2.1; 403.3	\$240 x
241070	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	West Loop Walk	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3	\$1,500 x
241071	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	West Loop Walk	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3	\$1,200 x
241072	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	West Loop Walk	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3	\$2,400 x
241073	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	South Loop Walk to NE 131st St	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3	\$4,800 x
241074	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The clear width of the exterior accessible route is less than 44".	South Loop Walk to NE 131st St	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3	\$0 x
241075	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	South Loop Walk	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3	\$6,000 x
	·				WASHINGTON: The slopes of the exterior	·	State of	WA Bldg Code 51- 50 WAC 1101.2.1;	
241076	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant. WASHINGTON: The slopes of the exterior	South Loop Walk	Washington State of	403.3 WA Bldg Code 51- 50 WAC 1101.2.1;	\$1,200 x
241077	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant. The accessible route does not have 80" vertical	East Loop Walk	Washington	403.3	\$6,000 x
241078	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	clearance. WASHINGTON: The slopes of the exterior	East Loop Walk	ADA State of	307.4 WA Bldg Code 51- 50 WAC 1101.2.1;	\$200 x
241079	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant. Sidewalk has areas of vertical level changes in	Walkway to Swings	Washington	403.3	\$250 x
241080	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped. WASHINGTON: The clear width of the exterior	Walkway to Swings	ADA State of	303 WA Bldg Code 51- 50 WAC 1101.2.1;	\$99 x
241081	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	accessible route is less than 44".	Walkway to Swings	Washington	403.3 WA Bldg Code 51-	\$2,378 x
241082	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. Sidewalk has areas of vertical level changes in	Walkway to Swings	State of Washington	50 WAC 1101.2.1; 403.3	\$179 x
241083	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Walkway to Swings	ADA	303	\$0 x

				Pł	nase 1				
Id Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
241097	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Play Area	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	; \$358 x
241098	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. Sidewalk has areas of vertical level changes in	Walkway to Covered Picnic Area	State of Washington	50 WAC 1101.2.1; 403.3	\$8,960 x
241099	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Covered Picnic Area	ADA	303 WA Bldg Code 51-	\$682 x
241101	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route has gaps in the surface	Walkway from Walk Loop to 132nd Ave Walkway from Walk Loop to 132nd	State of Washington	50 WAC 1101.2.1; 403.3	\$13,440 x
241102	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide.	Ave	ADA	302.3 WA Bldg Code 51	
241103	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Walk Loop to 132nd Ave	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$1,200 x
241104	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The maneuvering clearance at the accessible	Walkway from 132nd Ave to Baseball Diamond Storage Walkway from 132nd Ave to	State of Washington	50 WAC 1101.2.1; 403.3	\$6,900 x
241105	132nd Square Park	Entrance to Building	Building Entrance-Door	1	door is not level and clear. Sidewalk has areas of vertical level changes in	Baseball Diamond Storage Walkway from 132nd Ave to	ADA	305.2; 404.2	\$1,250 x
241106	132nd Square Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped. The hardware at the accessible door (including	Baseball Diamond Storage	ADA	303	\$0 x
241107	132nd Square Park	Entrance to Building	Building Entrance - Door	1	sliding doors - both sides) requires tight grasping, pinching or twisting of the wrist to operate OR is mounted below 34" or above 48". The swinging door does not have a smooth	, Baseball Diamond Storage	ADA	309, 404.2.7	\$676 x
240988	132nd Square Park	Restroom	Restroom/Bathroom - Door	2	surface within 10" of the ground measured vertically on the push side extending the full width of the door.	Women's Restroom (RR1)	ADA	404.2.10	\$200 x
240990	132nd Square Park	Restroom	Restroom/Bathroom-Unisex	2	The slope of the floor surface is greater than 2% cross or 5% running The restroom circulation path is not free of	Women's Restroom (RR1)	ADA	403.3	\$1,500 x
240996	132nd Square Park	Restroom	Protruding Object	2	objects protruding more than 4" from wall in the space between 27" and 80" height above finish floor. The swinging door does not have a smooth surface within 10" of the ground measured	Women's Restroom (RR1)	ADA	307.2	\$200 x
241009	132nd Square Park	Restroom	Restroom/Bathroom - Door	2	vertically on the push side extending the full width of the door. The slope of the floor surface is greater than 2%	Men's Restroom (RR2)	ADA	404.2.10	\$200 x
241010	132nd Square Park	Restroom	Restroom/Bathroom - Unisex	2	cross or 5% running	Men's Restroom (RR2)	ADA	403.3	\$1,500 x

				Ph	ase 1				
ld Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
241014	132nd Square Park	Restroom	Protruding Object	2	The restroom circulation path is not free of objects protruding more than 4" from wall in the space between 27" and 80" height above finish floor. The signage does not have compliant visual and	Men's Restroom (RR2)	ADA	307.2	\$93 x
241025	132nd Square Park	Interior Access Route	Signage	2	tactile characters, with raised or indented characters or symbols. The required number of wheelchair spaces is not provided at the bleacher seating for the ball	Janitor's Room	ADA	703.2; 216.2; 703.3; 703.5	\$55 x
241034	132nd Square Park	Baseball/Softball Field	Bleacher Seating	2	field. A wheelchair space is not leveled at each team	South Baseball Diamond	ADA	221; 802.2; 802.3	\$105 x
241038	132nd Square Park	Baseball/Softball Field	Player Seating	2	bench area at the ball field. The required number of wheelchair spaces is	North Baseball Diamond	ADA	221.2.1.4; 802.1	\$105 x
241042	132nd Square Park	Baseball/Softball Field	Bleacher Seating	2	not provided at the bleacher seating for the ball field. The picnic table does not allow a clear space for favorable wheelshe is a space should be spaced to be specified.	North Baseball Diamond	ADA	221; 802.2; 802.3	\$105 x
241060	132nd Square Park	Picnic Area	Picnic Table	2	forward wheelchair approach with knee and toe clearance.	Walkway to Playground	ADA	902.2; 902.4	\$1,300 x
241085	132nd Square Park	Playground	Play Component - Swing	2	A turning space is not provided at a school-age swing.	Swings	ADA	1008.4.1	\$0 x
241086	132nd Square Park	Playground	Ground Surface-Fibar	2	The ground surface has not been inspected and maintained regularly. Clear ground space is not provided at each	Swings	ADA	1008.2	\$750 x
241090	132nd Square Park	Playground	Play Component	2	ground play component, and each elevated play component connected by a ramp.	Play Area	ADA	1008.4.2	\$0 x
241092	132nd Square Park	Playground	Transfer System	2	A transfer space is not provided at the platform.	Play Area	ADA	1008.3.1.3	\$0 x
241096	132nd Square Park	Playground	Ground Surface-Fibar	2	The ground surface has not been inspected and maintained regularly. The picnic table does not allow a clear space for	Play Area	ADA	1008.2	\$1,000 x
241100	132nd Square Park	Picnic Area	Picnic Table	2	forward wheelchair approach with knee and toe clearance. WASHINGTON: The stair treads do not have	Covered Picnic Area	ADA	902.2; 902.4	\$1,300 x
240976	132nd Square Park	Exterior Access Route	Stairs	3	visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the remaining portion of the tread surface.	Stairs 1 (ST1)	IBC	2009 ANSI A117.1 504.5.1	\$317 x
240983	132nd Square Park	Restroom	Restroom/Bathroom - Signage	3	The restroom does not have compliant signage at the door with the International Symbol of Accessibility, raised characters, and Braille.	Women's Restroom (RR1)	ADA	216.2, 703.1, 703.2, 703.5, 703.6	\$55 x
240985	132nd Square Park	Restroom	Restroom/Bathroom - Door	3	The push side of the door does not have the required maneuvering clearances.	Women's Restroom (RR1)	ADA	404.2.4	\$1,250 x
240986	132nd Square Park	Restroom	Restroom/Bathroom - Door	3	The threshold at the accessible door is greater than ½" in height.	Women's Restroom (RR1)	ADA	404.2.5	\$179 x

				Ph	ase 1				
ld Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
					The accessible door with door closer has a sweep period of less than 5 seconds from 90				
240987	132nd Square Park	Restroom	Restroom/Bathroom - Door	3	degrees to a position 12 degrees from latch. The pull side of the accessible door does not	Women's Restroom (RR1)	ADA	404.2.8 404.2; Table	\$366 x
240989	132nd Square Park	Restroom	Restroom/Bathroom - Door	3	have the required maneuvering clearances. The hardware at the accessible door requires	Women's Restroom (RR1)	ADA	404.2.4.1	\$1,250 x
240991	132nd Square Park	Restroom	Restroom/Bathroom - Door	3	tight grasping, pinching or twisting of the wrist to operate	Women's Restroom (RR1)	ADA	309, 404.2.7	\$293 x
240992	132nd Square Park	Restroom	Restroom/Bathroom - Lavatory Restroom/Bathroom -	3	The lavatory is mounted higher than 34" to the higher of the rim or counter.	Women's Restroom (RR1)	ADA	606.2 and 606.3	\$720 x
240993	132nd Square Park	Restroom	Lavatory Restroom/Bathroom -	3	Pipes are not insulated. The automatic faucet, when activated, does not	Women's Restroom (RR1)	ADA	606.5	\$65 x
240994	132nd Square Park	Restroom	Lavatory Restroom/Bathroom -	3	remain on for minimum 10 seconds.	Women's Restroom (RR1)	ADA	606.4	\$555 x
240995	132nd Square Park	Restroom	Lavatory	3	The lavatory faucet hardware is not compliant.	Women's Restroom (RR1)	ADA	606.4; 309	\$0 x
240997	132nd Square Park	Restroom	Restroom/Bathroom - Water Closet Restroom/Bathroom - Water	3	The water closet in a single user / unisex restroom does not have the required clearance. The rear grab bar at the water closet is not	Women's Restroom (RR1)	ADA	604	\$1,368 x
240998	132nd Square Park	Restroom	Closet	3	compliant.	Women's Restroom (RR1)	ADA	604.5.2 ADA 604.7, 609.3	\$355 x
241000	132nd Square Park	Restroom	Restroom/Bathroom - Water Closet	3	WASHINGTON: The toilet paper dispenser location is not compliant.	Women's Restroom (RR1)	State of Washington	2009 ANSI A117.1 604.7	 \$293 x
241001	132nd Square Park	Restroom	Restroom/Bathroom - Water Closet	3	The height of the water closet is not 17" minimum to 19" maximum above finished floor.	Women's Restroom (RR1)	ADA	604.4	\$630 x
			Restroom/Bathroom -		The restroom does not have compliant signage at the door with the International Symbol of			216.2, 703.1,	
241004	132nd Square Park	Restroom	Signage	3	Accessibility, raised characters, and Braille.	Men's Restroom (RR2)	ADA	703.2, 703.5, 703.6	\$55 x
			Restroom/Bathroom -		The provided signage is not mounted at the			216.2,703.1,	
241005	132nd Square Park	Restroom	Signage	3	latch side of the door or at a compliant height. The threshold at the accessible door is greater	Men's Restroom (RR2)	ADA	703.2, 703.5	\$55 x
241006	132nd Square Park	Restroom	Restroom/Bathroom - Door	3	than ½" in height. The accessible door with door closer has a	Men's Restroom (RR2)	ADA	404.2.5	\$179 x
241007	132nd Square Park	Restroom	Restroom/Bathroom - Door	3	sweep period of less than 5 seconds from 90 degrees to a position 12 degrees from latch. The pull side of the accessible door does not	Men's Restroom (RR2)	ADA	404.2.8 404.2; Table	\$366 x
241008	132nd Square Park	Restroom	Restroom/Bathroom - Door Restroom/Bathroom -	3	have the required maneuvering clearances.	Men's Restroom (RR2)	ADA	404.2.4.1	\$1,250 x
241011	132nd Square Park	Restroom	Lavatory Restroom/Bathroom -	3	Pipes are not insulated.	Men's Restroom (RR2)	ADA	606.5	\$65 x
241012	132nd Square Park	Restroom	Lavatory	3	The lavatory faucet hardware is not compliant.	Men's Restroom (RR2)	ADA	606.4; 309	\$555 x

					Ph	ase 1				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
244042		122md Courses Doub	Destruction	Restroom/Bathroom -		The automatic faucet, when activated, does not	Marala Dastria and (DD2)	404	COC 4	ć 0
241013 241015		132nd Square Park 132nd Square Park	Restroom Restroom	Lavatory Controls And Dispensers	3 3	remain on for minimum 10 seconds. The height of controls are not compliant.	Men's Restroom (RR2) Men's Restroom (RR2)	ADA ADA	606.4 606.1; 309.3	\$0 x \$200 x
		•				·	, ,		,	
241016		132nd Square Park	Restroom	Restroom/Bathroom - Water Closet	3	The water closet in a single user / unisex restroom does not have the required clearance.	Men's Restroom (RR2)	ADA	604	\$1,368 x
						·	,			
241017		132nd Square Park	Restroom	Restroom/Bathroom-Water Closet	3	The grab bars at the water closet are not compliant.	Men's Restroom (RR2)	IBC	2009 ANSI A117.1- 604.5.2, 609	\$710 x
2.101,		152.11d 5quare 1 a.m.		Restroom/Bathroom - Water	J	The flush control is located on the closed side		.50	005.2, 003	ψ/10 A
241018		132nd Square Park	Restroom	Closet	3	and/or is not within reach range.	Men's Restroom (RR2)	ADA	604.6 ADA 604.7, 609.3;	\$313 x
				Restroom/Bathroom - Water		WASHINGTON: The toilet paper dispenser		State of	2009 ANSI A117.1-	
241019		132nd Square Park	Restroom	Closet	3	location is not compliant.	Men's Restroom (RR2)	Washington	604.7	\$293 x
				Restroom/Bathroom - Water		The height of the water closet is not 17"				
241020		132nd Square Park	Restroom	Closet	3	minimum to 19" maximum above finished floor. The centerline of the wheelchair accessible	Men's Restroom (RR2)	ADA	604.4	\$630 x
				Restroom/Bathroom - Water		toilet is not 16" minimum to 18" maximum from			2009 ANSI A117.1-	-
241021		132nd Square Park	Restroom	Closet	3	the side wall.	Men's Restroom (RR2)	IBC	604.2	\$630 x
									2009 ANSI A117.1	-
		122 15 5 1		Restroom/Bathroom-Toilet		WASHINGTON: A vertical side grab bar is not) (DD4)	ANG! A447.4	604.5.1 and	6255
241448		132nd Square Park	Restroom	Stall Drinking Fountain/Water	3	present in the wheelchair stall. The minimum number and types of drinking	Women's Restroom (RR1)	ANSI A117.1	A117.1-604.9.6	\$355 x
241027		132nd Square Park	Site Furnishings	Cooler	4	fountains are not provided.	Drinking Fountain 1 (DF1)	ADA	211.2; 602; 309	\$8,000 x
242998		Crestwoods Park	Amenity Not Evaluated	Amenity Not Evaluated	0	The amenity is not regulated by the ADA. Accessible parking spaces are not at the nearest	Trail	ADA	None	\$0 x
242980		Crestwoods Park	Accessible Parking	Parking Spaces-General	1	accessible entrance.	Parking Lot	ADA	208.3	\$420 x
						WASHINGTON: A van stall, access aisle, and signage are not provided and the slope and/or		State of	WA Bldg Code 51- 50 WAC 1101;	
242981		Crestwoods Park	Accessible Parking	Parking Space - Van	1	ground surface is/are not compliant.	Van Accessible Parking Space 1 (P1)		ADA 502.4, 502.5	\$11,300 x
						WASHINGTON: A car stall, access aisle, and signage are not provided and the slope and/or		State of	WA Bldg Code 51- 50 WAC 1101;	
242982		Crestwoods Park	Accessible Parking	Parking Space - Car	1	ground surface is/are not compliant.	Accessible Parking Space 2 (P2)	Washington	ADA 502.4, 502.5	\$11,300 x
									WA Bldg Code 51-	
									50 WAC 1101.6;	
						WASHINGTON, The clane of the gurb remarking is		Ctata of	ADA 406; 405.2	
242983		Crestwoods Park	Exterior Access Route	Curb Ramp	1	WASHINGTON: The slope of the curb ramp run is not compliant.	Curb Ramp 1 (CR1)	State of Washington	thru 405.5; Table 405.2; 403.5.1	\$1,750 x
						The curb ramp surface has vertical height				
242984		Crestwoods Park	Exterior Access Route	Curb Ramp	1	changes greater than 1/4" that are not ramped.	Curb Ramp 1 (CR1)	ADA	303, 403.4	\$0 x

					Ph	ase 1				
Id Fac	cility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
242985		Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. WASHINGTON: A car stall, access aisle, and	Path of travel from P1 and P2 to the park walkway	Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$800 x
242986		Crestwoods Park	Accessible Parking	Parking Space - Car	1	signage are not provided and the slope and/or ground surface is/are not compliant. WASHINGTON: A car stall, access aisle, and	Accessible Parking Space 3 (P3)	State of Washington	50 WAC 1101; ADA 502.4, 502.5 WA Bldg Code 51-	\$11,300 x
242987		Crestwoods Park	Accessible Parking	Parking Space - Car	1	signage are not provided and the slope and/or ground surface is/are not compliant. WASHINGTON: A car stall, access aisle, and	Accessible Parking Space 4 (P4)	State of Washington	50 WAC 1101; ADA 502.4, 502.5 WA Bldg Code 51-	\$11,300 x
242988		Crestwoods Park	Accessible Parking	Parking Space - Car	1	signage are not provided and the slope and/or ground surface is/are not compliant.	Accessible Parking Space 5 (P5)	State of Washington	50 WAC 1101; ADA 502.4, 502.5 304; 406.4; US	\$0 x
242989		Crestwoods Park	Exterior Access Route	Curb Ramp	1	The slope of the path of travel at the top of the curb ramp exceeds the maximum allowable 1:20 (5%).	Curb Ramp 2 (CR2)	ADA	Access Board Chap 4 Guide for Ramps and Curb Ramps WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2	\$1,289 x
242990		Crestwoods Park	Exterior Access Route	Curb Ramp	1	WASHINGTON: The slope of the curb ramp run is not compliant.	Curb Ramp 2 (CR2)	State of Washington	thru 405.5; Table 405.2; 403.5.1	\$1,750 x
242991		Crestwoods Park	Exterior Access Route	Curb Ramp	1	The curb ramp surface has vertical height changes greater than 1/4" that are not ramped.	Curb Ramp 2 (CR2)	ADA	303, 403.4 WA Bldg Code 51-	\$0 x
242992		Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. Sidewalk has areas of vertical level changes in	Walkway from P1 and P2	State of Washington	50 WAC 1101.2.1; 403.3	\$1,200 x
242993		Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Walkway from 6th St	ADA	303 WA Bldg Code 51-	\$79 x
242994		Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from 6th St	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$555 x
242996		Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route does not have 80" vertical	Walkway from CR3	State of Washington	50 WAC 1101.2.1; 403.3	\$714 x
242997		Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	clearance.	Walkway from CR3	ADA	307.4 WA Bldg Code 51-	\$250 x
243001		Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route has gaps in the surface	Walkway from 6th St to Restrooms	State of Washington	50 WAC 1101.2.1; 403.3	\$14,500 x
243002		Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide.	Walkway from 6th St to Restrooms	ADA	302.3	\$800 x

				Ph	nase 1				
ld Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243004	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. Alcoves are not 36" wide minimum where the depth exceeds 24" with forward approach, or	Walkway from Bleachers to Men's Restroom	State of Washington	WA Bldg Code 51: 50 WAC 1101.2.1; 403.3	
243014	Crestwoods Park	Restroom	Restroom/Bathroom - Urinal	1	60" wide minimum with parallel approach and depth exceeding 15".	Men's Restroom 1 (RR1)	ADA	305.7.1 & 305.7.2	
243024	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Men's Restroom to Women's Restroom	State of Washington	WA Bldg Code 51: 50 WAC 1101.2.1; 403.3	
243031	Crestwoods Park	Exterior Access Route	Protruding Object	1	Protruding objects in the 27" to 80" range above finished floor protrude more than 4" into the circulation path along the accessible route.	e Drinking Fountain 1 (DF1)	ADA	307.2 WA Bldg Code 51	\$1,728 x
243046	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway to Baseball Field #1 Team Seating 1	Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$2,378 x
243047	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. Sidewalk has areas of vertical level changes in	Walkway to Baseball Field #1 Team Seating 1 Walkway to Baseball Field #1 Team	Washington	50 WAC 1101.2.1; 403.3	\$358 x
243048	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped. The accessible route has gaps in the surface	Seating 1 Walkway to Baseball Field #1	ADA	303	\$99 x
243049	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide.	Bleacher	ADA	302.3 WA Bldg Code 51	\$54 x
243052	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route has gaps in the surface	Walkway between Baseball Fields #2/3 Walkway between Baseball Fields	State of Washington	50 WAC 1101.2.1; 403.3	
243053	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide.	#2/3	ADA	302.3 WA Bldg Code 51	\$800 x
243054	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. Sidewalk has areas of vertical level changes in	Walkway to Baseball Field #1 Team Seating 2 Walkway to Baseball Field #1 Team	Washington	50 WAC 1101.2.1; 403.3	\$717 x
243055	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Seating 2	ADA	303 WA Bldg Code 51	\$45 x
243056	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. The accessible route has gaps in the surface	Walkway to Baseball Field #2 Team Seating 2 Walkway to Baseball Field #2	State of Washington	50 WAC 1101.2.1; 403.3	\$717 x
243057	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide.	Bleacher	ADA	302.3 WA Bldg Code 51	\$54 x
243058	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway to Baseball Field #2 Team Seating 2	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$8,500 x
243059	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway to Baseball Field 2 Team Seating 2	State of Washington	50 WAC 1101.2.1; 403.3	\$1,200 x

				Ph	ase 1				
ld Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243060	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	Sidewalk has areas of vertical level changes in excess of 1/4" that are not ramped.	Walkway to Baseball Field 2 Team Seating 2	ADA	303 WA Bldg Code 51-	\$0 x
243061	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Walkway to Baseball Field 2 Team Seating 2	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$358 x
243062	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route does not have 80" vertical	Walkway from Baseball Field #2 to CR4 Walkway from Baseball Field #2 to	State of Washington	50 WAC 1101.2.1; 403.3	\$16,000 x
243063	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	clearance.	CR4	ADA	307.4 304; 406.4; US	\$250 x
243064	Crestwoods Park	Exterior Access Route	Curb Ramp	1	The slope of the path of travel at the top of the curb ramp exceeds the maximum allowable 1:20 (5%).	Curb Ramp 4 (CR4)	ADA	Access Board Chap 4 Guide for Ramps and Curb Ramps WA Bldg Code 51- 50 WAC 1101.6;	\$1,289 x
243065	Crestwoods Park	Exterior Access Route	Curb Ramp	1	WASHINGTON: The slope of the curb ramp run is not compliant.	; Curb Ramp 4 (CR4)	State of Washington	ADA 406; 405.2 thru 405.5; Table 405.2; 403.5.1	\$1,750 x
243066	Crestwoods Park	Exterior Access Route	Curb Ramp	1	The curb ramp surface has vertical height changes greater than 1/4" that are not ramped.	Curb Ramp 4 (CR4)	ADA	303, 403.4 WA Bldg Code 51-	\$1,750 x
243067	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. Sidewalk has areas of vertical level changes in	Walkway from CR4 to Basketball Courts Walkway from CR4 to Basketball	State of Washington	50 WAC 1101.2.1; 403.3	\$1,000 x
243068	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Courts	ADA	303 WA Bldg Code 51-	\$0 x
243069	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from CR4 to Basketball Courts	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$13,000 x
243070	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The sidewalk does not have 80" vertical	Walkway from CR4 to Basketball Courts Walkway from CR4 to Basketball	State of Washington	50 WAC 1101.2.1; 403.3	
243071	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	clearance.	Courts	ADA	307.4	\$1,599 x
243073	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Basketball Courts to Baseball Field #3	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$2,400 x
243074	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route has gaps in the surface	Walkway from Basketball Courts to Baseball Field #3 Walkway from Basketball Courts to	State of Washington	50 WAC 1101.2.1; 403.3	\$320 x
243075	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide.	Baseball Field #3	ADA	302.3	\$800 x

				Ph	ase 1				
Id Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243077	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	Sidewalk has areas of vertical level changes in excess of 1/4" that are not ramped. Sidewalk has areas of vertical level changes in	Walkway at Baseball Field #3	ADA	303	\$297 x
243078	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Walkway at Baseball Field #3	ADA	303	\$119 x
243079	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	The accessible route has gaps in the surface greater than 1/2" wide.	Walkway at Baseball Field #3	ADA	302.3 WA Bldg Code 51-	\$36 x
243081	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from CR4 to Playground Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$21,802 x
243082	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway between Picnic Area and Soccer Field	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$5,000 x
243083	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway between Picnic Area and Soccer Field	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$4,500 x
243084	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Picnic Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$1,434 x
243086	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. Sidewalk has areas of vertical level changes in	Walkway to Playground Area	State of Washington	50 WAC 1101.2.1; 403.3	\$240 x
243087	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Walkway to Playground Area	ADA	303 WA Bldg Code 51-	\$40 x
243097	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Play Area to Fitness Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$4,800 x
243098	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Sixth St to Fitness Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$800 x
243099	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. Clear floor space is not provided at the transfer	Fitness Area	State of Washington	50 WAC 1101.2.1; 403.3	\$10,000 x
243100	Crestwoods Park	Fitness Course	Exercise Equipment	1	point to the exercise equipment. Clear floor space is not provided at the transfer	Fitness Area	ADA	1004.1	\$0 x
243101	Crestwoods Park	Fitness Course	Exercise Equipment	1	point to the exercise equipment.	Fitness Area	ADA	1004.1 WA Bldg Code 51-	\$0 x
243103	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Practice Baseball Field	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$2,688 x
243104	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route does not have 80" vertical	Walkway from Fitness Area to Trail	State of Washington	50 WAC 1101.2.1; 403.3	\$11,000 x
243105	Crestwoods Park	Exterior Access Route	Exterior Accessible Route	1	clearance. The slope of the floor surface is greater than	Walkway from Fitness Area to Trail	ADA	307.4	\$250 x
243009	Crestwoods Park	Restroom	Restroom/Bathroom - Unisex	2		Men's Restroom 1 (RR1)	ADA	403.3	\$1,613 x

				Ph	nase 1				
ld Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
					The restroom circulation path is not free of objects protruding more than 4" from wall in the space between 27" and 80" height above finish	,			
243011	Crestwoods Park	Restroom	Protruding Object	2	floor. The slope of the floor surface is greater than	Men's Restroom 1 (RR1)	ADA	307.2	\$700 x
243035	Crestwoods Park	Restroom	Restroom/Bathroom - Unisex	2	1:48 (2.08%). The restroom circulation path is not free of	Women's Restroom 2 (RR2)	ADA	403.3	\$1,613 x
					objects protruding more than 4" from wall in the space between 27" and 80" height above finish				
243037	Crestwoods Park	Restroom	Protruding Object	2	floor. The required number of wheelchair spaces is	Women's Restroom 2 (RR2)	ADA	307.2	\$700 x
243051	Crestwoods Park	Baseball/Softball Field	Bleacher Seating	2	not provided at the bleacher seating for the ball field.	Baseball Field #2	ADA	221; 802.2; 802.	3 \$105 x
243072	Crestwoods Park	Basketball Court	Player Seating	2	A wheelchair space is not provided at the player seating for the basketball courts.	Basketball Court	ADA	221.2.1.4; 802.1	\$52 x
					The lawn seating and exterior overflow seating				
243080	Crestwoods Park	Soccer Field	Exterior Accessible Route	2	areas, where fixed seating is not provided, do not connect to an accessible route.	Soccer Field	ADA	221.5	\$3,146 x
243091	Crestwoods Park	Playground	Ground Surface-Fibar	2	The ground surface has not been inspected and maintained regularly.	Playground Area	ADA	1008.2	\$2,000 x
242006	Crestwoods Park	Playground	Dlay Component	2	The entry points to a play component requiring transfer to entry points or seats is lower than 11' and higher than 24".	п	ADA	1008.4.4	\$400 x
243096	Crestwoods Park	Playground	Play Component	2	Operable parts or items requiring an unobstructed side reach motion are higher than	Playground Area	ADA	1008.4.4	\$400 X
243102	Crestwoods Park	Exterior Access Route	Reach Range	2	48" maximum and/or lower than 15" minimum height above finish floor.	Fitness Area	ADA	308, 309	\$5,000 x
243102	Crestwoods rank	Exterior Access Noute	Neach Kange		WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Titless Area	ADA	308, 303	,3,000 X
243003	Crestwoods Park	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface.	Stair 1 (ST1)	IBC	2009 ANSI A117. 504.5.1	1- \$176 x
243005	Crestwoods Park	Restroom	Restroom/Bathroom - Door	3	The pull side of the accessible door does not have the required maneuvering clearances.	Men's Restroom 1 (RR1)	ADA	404.2; Table 404.2.4.1	\$1,250 x
2.5555	0.000.000000000000000000000000000000000				The accessible door with door closer has a sweep period of less than 5 seconds from 90		7.57.		Ψ 2,23 0 X
243006	Crestwoods Park	Restroom	Restroom/Bathroom - Door	3	degrees to a position 12 degrees from latch. The threshold at the accessible door is greater	Men's Restroom 1 (RR1)	ADA	404.2.8	\$366 x
243007	Crestwoods Park	Restroom	Restroom/Bathroom - Door	3	than ½" in height. The push side of the door does not have the	Men's Restroom 1 (RR1)	ADA	404.2.5	\$179 x
243008	Crestwoods Park	Restroom	Restroom/Bathroom - Door Restroom/Bathroom -	3	required maneuvering clearances.	Men's Restroom 1 (RR1)	ADA	404.2.4	\$100 x
243010	Crestwoods Park	Restroom	Lavatory Restroom/Bathroom-Coat	3	Pipes are not insulated. The coat hook is not within an allowable reach	Men's Restroom 1 (RR1)	ADA	606.5	\$65 x
243012	Crestwoods Park	Restroom	Hook	3	range.	Men's Restroom 1 (RR1)	ADA	308	\$115 x

					Ph	ase 1				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243013		Crestwoods Park	Locker and Dressing Rooms	Locker and Dressing Rooms	3	The locker room does not have a compliant bench.	Men's Restroom 1 (RR1)	ADA	903	\$789 x
243015		Crestwoods Park	Restroom	Restroom/Bathroom - Urinal	3	The urinal dimensions are not compliant. The flush control is more than 48" high, for an obstructed forward reach range of maximum 20"	Men's Restroom 1 (RR1)	ADA	605.2	\$935 x
243016		Crestwoods Park	Restroom	Restroom/Bathroom - Urinal	3	horizontally.	Men's Restroom 1 (RR1)	ADA	605.4; 309	\$313 x
243017		Crestwoods Park	Restroom	Restroom/Bathroom - Door	3	The wheelchair stall door is not self closing. The hardware at the wheelchair stall door is not	Men's Restroom 1 (RR1)	ADA	604.8.1.2 309, 404.2.7,	\$293 x
243018		Crestwoods Park	Restroom	Restroom/Bathroom - Door Restroom/Bathroom - Toilet	3	compliant. The rear grab bar in the wheelchair stall is not	Men's Restroom 1 (RR1)	ADA	604.8.1.2	\$293 x
243020		Crestwoods Park	Restroom	Stall Restroom/Bathroom - Toilet	3	compliant. The side grab bar is not compliant in the	Men's Restroom 1 (RR1)	ADA	604.5.1; 604.8.1.5	5 \$355 x
243021		Crestwoods Park	Restroom	Stall	3	wheelchair stall.	Men's Restroom 1 (RR1)	ADA	604.5.1; 604.8.1.5	5 \$355 x
243022		Crestwoods Park	Restroom	Restroom/Bathroom - Toilet Stall	3	WASHINGTON: A vertical side grab bar is not present in the wheelchair stall. The centerline of the toilet in the wheelchair	Men's Restroom 1 (RR1)	ANSI A117.1	2009 ANSI A117.1 604.5.1 and A117.1-604.9.6	 \$355 х
243023		Crestwoods Park	Restroom	Restroom/Bathroom - Water Closet	3	stall is not 16" minimum to 18" maximum from the sidewall.	Men's Restroom 1 (RR1)	ADA	604.2	\$630 x
243025		Crestwoods Park	Restroom	Restroom/Bathroom-Signage	3	The restroom does not have compliant signage at the door with the International Symbol of Accessibility, raised characters, and Braille.	Women's Restroom 2 (RR2)	ADA	216.2, 703.1, 703.2, 703.5, 703.6	\$55 x
243026		Crestwoods Park	Restroom	Restroom/Bathroom - Door	3	The pull side of the accessible door does not have the required maneuvering clearance slope. The accessible door with door closer has a sweep period of less than 5 seconds from 90	Women's Restroom 2 (RR2)	ADA	404.2; Table 404.2.4.1	\$1,250 x
243032		Crestwoods Park	Restroom	Restroom/Bathroom - Door	3	degrees to a position 12 degrees from latch. The threshold at the accessible door is greater	Women's Restroom 2 (RR2)	ADA	404.2.8	\$366 x
243033		Crestwoods Park	Restroom	Restroom/Bathroom - Door	3	than ½" in height. The push side of the door does not have the	Women's Restroom 2 (RR2)	ADA	404.2.5	\$179 x
243034		Crestwoods Park	Restroom	Restroom/Bathroom - Door Restroom/Bathroom -	3	required maneuvering clearances.	Women's Restroom 2 (RR2)	ADA	404.2.4	\$100 x
243036		Crestwoods Park	Restroom	Lavatory Restroom/Bathroom-Coat	3	Pipes are not insulated. The coat hook is not within an allowable reach	Women's Restroom 2 (RR2)	ADA	606.5	\$65 x
243038		Crestwoods Park	Restroom	Hook	3	range. The locker room does not have a compliant	Women's Restroom 2 (RR2)	ADA	308	\$115 x
243039		Crestwoods Park	Locker and Dressing Rooms	Locker and Dressing Rooms	3	bench.	Women's Restroom 2 (RR2)	ADA	903	\$789 x
243040		Crestwoods Park	Restroom	Restroom/Bathroom - Door	3	The wheelchair stall door is not self closing. The hardware at the wheelchair stall door is not	Women's Restroom 2 (RR2)	ADA	604.8.1.2 309, 404.2.7,	\$293 x
243041		Crestwoods Park	Restroom	Restroom/Bathroom - Door Restroom/Bathroom - Toilet	3	compliant. The rear grab bar in the wheelchair stall is not	Women's Restroom 2 (RR2)	ADA	604.8.1.2	\$293 x
243043		Crestwoods Park	Restroom	Stall	3	compliant.	Women's Restroom 2 (RR2)	ADA	604.5.1; 604.8.1.5	5 \$355 x

					Ph	ase 1				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243044		Crestwoods Park	Restroom	Restroom/Bathroom - Toilet Stall	3	The side grab bar is not compliant in the wheelchair stall.	Women's Restroom 2 (RR2)	ADA	604.5.1; 604.8.1.5	\$355 x
				Restroom/Bathroom - Toilet		WASHINGTON: A vertical side grab bar is not			2009 ANSI A117.1- 604.5.1 and	
243045		Crestwoods Park	Restroom	Stall Drinking Fountain/Water	3	present in the wheelchair stall. The minimum number and types of drinking	Women's Restroom 2 (RR2)	ANSI A117.1	A117.1-604.9.6	\$355 x
243027		Crestwoods Park	Site Furnishings	Cooler Drinking Fountain/Water	4	fountains are not provided. The spout height is higher than 36" at the	Drinking Fountain 1 (DF1)	ADA	211.2; 602; 309	\$8,000 x
243028		Crestwoods Park	Site Furnishings	Cooler Drinking Fountain/Water	4	lower/wheelchair level drinking fountain. The spout and/or water flow of the lower level	Drinking Fountain 1 (DF1)	ADA	602.4	\$2,000 x
243029		Crestwoods Park	Site Furnishings	Cooler	4	drinking fountain is not compliant. A clear space is not positioned at the lower level	Drinking Fountain 1 (DF1)	ADA	602.2, 602.5	\$0 x
243030		Crestwoods Park	Site Furnishings	Drinking Fountain/Water Cooler	4	drinking fountain for a forward approach is not leveled.	Drinking Fountain 1 (DF1)	ADA	602.2	\$120 x
243085		Crestwoods Park	Picnic Area	Picnic Table	4	A compliant picnic table is not provided.	Picnic Area	ADA	902	\$1,300 x
243092		Crestwoods Park	Picnic Area	Picnic Table	4	A compliant pi <mark>cnic table i</mark> s not provided.	Picnic Table at Playground	ADA	902 WA Bldg Code 51-	\$1,300 x
						WASHINGTON: The slopes of the exterior		State of	50 WAC 1101.2.1;	4
239270		David E. Brink Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Walkway W1	Washington	403.3	\$1,268 x
239272		David E. Brink Park	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided.	Stair ST1	ADA	505	\$0 x
239273		David E. Brink Park	Exterior Access Route	Stairs	1	Handrail extensions are not compliant.	Stair ST1	ADA	505.1 WA Bldg Code 51-	\$978 x
239274		David E. Brink Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway W2	State of Washington	50 WAC 1101.2.1; 403.3	\$714 x
						WASHINGTON: The slopes of the exterior	,	State of	WA Bldg Code 51- 50 WAC 1101.2.1;	
239275		David E. Brink Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Walkway W2	Washington	403.3	\$3,568 x
						WASHINGTON: The slopes of the exterior		State of	WA Bldg Code 51- 50 WAC 1101.2.1;	
239276		David E. Brink Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Walkway W3	Washington	403.3 WA Bldg Code 51-	\$39,640 x
						WASHINGTON: The slopes of the exterior		State of	50 WAC 1101.2.1;	
239277		David E. Brink Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Walkway W4	Washington	403.3	\$2,478 x
239279		David E. Brink Park	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided.	Stair ST2	ADA	505 WA Bldg Code 51-	\$4,890 x
						WASHINGTON: The slopes of the exterior		State of	50 WAC 1101.2.1;	
239280		David E. Brink Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant. Sidewalk has areas of vertical level changes in	Stair ST2	Washington	403.3	\$991 x
239281		David E. Brink Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Walkway W3	ADA	303	\$198 x
						WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the			2009 ANSI A117.1-	
239271		David E. Brink Park	Exterior Access Route	Stairs	3	remaining portion of the tread surface.	Stair ST1	IBC	504.5.1	\$493 x

				Ph	nase 1				
Id Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
				·	WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the			2009 ANSI A117.1	
239278	David E. Brink Park	Exterior Access Route	Stairs Drinking Fountain/Water	3	remaining portion of the tread surface. The minimum number and types of drinking	Stair ST2	IBC	504.5.1	\$317 x
239269	David E. Brink Park	Exterior Access Route	Cooler	4	fountains are not provided. A clear space is not positioned at the lower level	Drinking Fountain DF1	ADA	211.2; 602; 309	\$8,000 x
240081	David E. Brink Park	Site Furnishings	Drinking Fountain/Water Cooler	4	drinking fountain for a forward approach and centered on the unit.	Drinking Fountain DF1	ADA	602.2	\$238 x
240688	Edith Moulton Park	Amenity Not Evaluated	Amenity Not Evaluated	0	The amenity is not regulated by the ADA.	Trails, Stairs 1 (ST1)	ADA	None WA Bldg Code 51	\$0 x
240649	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Northwest Entrance Walkway	State of Washington	50 WAC 1101.2.1; 403.3	
240651	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	The accessible route has gaps in the surface greater than 1/2" wide.	Northwest Entrance Walkway	ADA	302.3 WA Bldg Code 51	\$375 x
240661	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	East Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	; \$4,500 x
240662	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	North Covered Picnic Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	; \$1,120 x
240664	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	East Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	; \$720 x
240665	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	East Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	; \$360 x
240666	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	East Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	; \$360 x
240667	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	East Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	; \$1,800 x
240668	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	East Covered Picnic Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	; \$1,200 x
240670	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	East Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3	; \$480 x
240671	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	East Loop Walk	State of Washington	WA Bldg Code 51 50 WAC 1101.2.1; 403.3	; \$2,000 x
240672	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	South Loop Walk	State of Washington	WA Bldg Code 51 50 WAC 1101.2.1; 403.3	

				Ph	nase 1				
ld Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
240673	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	The accessible route does not have 80" vertical clearance.	West Loop Walk	ADA	307.4 WA Bldg Code 51-	\$200 x
240674	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	West Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3	\$1,200 x
240675	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway at Play Area	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3	\$250 x
240679	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	West Loop Walk	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3	\$7,200 x
240680	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Southwest Entrance Walkway	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3	\$1,350 x
240681	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Southwest Entrance Walkway	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3	
240690	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	Signage indicating the accessible route to the amenity is not provided.	Walkway from 108th Ave NE to Dog Park	ADA	216.6 WA Bldg Code 51-	\$280 x
240691	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from 108th Ave NE to Dog Park	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$1,200 x
240693	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Walkway from 108th Ave NE to Dog Park	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$120 x
240694	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from 108th Ave NE to Dog Park	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$800 x
240695	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route has areas of vertical level	Walkway from 108th Ave NE to Dog Park	State of Washington	50 WAC 1101.2.1; 403.3	
240696	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	changes in excess of 1/4" that are not beveled or ramped. Signage indicating the accessible route to the	Walkway from public right-of-way to Dog Park Walkway from public right-of-way	ADA	303	\$0 x
240697	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	amenity is not provided. The accessible route does not have 80" vertical	to Dog Park Walkway from public right-of-way	ADA	216.6	\$280 x
240698	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	clearance.	to Dog Park	ADA	307.4 WA Bldg Code 51-	\$200 x
240699	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from public right-of-way to Dog Park	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$2,500 x
240700	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. Signage indicating the accessible route to the	Walkway from public right-of-way to Dog Park Walkway from public right-of-way	State of Washington	50 WAC 1101.2.1; 403.3	
240701	Edith Moulton Park	Exterior Access Route	Exterior Accessible Route	1	amenity is not provided.	to Dog Park	ADA	216.6	\$280 x

					Ph	ase 1				
Id Fac	acility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
240703		Edith Moulton Park	Entrance to Building	Building Entrance - Door	1	The maneuvering clearance at the accessible door is not level and clear. The swinging door does not have a smooth surface within 10" of the ground measured	Dog Park	ADA	305.2; 404.2	\$0 x
240656		Edith Moulton Park	Restroom	Restroom/Bathroom - Door Trash Receptacle Without	2	vertically on the push side extending the full width of the door. A trash receptacle is not located on an	Unisex Restroom (RR1)	ADA	404.2.10	\$200 x
240669		Edith Moulton Park	Site Furnishings	Operable Lid	2	accessible route and within reach range. The ground surface has not been inspected and	East Covered Picnic Area	ADA	228.1, 308	\$115 x
240676		Edith Moulton Park	Playground	Ground Surface-Fibar	2	maintained regularly. The gate does not have a smooth surface within	Play Area	ADA	1008.2	\$500 x
240702		Edith Moulton Park	Exterior Access Route	Gate	2	10" of the ground. The accessible door with door closer has a sweep period of less than 5 seconds from 90	Dog Park	ADA	404.2.10	\$320 x
240655		Edith Moulton Park	Restroom	Restroom/Bathroom - Door	3	degrees to a position 12 degrees from latch. The push side of the door does not have the	Unisex Restroom (RR1)	ADA	404.2.8	\$366 x
240657		Edith Moulton Park	Restroom	Restroom/Bathroom-Door Restroom/Bathroom -	3	required maneuvering clearances. The lavatory is mounted higher than 34" to the	Unisex Restroom (RR1)	ADA	404.2.4	\$100 x
240658		Edith Moulton Park	Restroom	Lavatory	3	higher of the rim or counter. The space between the grab bar and projecting	Unisex Restroom (RR1)	ADA	606.2 and 606.3	\$720 x
240660		Edith Moulton Park	Restroom	Restroom/Bathroom-Water Closet	3	objects below and at the ends of the bar is less than 1-1/2". A clear space is not positioned at the lower level	Unisex Restroom (RR1)	ADA	609.3	\$650 x
240652		Edith Moulton Park	Site Furnishings	Drinking Fountain/Water Cooler Drinking Fountain/Water	4	drinking fountain for a forward approach and centered on the unit. The spout and/or water flow of the lower level	Drinking Fountain 1 (DF1)	ADA	602.2	\$5,600 x
240653		Edith Moulton Park	Site Furnishings	Cooler	4	drinking fountain is not compliant.	Drinking Fountain 1 (DF1)	ADA	602.2, 602.5	\$8,000 x
240663		Edith Moulton Park	Picnic Area	Picnic Table	4	A compliant picnic table is not provided. WASHINGTON: A van stall, access aisle, and	North Covered Picnic Area	ADA	902 WA Bldg Code 51-	\$1,300 x
240766		Everest Park	Accessible Parking	Parking Space - Van	1	signage are not provided and the slope and/or ground surface is/are not compliant. The slope of the parking space is greater than	Parking Lot 1	State of Washington	50 WAC 1101; ADA 502.4, 502.5	\$11,300 x
240767		Everest Park	Accessible Parking	Parking Space - Car	1	1:50 (2%).	Parking Stall 1 (P1)	ADA	502.4	\$6,300 x
240768		Everest Park	Accessible Parking	Parking Space - Car	1	The access aisle slope is greater than 1:50 (2%).	Parking Stall 1 (P1)	ADA	502.4	\$5,000 x
240769		Everest Park	Accessible Parking	Parking Space - Car	1	The access aisle is less than 60" wide. WASHINGTON: Signage is not located at the required height for the standard accessible space	Parking Stall 1 (P1)	ADA	502.3.1 502.6; WA Bldg Code 51-50 WAC	\$0 x
240770		Everest Park	Accessible Parking	Parking Space - Car	1	or access aisle. The slope of the parking space is greater than	Parking Stall 1 (P1)	ADA	1101.2.6	\$280 x
240771		Everest Park	Accessible Parking	Parking Space - Car	1	1:50 (2%).	Parking Stall 2 (P2)	ADA	502.4	\$6,300 x
240772		Everest Park	Accessible Parking	Parking Space - Car	1	The access aisle slope is greater than 1:50 (2%).	Parking Stall 2 (P2)	ADA	502.4	\$5,000 x
240773		Everest Park	Accessible Parking	Parking Space - Car	1	The access aisle is less than 60" wide. WASHINGTON: The car access aisle signage is	Parking Stall 2 (P2)	ADA State of	502.3.1 WA Bldg Code 51-	\$0 x
240774		Everest Park	Accessible Parking	Parking Space - Car	1	not compliant or not provided.	Parking Stall 2 (P2)	Washington	50 WAC 1101	\$280 x

				Pł	nase 1				
ld Facility	Building	Assembly	Туре	Barrier Priority		Location Description	ADA	Ref. Number	Total
240775	Everest Park	Accessible Parking	Parking Space - Car	1	WASHINGTON: Compliant signage is not provided at the standard space or access aisle. WASHINGTON: The car access aisle signage is	Parking Stall 2 (P2)	ADA State of	502.6; WA Bldg Code 51-50 WAC 1101.2.6 WA Bldg Code 51	\$280 x
240776	Everest Park	Accessible Parking	Parking Space - Car	1	not compliant or not provided.	Parking Stall 1 (P1)	Washington	50 WAC 1101	\$280 x
240777	Everest Park	Accessible Parking	Parking Space - Car	1	The slope of the parking space is greater than 1:50 (2%). WASHINGTON: Signage is not located at the required height for the standard accessible space	Parking Stall 3 (P3)	ADA	502.4 502.6; WA Bldg Code 51-50 WAC	\$6,300 x
240778	Everest Park	Accessible Parking	Parking Space - Car	1	or access aisle.	Parking Stall 3 (P3)	ADA	1101.2.6	\$280 x
240779	Everest Park	Accessible Parking	Parking Space - Car	1	The access aisle slope is greater than 1:50 (2%). WASHINGTON: The car access aisle signage is	Parking Stall 4 (P4)	ADA State of	502.4 WA Bldg Code 51	\$5,000 x
240780	Everest Park	Accessible Parking	Parking Space - Car	1	not compliant or not provided. The slope of the parking space is greater than	Parking Stall 4 (P4)	Washington	50 WAC 1101	\$280 x
240781	Everest Park	Accessible Parking	Parking Space - Car	1	1:50 (2%). WASHINGTON: Signage is not located at the required height for the standard accessible space	Parking Stall 4 (P4)	ADA	502.4 502.6; WA Bldg Code 51-50 WAC	\$6,300 x
240782	Everest Park	Accessible Parking	Parking Space - Car	1	or access aisle. Sidewalk has areas of vertical level changes in	Parking Stall 4 (P4) Men's & Women's Restroom (MRR	ADA	1101.2.6	\$280 x
240784	Everest Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped. The accessible route has gaps in the surface	& WRR) Men's & Women's Restroom (MRR	ADA	303	\$357 x
240791	Everest Park	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide.	& WRR)	ADA	302.3 WA Bldg Code 51	\$1,229 x
240793	Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Men's & Women's Restroom (MRR & WRR)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$6,184 x
240796	Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 1 (W1)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$3,369 x
240707	Fugurest Dayle	Futorior Access Doute	Futorior Associale Poute		WASHINGTON: An exterior accessible route is	Diamia Area 1 (DA1)	State of	50 WAC 1101.2.1;	
240797	Everest Park	Exterior Access Route	Exterior Accessible Route	1	not provided.	Picnic Area 1 (PA1)	Washington	403.3 WA Bldg Code 51	
240798	Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Picnic Area 2 (PA2)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$573 x
240799	Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Ball Field 1 (BF1)	State of Washington	50 WAC 1101.2.1; 403.3	\$2,294 x
240804	Everest Park	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided.	Stair 2 (ST2)	ADA	505 WA Bldg Code 51	\$5,542 x
240806	Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Ball Field 1 (BF1)	State of Washington	50 WAC 1101.2.1; 403.3	\$2,330 x
240808	Everest Park	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided.	. Ball Field 1 (BF1)	ADA	505	\$7,824 x

				Ph	ase 1				
Id Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
240810	Everest Park	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided.	Stair 3 (ST3)	ADA	505 WA Bldg Code 51-	\$7,824 x
240811	Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route has gaps in the surface	Walkway 2 (W2)	State of Washington	50 WAC 1101.2.1; 403.3	\$6,048 x
240813	Everest Park	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide.	Ball Field 2 (BF2)	ADA	302.3	\$375 x
240815	Everest Park	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided.	Ball Field 2 (BF2)	ADA	505 WA Bldg Code 51-	\$7,824 x
240816	Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Ball Field 2 (BF2)	State of Washington	50 WAC 1101.2.1; 403.3	\$2,330 x
240824	Everest Park	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided.	Ball Field 3 (BF3)	ADA	505 WA Bldg Code 51-	\$7,824 x
240825	Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Ball Field 3 (BF3)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$2,330 x
240828	Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Ball Field 4 (BF4)	State of Washington	50 WAC 1101.2.1; 403.3	\$2,330 x
240830	Everest Park	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided.	Ball Field 4 (BF4)	ADA	505 WA Bldg Code 51-	\$7,824 x
240833	Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 3 (W3)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$22,440 x
240834	Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Playground 1 (PG1)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$143 x
240838	Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Playground 2 (PG2)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$1,168 x
240841	Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Shelter 1 (S1)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$177 x
240842	Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Picnic Area 3 (PA3)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$649 x
240843	Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Ball Field 2 (BF2)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$1,080 x
240844	Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Batting Cage (BC)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$779 x
240846	Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 4 (W4)	State of Washington	50 WAC 1101.2.1; 403.3	\$2,700 x

					Ph	ase 1				
Id F	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
240847		Everest Park	Accessible Parking	Parking Space - Van	1	WASHINGTON: A van stall, access aisle, and signage are not provided and the slope and/or ground surface is/are not compliant. The slope of the parking space is greater than	Parking Lot 2	State of Washington	WA Bldg Code 51- 50 WAC 1101; ADA 502.4, 502.5	\$11,300 x
240848		Everest Park	Accessible Parking	Parking Space - Car	1	1:50 (2%). WASHINGTON: Signage is not located at the required height for the standard accessible space	Parking Stall 5 (P5)	ADA	502.4 502.6; WA Bldg Code 51-50 WAC	\$6,300 x
240849		Everest Park	Accessible Parking	Parking Space - Car	1	or access aisle.	Parking Stall 5 (P5)	ADA	1101.2.6	\$280 x
240850		Everest Park	Accessible Parking	Parking Space - Car	1	The access aisle is less than 60" wide.	Parking Stall 5 & 6 Access Aisle	ADA	502.3.1	\$0 x
240851		Everest Park	Accessible Parking	Parking Space - Car	1	The access aisle slope is greater than 1:50 (2%). WASHINGTON: The car access aisle signage is	Parking Stall 5 & 6 Access Aisle	ADA State of	502.4 WA Bldg Code 51-	\$5,000 x
240852		Everest Park	Accessible Parking	Parking Space - Car	1	not compliant or not provided. The slope of the parking space is greater than	Parking Stall 5 & 6 Access Aisle	Washington	50 WAC 1101	\$280 x
240853		Everest Park	Accessible Parking	Parking Space - Car	1	1:50 (2%). WASHINGTON: Signage is not located at the required height for the standard accessible space	Parking Stall 6 (P6)	ADA	502.4 502.6; WA Bldg Code 51-50 WAC	\$6,300 x
240854		Everest Park	Accessible Parking	Parking Space - Car	1	or access aisle.	Parking Stall 6 (P6)	ADA	1101.2.6 WA Bldg Code 51-	\$280 x
240855		Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 5 (W5)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$18,600 x
240856		Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 6 (W6)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$5,200 x
240857		Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 7 (W7)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$1,200 x
240858		Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 8 (W8)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$2,000 x
240859		Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. Sidewalk has areas of vertical level changes in	Walkway 9 (W9)	State of Washington	50 WAC 1101.2.1; 403.3	\$5,150 x
240860		Everest Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Walkway 9 (W9)	ADA	303	\$30 x
240861		Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The gate maneuvering clearance area is not	Walkway 9 (W9)	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3 404; 404.2.3,	\$8,800 x
240862		Everest Park	Exterior Access Route	Gate	1	compliant.	Pickleball Court	ADA	404.2.4	\$568 x
240864		Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Picnic Area 4 (PA4)	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$649 x
241205		Everest Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 10 (W10)	State of Washington	50 WAC 1101.2.1; 403.3	\$13,100 x

				Ph	ase 1				
Id Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
241446	Everest Park	Accessible Parking	Parking Space-Car	1	WASHINGTON: A car stall, access aisle, and signage are not provided and the slope and/or ground surface is/are not compliant. The restroom circulation path is not free of objects protruding more than 4" from wall in the	Parking Lot 2	State of Washington	WA Bldg Code 51- 50 WAC 1101; ADA 502.4, 502.5	\$11,300 x
240787	Everest Park	Restroom	Protruding Object	2	space between 27" and 80" height above finish floor. The required number of wheelchair spaces is not provided at the bleacher seating for the ball	Men's & Women's Restroom (MRR & WRR)	ADA	307.2	\$186 x
240801	Everest Park	Common Areas	Assembly Area	2	field. The gate does not have a smooth surface within	Ball Field 1 (BF1)	ADA	221; 802.2; 802.3	\$105 x
240805	Everest Park	Exterior Access Route	Gate	2	10" of the ground. A wheelchair space is not provided at each team	Ball Field 1 (BF1)	ADA	404.2.10	\$320 x
240817	Everest Park	Baseball/Softball Field	Player Seating	2	bench area at the ball field. The gate does not have a smooth surface within	Ball Field 2 (BF2)	ADA	221.2.1.4; 802.1	\$105 x
240818	Everest Park	Exterior Access Route	Gate	2	10" of the ground. The required number of wheelchair spaces is not provided at the bleacher seating for the ball	Ball Field 2 (BF2)	ADA	404.2.10	\$320 x
240819	Everest Park	Common Areas	Assembly Area	2	field. The required number of wheelchair spaces is	Ball Field 2 (BF2)	ADA	221; 802.2; 802.3	\$210 x
240821	Everest Park	Common Areas	Assembly Area	2	not provided at the bleacher seating for the ball field. The required number of wheelchair spaces is	Ball Field 3 (BF3)	ADA	221; 802.2; 802.3	\$210 x
240827	Everest Park	Common Areas	Assembly Area	2	not provided at the bleacher seating for the ball field. The wheelchair space is not the minimum	Ball Field 4 (BF4)	ADA	221; 802.2; 802.3	\$210 x
240831	Everest Park	Baseball/Softball Field	Player Seating	2	required dimensions at the team seating for the baseball/softball field. The gate does not have a smooth surface within	Ball Field 4 (BF4)	ADA	221.2.1.4; 802.1	\$476 x
240832	Everest Park	Exterior Access Route	Gate	2	10" of the ground. The ground surface has not been inspected and	Ball Field 4 (BF4)	ADA	404.2.10	\$320 x
240837	Everest Park	Playground	Ground Surface - Fibar	2	maintained regularly. The ground surface has not been inspected and	Playground 1 (PG1)	ADA	1008.2	\$1,680 x
240839	Everest Park	Playground	Ground Surface - Fibar	2	maintained regularly. The play table does not provide knee clearance 24" high minimum, 17" deep minimum, and 30" wide minimum, and/or the tops of rims, curbs, or other obstructions at the play table are higher	Playground 2 (PG2)	ADA	1008.2	\$612 x
240840	Everest Park	Playground	Play Component - Play Table	2	than 31". The gate does not have a smooth surface within	Shelter 1 (S1)	ADA	1008.4.3	\$1,103 x
240845	Everest Park	Exterior Access Route	Gate	2	10" of the ground. The gate does not have a smooth surface within	Ball Field 3 (BF3)	ADA	404.2.10	\$320 x
240863	Everest Park	Exterior Access Route	Gate	2	10" of the ground.	Pickleball Court	ADA	404.2.10	\$160 x
240783	Everest Park	Restroom	Restroom/Bathroom - Signage	3	The provided signage is not mounted at the latch side of the door or at a compliant height.	Men's & Women's Restroom (MRR & WRR)	ADA	216.2,703.1, 703.2, 703.5	\$110 x

				Ph	nase 1				
ld Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
240785	Everest Park	Restroom	Restroom/Bathroom - Door	3	The door has less than 32" clear width. The threshold at the accessible door is greater	Men's & Women's Restroom (MRR & WRR) Men's & Women's Restroom (MRR	ADA	404.2.3	\$2,248 x
240786	Everest Park	Restroom	Restroom/Bathroom - Door Restroom/Bathroom -	3	than ½" in height.	& WRR) Men's & Women's Restroom (MRR	ADA	404.2.5	\$358 x
240788	Everest Park	Restroom	Lavatory Restroom/Bathroom -	3	Pipes are not insulated. The lavatory does not have the required clear	& WRR)	ADA	606.5	\$130 x
240789	Everest Park	Restroom	Lavatory	3	floor space of minimum 30" by minimum 48".	Men's Restroom (MRR)	ADA	606.2; 305 309, 404.2.7, 604.5.1, 604.6, 604.7, 604.8.1.1, 604.8.1.2,	\$3,000 x
			Restroom/Bathroom - Toilet		A wheelchair stall is not provided in a multi-user	·		604.8.1.5, 604.9,	
240790	Everest Park	Restroom	Stall	3	restroom.	& WRR)	ADA	609.3	\$5,500 x
			Restroom/Bathroom -		The lavatory is mounted higher than 34" to the	Men's & Women's Restroom (MRR			4
240792	Everest Park	Restroom	Lavatory	3	higher of the rim or counter. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	& WRR)	ADA	606.2 and 606.3	\$1,440 x
240802	Everest Park	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Stair 1 (ST1)	IBC	2009 ANSI A117.3 504.5.1	1- \$1,267 x
240803	Everest Park	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have	Stair 2 (ST2)	IBC	2009 ANSI A117.: 504.5.1	1- \$458 x
240807	Everest Park	Exterior Access Route	Stairs	3	visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have	Ball Field 1 (BF1)	IBC	2009 ANSI A117.: 504.5.1	1- \$563 x
240809	Everest Park	Exterior Access Route	Stairs	3	visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have	Stair 3 (ST3)	IBC	2009 ANSI A117.: 504.5.1	1- \$458 x
240814	Everest Park	Exterior Access Route	Stairs	3	visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have	Ball Field 2 (BF2)	IBC	2009 ANSI A117.: 504.5.1	1- \$563 x
240823	Everest Park	Exterior Access Route	Stairs	3	visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Ball Field 3 (BF3)	IBC	2009 ANSI A117.: 504.5.1	1- \$563 x
240829	Everest Park	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface.	Ball Field 4 (BF4)	IBC	2009 ANSI A117.: 504.5.1	1- \$563 x

				Pł	nase 1				
Id Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
240835	Everest Park	Exterior Access Route	Stairs Drinking Fountain/Water	3	WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the remaining portion of the tread surface. A clear space is not positioned at the lower level drinking fountain for a forward approach and	Playground 1 (PG1)	IBC	2009 ANSI A117.1 504.5.1	- \$634 x
240794	Everest Park	Site Furnishings	Cooler Drinking Fountain/Water	4	centered on the unit. The minimum number and types of drinking	Drinking Fountain 1 (DF1)	ADA	602.2	\$238 x
240795	Everest Park	Site Furnishings	Cooler	4	fountains are not provided.	Drinking Fountain 1 (DF1)	ADA	211.2; 602; 309	\$8,000 x
									\$911,728

	Phase 2											
Id	Facility	Building	Assembly	IVDE	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total		
253486	Juanita Bay Park	EXTERIOR	Accessible Parking	Parking Space - Van	1	The parking space slope is greater than 1:50 (2%). WASHINGTON: Signage is not located at the required height for the van accessible space or	Accessible Parking Stall P1	ADA	502.4 502.6; WA Bldg Code 51-50 WAC	\$6,300		
253487	Juanita Bay Park	EXTERIOR	Accessible Parking	Parking Space - Van	1	access aisle. WASHINGTON: The van access aisle signage is	Accessible Parking Stall P1 Accessible Parking Stall P1 & P2	ADA State of	1101.2.6 WA Bldg Code 51-	\$280		
253488	Juanita Bay Park	EXTERIOR	Accessible Parking	Parking Space - Van	1	not compliant or not provided.	Access Aisle Accessible Parking Stall P1 & P2	Washington	50 WAC 1101	\$280		
253489	Juanita Bay Park	EXTERIOR	Accessible Parking	Parking Space-Van	1	The access aisle slope is greater than 1:50 (2%). WASHINGTON: Signage is not located at the required height for the van accessible space or	Access Aisle	ADA	502.4 502.6; WA Bldg Code 51-50 WAC	\$5,000		
253491	Juanita Bay Park	EXTERIOR	Accessible Parking	Parking Space-Van	1	access aisle. The counter slopes of adjoining gutters and streets at the curb ramp are greater than 1:20	Accessible Parking Stall P2	ADA	1101.2.6	\$280		
253492	Juanita Bay Park	EXTERIOR	Exterior Access Route	Curb Ramp	1	(5%).	Curb Ramp CR1	ADA	406.2	\$1,750		
253493	Juanita Bay Park	EXTERIOR	Exterior Access Route	Curb Ramp	1	The parallel curb ramp landing is not compliant. Steps do not have a uniform and compliant riser	Curb Ramp CR1	ADA	304, 406.4	\$1,289		
253496	Juanita Bay Park	EXTERIOR	Exterior Access Route	Stairs	1	heights and/or tread depths.	Stairs ST2	ADA	504.2	\$918		
253497	Juanita Bay Park	EXTERIOR	Exterior Access Route	Stairs	1	Handrails are not compliant. Steps do not have uniform and compliant riser	Stairs ST2	ADA	505	\$1,630		
253499	Juanita Bay Park	EXTERIOR	Exterior Access Route	Stairs	1	heights and/or tread depths.	Stairs ST3	ADA	504.2	\$5,508		
253500	Juanita Bay Park	EXTERIOR	Exterior Access Route	Stairs	1	Handrails are not compliant.	Stairs ST3	ADA	505 WA Bldg Code 51-	\$6,520		
253501	Juanita Bay Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Access Route from ST2 to ST3	State of Washington	50 WAC 1101.2.1; 403.3	\$5,000		
									WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2			
252522		5)(750)00				WASHINGTON: The slope of the curb ramp run	0 1 0 000	State of	thru 405.5; Table	44 750		
253502	Juanita Bay Park	EXTERIOR	Exterior Access Route	Curb Ramp	1	is not compliant.	Curb Ramp CR2	Washington	405.2; 403.5.1 WA Bldg Code 51-			
						WASHINGTON: The slopes of the exterior		State of	50 WAC 1101.2.1;			
253504	Juanita Bay Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Access Route AR1	Washington	403.3 WA Bldg Code 51-	\$2,800		
						WASHINGTON: The slopes of the exterior		State of	50 WAC 1101.2.1;			
253505	Juanita Bay Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Access Route AR2	Washington	403.3 WA Bldg Code 51-			
		SVEENION				WASHINGTON: The slopes of the exterior		State of	50 WAC 1101.2.1;			
253506	Juanita Bay Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Access Route AR3	Washington	403.3	\$7,200		
253507	Juanita Bay Park	EXTERIOR	Exterior Access Route	Ramp	1	The ramp is required but not provided. Steps do not have a uniform and compliant riser	Ramp R1	ADA	405, 505	\$14,564		
253508	Juanita Bay Park	EXTERIOR	Exterior Access Route	Stairs	1	heights and/or tread depths.	Stairs ST4	ADA	504.2	\$612		
253509	Juanita Bay Park	EXTERIOR	Exterior Access Route	Stairs	1	Handrails are not compliant.	Stairs ST4	ADA	505	\$978		

					Ph	ase 2				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
253510	Juanita Bay Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The clear width of the exterior accessible route is less than 44".	Bridge-boarded sidewalk	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3	
	,					The accessible route has gaps in the surface		J		
253511	Juanita Bay Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide. Ground surfaces are not firm, stable and slip	Bridge-boarded sidewalk	ADA	302.3	\$0
253512	Juanita Bay Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	resistant.	Bridge-boarded sidewalk	ADA	302.1	\$200,000
253513	Juanita Bay Park	EXTERIOR	Exterior Access Route	Ramp	1	The ramp is required but not provided. WASHINGTON: Handrails are not provided where the ramp rises more than 6" or are not	Ramp R2	ADA State of	405, 505 ADA 505.6; WA Bldg Code 51-50	\$14,564
253514	Juanita Bay Park	EXTERIOR	Exterior Access Route	Ramp	1	compliant. WASHINGTON: Handrails are not provided	Ramp R1	Washington	WAC 1101.2.1 ADA 505.6; WA	\$4,564
253515	Juanita Bay Park	EXTERIOR	Exterior Access Route	Ramp	1	where the ramp rises more than 6" or are not compliant. Steps do not have uniform and compliant riser	Ramp R2	State of Washington	Bldg Code 51-50 WAC 1101.2.1	\$4,564
253516	Juanita Bay Park	EXTERIOR	Exterior Access Route	Stairs	1	heights and/or tread depths.	Stairs ST5	ADA	504.2	\$612
253517	Juanita Bay Park	EXTERIOR	Exterior Access Route	Stairs	1	Handrails are not compliant. The accessible route has gaps in the surface	Stairs ST5	ADA	505	\$978
253518	Juanita Bay Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide. The accessible route has gaps in the surface	Bridge-North Entrance	ADA	302.3	\$198
253519	Juanita Bay Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide. Ground surfaces are not firm, stable and slip	Boardwalk to View Area #1	ADA	302.3	\$0
253520	Juanita Bay Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	resistant. WASHINGTON: The slopes of the exterior	Boardwalk to View Area #1	ADA State of	302.1 WA Bldg Code 51- 50 WAC 1101.2.1;	
253521	Juanita Bay Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Access Route AR4	State of Washington	403.3 WA Bldg Code 51-	\$198
						WASHINGTON: The slopes of the exterior		State of	50 WAC 1101.2.1;	
253522	Juanita Bay Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant. The accessible route has gaps in the surface	Access Route AR5	Washington	403.3	\$2,100
253523	Juanita Bay Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide. Ground surfaces are not firm, stable and slip	Boardwalk to View Area #2	ADA	302.3	\$0
253524	Juanita Bay Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	resistant.	Boardwalk to View Area #2	ADA	302.1	\$58,750
									WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2	-
253525	Juanita Bay Park	EXTERIOR	Exterior Access Route	Curb Ramp	1	WASHINGTON: The slope of the curb ramp run is not compliant.	Curb Ramp CR3	State of Washington	thru 405.5; Table 405.2; 403.5.1 WA Bldg Code 51-	\$1,750
253526	Juanita Bay Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Access Route AR6	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$4,800
253527	Juanita Bay Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Access Route AR7	State of Washington	50 WAC 1101.2.1; 403.3	

					Ph	ase 2				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
					Í				WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2	
253528	Juanita Bay Park	EXTERIOR	Exterior Access Route	Curb Ramp	1	WASHINGTON: The slope of the curb ramp run is not compliant.	Curb Ramp CR4	State of Washington	thru 405.5; Table 405.2; 403.5.1 WA Bldg Code 51-	\$1,750
253529	Juanita Bay Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Access Route AR8	State of Washington	50 WAC 1101.2.1; 403.3	\$3,600
253494	Juanita Bay Park	EXTERIOR	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have	Stairs ST1	IBC	2009 ANSI A117.1- 504.5.1	\$528
253495	Juanita Bay Park	EXTERIOR	Exterior Access Route	Stairs	3	visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have	Stairs ST2	IBC	2009 ANSI A117.1 504.5.1	\$141
253498	Juanita Bay Park	EXTERIOR	Exterior Access Route	Stairs	3	visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have	Stairs ST3	IBC	2009 ANSI A117.1- 504.5.1	\$634
254881	Juanita Bay Park	EXTERIOR	Exterior Access Route	Stairs	3	visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Stairs ST4	IBC	2009 ANSI A117.1- 504.5.1	\$70
254882	Juanita Bay Park	EXTERIOR	Exterior Access Route	Stairs Drinking Fountain/Water	3	on the leading 2" of the tread from the remaining portion of the tread surface. The minimum number and types of drinking	Stairs ST5	IBC	2009 ANSI A117.1- 504.5.1	\$211
253485	Juanita Bay Park	EXTERIOR	Site Furnishings	Cooler	4	fountains are not provided. The parking space slope is greater than 1:50	Adjacent to the Restrooms	ADA	211.2; 602; 309	\$8,000
253490	Juanita Bay Park	EXTERIOR	Accessible Parking	Parking Space-Van	5	(2%). WASHINGTON: Signage is not located at the required height for the van accessible space or	Accessible Parking Stall P2	ADA	502.4 502.6; WA Bldg Code 51-50 WAC	\$6,300
239526	Heritage Hall & Park	Heritage Hall	Accessible Parking	Parking Space - Van	1	access aisle. The parking space slope is greater than 1:50	Parking Lot 3 Stall P2 (P2)	ADA	1101.2.6	\$280
239527	Heritage Hall & Park	Heritage Hall	Accessible Parking	Parking Space - Van	1	(2%).	Parking Lot 3 Stall P2 (P2)	ADA	502.4	\$6,300
239528	Heritage Hall & Park	Heritage Hall	Accessible Parking	Parking Space - Van	1	The access aisle slope is greater than 1:50 (2%). WASHINGTON: The van access aisle signage is	Parking Lot 3 Stall P2 (P2)	ADA State of	502.4 WA Bldg Code 51-	\$5,000
239529	Heritage Hall & Park	Heritage Hall	Accessible Parking	Parking Space - Van	1	not compliant or not provided.	Parking Lot 3 Stall P2 (P2)	Washington	50 WAC 1101 WA Bldg Code 51-	\$280
239530	Heritage Hall & Park	Heritage Hall	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Walkway 4 (W4)	State of Washington	50 WAC 1101.2.1; 403.3	\$25,088

					Ph	ase 2				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
239531	Heritage Hall & Park	Heritage Hall	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided.	Stair 4 (ST4)	ADA	505	\$1,304
239532	Heritage Hall & Park	Heritage Hall	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided. The maneuvering clearance at the accessible	Stair 5 (ST5)	ADA	505	\$978
239533	Heritage Hall & Park	Heritage Hall	Entrance to Building	Building Entrance - Door	1	door is not level and clear. The ramp does not have a level landing at the	Entrance 1 (ENT 1)	ADA	305.2; 404.2 405.7; 405.8;	\$1,250
239534	Heritage Hall & Park	Heritage Hall	Exterior Access Route	Ramp	1	top and/or bottom of each run.	Ramp 1 (R1)	ADA	405.9	\$3,490
239535	Heritage Hall & Park	Heritage Hall	Exterior Access Route	Ramp	1	WASHINGTON: The slopes of the ramp are not compliant.	Ramp 1 (R1)	State of Washington	WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2 thru 405.5; Table 405.2; 403.5.1	\$35,748
233333	Tieritage Flair & Fark	nentage nam	Exterior Access Notice	Namp	1	WASHINGTON: An exterior accessible route is	Nump I (NI)	State of	WA Bldg Code 51- 50 WAC 1101.2.1;	
239536	Heritage Hall & Park	Heritage Hall	Exterior Access Route	Exterior Accessible Route	1	not provided.	Walkway 5 (W5)	Washington	403.3	\$13,081
239538	Heritage Hall & Park	Heritage Hall	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided. The threshold at the accessible door is greater	Stair 6 (ST6)	ADA	505	\$978
239539	Heritage Hall & Park	Heritage Hall	Entrance to Building	Building Entrance - Door	1	than ½" in height. The building does not have elevator access	Heritage Hall Lower Level Entrance	ADA	404.2.5	\$179
239540	Heritage Hall & Park	Heritage Hall	Interior Access Route	Elevator	1	between stories. The height of controls throughout the common	Heritage Hall	ADA	206.2.3	\$80,000
239544	Heritage Hall & Park	Heritage Hall	Interior Access Route	Controls And Dispensers	1	area are not compliant. The opening force required to open the	Heritage Hall Upper Level	ADA	308	\$500
239554	Heritage Hall & Park	Heritage Hall	Interior Access Route	Door	1	accessible, hinged, non-fire door is more than 5 pounds.	Heritage Hall Lower Level Door Between Museum & Restroom	ADA	404.2.9 WA Bldg Code 51-	\$366
239558	Heritage Hall & Park	Heritage Hall	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. A compliant accessible route is not provided from accessible parking to the public facility	Walkway 6 (W6)	State of Washington	50 WAC 1101.2.1; 403.3 206; 206.2.2;	\$1,982
239559	Heritage Hall & Park	Heritage Hall	Exterior Access Route	Exterior Accessible Route	1	entrance. Tactile means of egress signage is not provided at the latch side of the door. (Applies to designated egress stairways, exit doors, areas of	Walkway 7 (W7)	ADA	403.3	\$8,324
239541	Heritage Hall & Park	Heritage Hall	Interior Access Route	Signage	2	refuge) The sink rim is higher than 34", and does not	Heritage Hall	ADA	216.4, 703	\$165
239545	Heritage Hall & Park	Heritage Hall	Common Areas	Sink	2	have knee and toe clearance (does not apply to mop basins, utility sinks, or bar sinks). An accessible window is not provided where operable glazed windows are provided in an	Heritage Hall Upper Level Kitchenette	ADA	306.2 and 606.3	\$720
239556	Heritage Hall & Park	Heritage Hall	Interior Access Route	Window	2	accessible room or space.	Heritage Hall Upper Level	ADA	229	\$805

	Phase 2											
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total		
239557	Heritage Hall & Park	Heritage Hall	Interior Access Route	Window	2	An accessible window is not provided where operable glazed windows are provided in an accessible room or space. The dining or work surface does not have a minimum 20% and province 24% height with	Heritage Hall Upper Level	ADA	229	\$805		
240083	Heritage Hall & Park	Heritage Hall	Common Areas	Dining And Work Surface	2	minimum 28" and maximum 34" height with knee and toe clearance. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Heritage Hall Upper Level Kitchenette	ADA	902.3	\$2,382		
239537	Heritage Hall & Park	Heritage Hall	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface.	Stair 6 (ST6)	IBC	2009 ANSI A117.2 504.5.1	1- \$317		
239547	Heritage Hall & Park	Heritage Hall	Restroom	Restroom/Bathroom - Toilet Stall	3	WASHINGTON: A vertical side grab bar is not present in the wheelchair stall. The mirror is mounted higher than 40" above finish floor to the bottom of the reflective	Heritage Hall Upper Level Unisex Restroom	ANSI A117.1	2009 ANSI A117.3 604.5.1 and A117.1-604.9.6	\$355		
239548	Heritage Hall & Park	Heritage Hall	Restroom	Restroom/Bathroom - Mirror	3	surface, where it is installed above a lavatory or counter.	Heritage Hall Upper Level Unisex Restroom	ADA	213.3.5; 603.3	\$200		
239549 239550	Heritage Hall & Park Heritage Hall & Park	Heritage Hall Heritage Hall	Restroom Restroom	Restroom/Bathroom - Toilet Stall Restroom/Bathroom - Lavatory	3	WASHINGTON: A vertical side grab bar is not present in the wheelchair stall. Pipes are not insulated. The mirror is mounted higher than 40" above finish floor to the bottom of the reflective	Heritage Hall Lower Level Unisex Restroom Heritage Hall Lower Level Unisex Restroom	ANSI A117.1 ADA	2009 ANSI A117.: 604.5.1 and A117.1-604.9.6 606.5	\$355 \$65		
239551	Heritage Hall & Park	Heritage Hall	Restroom	Restroom/Bathroom - Mirror	3	surface, where it is installed above a lavatory or counter.	Heritage Hall Lower Level Unisex Restroom Heritage Hall Lower Level Unisex	ADA	213.3.5; 603.3	\$200		
239552	Heritage Hall & Park	Heritage Hall	Restroom	Controls And Dispensers	3	The height of controls are not compliant. The hardware at the accessible door requires	Restroom	ADA	606.1; 309.3	\$200		
239553	Heritage Hall & Park	Heritage Hall	Restroom	Restroom/Bathroom - Door	3	tight grasping, pinching or twisting of the wrist to operate The hardware at the accessible door requires	Heritage Hall Lower Level Unisex Restroom	ADA	309, 404.2.7	\$293		
239555	Heritage Hall & Park	Heritage Hall	Restroom	Restroom/Bathroom - Door	3	tight grasping, pinching or twisting of the wrist to operate WASHINGTON: The stair treads do not have	Heritage Hall Upper Level Unisex Restroom	ADA	309, 404.2.7	\$293		
243106	Heritage Hall & Park	Heritage Hall	Exterior Access Route	Stairs	3	visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the	Stair 4 (ST4)	IBC	2009 ANSI A117.: 504.5.1 2009 ANSI A117.:	\$141		
243107	Heritage Hall & Park	Heritage Hall	Exterior Access Route	Stairs	3	remaining portion of the tread surface.	Stair 5 (ST5)	IBC	504.5.1	\$106		

	Phase 2											
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total		
239546	Heritage Hall & Park	Heritage Hall	Common Areas	Controls And Dispensers	4	Controls and/or dispensers are not within an allowable reach range. WASHINGTON: A van stall, access aisle, and	Heritage Hall Upper Level Kitchenette	ADA	606.1; 308 WA Bldg Code 51-	\$500		
239506	Heritage Hall & Park	Heritage Park	Accessible Parking	Parking Space - Van	1	signage are not provided and the slope and/or ground surface is/are not compliant.	Parking Lot 2	State of Washington	50 WAC 1101; ADA 502.4, 502.5	\$11,300		
239508	Heritage Hall & Park	Heritage Park	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided.	Stair 1 (ST1)	ADA	505 WA Bldg Code 51-	\$3,912		
239509	Heritage Hall & Park	Heritage Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 1 (W1)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$1,200		
239512	Heritage Hall & Park	Heritage Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. WASHINGTON: A van stall, access aisle, and	Walkway 2 (W2)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$360		
239513	Heritage Hall & Park	Heritage Park	Accessible Parking	Parking Space - Van	1	signage are not provided and the slope and/or ground surface is/are not compliant.	Parking Lot 1	State of Washington	50 WAC 1101; ADA 502.4, 502.5	\$11,300		
239514	Heritage Hall & Park	Heritage Park	Accessible Parking	Parking Space - Car	1	The slope of the parking space is greater than 1:50 (2%). WASHINGTON: Signage is not located at the	Parking Lot 1 - Stall P1	ADA	502.4 502.6; WA Bldg	\$6,300		
239515	Heritage Hall & Park	Heritage Park	Accessible Parking	Parking Space - Car	1	required height for the standard accessible space or access aisle.	Parking Lot 1 - Stall P1	ADA	Code 51-50 WAC 1101.2.6	\$280		
239516	Heritage Hall & Park	Heritage Park	Accessible Parking	Parking Space - Car	1	The access aisle slope is greater than 1:50 (2%).	Parking Lot 1 - Stall P1	ADA	502.4	\$5,000		
239517	Heritage Hall & Park	Heritage Park	Accessible Parking	Parking Space - Car	1	WASHINGTON: The car access aisle signage is not compliant or not provided.	Parking Lot 1 - Stall P1	State of Washington	WA Bldg Code 51- 50 WAC 1101 WA Bldg Code 51-	\$280		
239518	Heritage Hall & Park	Heritage Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: A compliant exterior accessible route is not provided.	Walkway 3 (W3)	State of Washington	50 WAC 1101.2.1; 403.3	\$44,899		
239520	Heritage Hall & Park	Heritage Park	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided.	Stair 3 (ST3)	ADA	505	\$4,727		
239521	Heritage Hall & Park	Heritage Park	Exterior Access Route	Stairs	1	Steps do not have uniform and compliant riser heights and/or tread depths.	Stair 3 (ST3)	ADA	504.2	\$11,934		
239523	Heritage Hall & Park	Heritage Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. WASHINGTON: A car stall, access aisle, and	Park Entrance (PE)	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$960		
240082	Heritage Hall & Park	Heritage Park	Accessible Parking	Parking Space-Car	1	signage are not provided and the slope and/or ground surface is/are not compliant.	Parking Lot 2	State of Washington	50 WAC 1101; ADA 502.4, 502.5 WA Bldg Code 51-	\$11,300		
240210	Heritage Hall & Park	Heritage Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. The gate does not have a smooth surface within	Playground Tennis Court Gate 1 & Gate 2 (G1 &	State of Washington	50 WAC 1101.2.1; 403.3			
239511 239524	Heritage Hall & Park Heritage Hall & Park	Heritage Park Heritage Park	Exterior Access Route Exterior Access Route	Gate Reach Range	2 2		G2)	ADA ADA	404.2.10 308, 309	\$320 \$450		

	Phase 2											
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total		
240212	Heritage Hall & Park	Heritage Park	Playground	Ground Surface-Fibar	2	The ground surface has not been inspected and maintained regularly. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Playground	ADA	1008.2	\$682		
239507	Heritage Hall & Park	Heritage Park	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Stair 1 (ST1)	IBC	2009 ANSI A117.1- 504.5.1	\$246		
239510	Heritage Hall & Park	Heritage Park	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Stair 2 (ST2)	IBC	2009 ANSI A117.1- 504.5.1	\$669		
239519	Heritage Hall & Park	Heritage Park	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface.	Stair 3 (ST3)	IBC	2009 ANSI A117.1- 504.5.1	\$493		
243914	Heritage Hall & Park	Heritage Park	Exterior Access Route	Signage	4	ADVISORY: Directional signage indicating the accessible route is not provided, where existing routes are both accessible and non-accessible.	Routes Throughout Park	ADA	216.6	\$0		
240868		Juanita Beach Park	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided. WASHINGTON: Signage is not located at the required height for the standard accessible	Stair 1 (ST1)	ADA	505 502.6; WA Bldg Code 51-50 WAC	\$5,868		
240869		Juanita Beach Park	Accessible Parking	Parking Space - Car	1	space or access aisle. WASHINGTON: The car access aisle signage is	Parking Stalls P1 - P10	ADA State of	1101.2.6 WA Bldg Code 51-	\$2,800		
240870		Juanita Beach Park	Accessible Parking	Parking Space - Car	1	not compliant or not provided. The slope of the parking space is greater than	Parking Stalls P1 - P10	Washington	50 WAC 1101	\$1,400		
240871		Juanita Beach Park	Accessible Parking	Parking Space - Car	1	1:50 (2%).	Parking Stall 3 (P3)	ADA	502.4	\$6,300		
240872		Juanita Beach Park	Accessible Parking	Parking Space - Car	1	The access aisle slope is greater than 1:50 (2%). The slope of the parking space is greater than	Parking Stall P3/P4	ADA	502.4	\$5,000		
240873		Juanita Beach Park	Accessible Parking	Parking Space - Car	1	1:50 (2%). The sidewalk does not have 80" vertical	Parking Stall 4 (P4)	ADA	502.4	\$6,300		
240874		Juanita Beach Park	Exterior Access Route	Exterior Accessible Route	1	clearance. The slope of the parking space is greater than	Walkway 1 (W1)	ADA	307.4	\$200		
240875		Juanita Beach Park	Accessible Parking	Parking Space - Car	1	1:50 (2%).	Parking Stall 5 (P5)	ADA	502.4	\$6,300		
240876		Juanita Beach Park	Accessible Parking	Parking Space - Car	1	The access aisle slope is greater than 1:50 (2%). The slope of the parking space is greater than	Parking Stall P5/P6	ADA	502.4	\$5,000		
240877		Juanita Beach Park	Accessible Parking	Parking Space - Car	1	1:50 (2%).	Parking Stall 6 (P6)	ADA	502.4	\$6,300		
240878		Juanita Beach Park	Accessible Parking	Parking Space - Car	1	The slope of the parking space is greater than 1:50 (2%).	Parking Stall 7 (P7)	ADA	502.4	\$6,300		
240879		Juanita Beach Park	Accessible Parking	Parking Space - Car	1	The access aisle slope is greater than 1:50 (2%).	Parking Stall P7/P8	ADA	502.4	\$5,000		
240880		Juanita Beach Park	Accessible Parking	Parking Space - Car	1	The slope of the parking space is greater than 1:50 (2%).	Parking Stall 8 (P8)	ADA	502.4	\$6,300		

Phase 2											
ld Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total		
240881	Juanita Beach Park	Accessible Parking	Parking Space - Car	1	The slope of the parking space is greater than 1:50 (2%).	Parking Stall 9 (P9)	ADA	502.4	\$6,300		
240882	Juanita Beach Park	Accessible Parking	Parking Space - Car	1	The access aisle slope is greater than 1:50 (2%). The slope of the parking space is greater than	Parking Stall P9/P10	ADA	502.4	\$5,000		
240883	Juanita Beach Park	Accessible Parking	Parking Space - Car	1	1:50 (2%). An accessible route does not directly connect	Parking Stall 10 (P10)	ADA	502.4	\$6,300		
240884	Juanita Beach Park	Volleyball Courts	Sport Court	1	each side of the court outside of play lines.	Volleyball Court (VC)	ADA	206.2.12; 403 WA Bldg Code 51	\$4,673 -		
240886	Juanita Beach Park	Picnic Area	Picnic Table	1	WASHINGTON: An exterior accessible route is not provided.	Picnic Area 1 (PA1)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$867 -		
240889	Juanita Beach Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. Sidewalk has areas of vertical level changes in	Art Sculpture (AS)	State of Washington	50 WAC 1101.2.1; 403.3	\$1,080		
240890	Juanita Beach Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Walkway 1 (W1)	ADA	303 WA Bldg Code 51	\$60		
240892	Juanita Beach Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 2 (W2)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$500		
240893	Juanita Beach Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. WASHINGTON: A van stall, access aisle, and	Walkway 1 (W1)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$23,200		
240894	Juanita Beach Park	Accessible Parking	Parking Space - Van	1	signage are not provided and the slope and/or ground surface is/are not compliant.	Parking Lot 1	State of Washington	50 WAC 1101; ADA 502.4, 502.5 WA Bldg Code 51	\$11,300		
240895	Juanita Beach Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 3 (W3)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$1,440		
240896	Juanita Beach Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 4 (W4)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$1,440		
240897	Juanita Beach Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. WASHINGTON: Where a detectable warning is	Walkway 5 (W5)	State of Washington	50 WAC 1101.2.1; 403.3	\$4,320		
240898	Juanita Beach Park	Exterior Access Route	Curb Ramp	1	located on a curb ramp run, the detectable warning is not compliant.	Curb Ramps 1 - 4 (CR1 - CR4)	IBC	2009 ANSI A117.1 705.3 and 705.5 WA Bldg Code 51	\$2,560		
240899	Juanita Beach Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. An accessible route does not directly connect	Picnic Area 2 (PA2)	State of Washington	50 WAC 1101.2.1; 403.3	\$867		
240900	Juanita Beach Park	Horseshoe Courts	Sport Court	1	each side of the court.	Horseshoe Pit (HP)	ADA	206.2.12; 403 WA Bldg Code 51	\$876		
240901	Juanita Beach Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 6 (W6)	State of Washington	50 WAC 1101.2.1; 403.3			

Phase 2										
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
240902		Juanita Beach Park	Exterior Access Route	Curb Ramp	1	WASHINGTON: Where a detectable warning is located on a curb ramp run, the detectable warning is not compliant.	Curb Ramps 11 - 14 (CR11 - CR14) Tennis Court (TC) - Ball Field 1 & 2	IBC	2009 ANSI A117.1 705.3 and 705.5 WA Bldg Code 51-	\$2,560
240903		Juanita Beach Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. The gate maneuvering clearance area is not	(BF1 & BF2) - Picnic Area 3 (PA3) - Portable Restroom (PRR)	State of Washington	50 WAC 1101.2.1; 403.3 404; 404.2.3,	
240904		Juanita Beach Park	Exterior Access Route	Gate	1	compliant.	Tennis Court (TC)	ADA	404.2.4	\$1,136
240911		Juanita Beach Park	Exterior Access Route	Exterior Accessible Route	1	The gate is less than 32" in width. WASHINGTON: A van stall, access aisle, and	Ball Field 2 (BF2)	ADA	404; 404.2.3 WA Bldg Code 51-	\$1,136
240913		Juanita Beach Park	Accessible Parking	Parking Space - Van	1	signage are not provided and the slope and/or ground surface is/are not compliant.	Parking Lot 2	State of Washington	50 WAC 1101; ADA 502.4, 502.5 WA Bldg Code 51-	\$11,300
						WASHINGTON: An exterior accessible route is		State of	50 WAC 1101.2.1;	
240916		Juanita Beach Park	Exterior Access Route	Exterior Accessible Route	1	not provided.	Boat Launch (BL)	Washington	403.3	\$2,336
240918		Juanita Beach Park	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided.	Stair 2 (ST2)	ADA	505	\$978
240919		Juanita Beach Park	Exterior Access Route	Ramp	1	The ramp is required but not provided.	Stair 2 (ST2)	ADA	405, 505	\$7,944
240920		Juanita Beach Park	Exterior Access Route	Exterior Accessible Route	1	The accessible route has gaps in the surface greater than 1/2" wide. The accessible route has gaps in the surface	Stair 2 (ST2)	ADA	302.3	\$555
240921		Juanita Beach Park	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide.	Walkway 7 (W7)	ADA	302.3 WA Bldg Code 51-	\$50
240922		Juanita Beach Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. WASHINGTON: Where a detectable warning is	Beach Access	State of Washington	50 WAC 1101.2.1; 403.3	\$79
241207		Juanita Beach Park	Exterior Access Route	Curb Ramp	1	located on a curb ramp run, the detectable warning is not compliant.	Curb Ramps 8 - 10 (CR8 - CR10)	IBC	2009 ANSI A117.1 705.3 and 705.5 WA Bldg Code 51-	\$1,920
241208		Juanita Beach Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. WASHINGTON: Where a detectable warning is	Walkway 8 (W8)	State of Washington	50 WAC 1101.2.1; 403.3	\$1,593
241209		Juanita Beach Park	Exterior Access Route	Curb Ramp	1	located on a curb ramp run, the detectable warning is not compliant.	Curb Ramps 5 - 7 (CR5 - CR7)	IBC	2009 ANSI A117.1 705.3 and 705.5 WA Bldg Code 51-	\$1,920
241210		Juanita Beach Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. WASHINGTON: A car stall, access aisle, and	Walkway 9 (W9)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$1,180
241504		Juanita Beach Park	Accessible Parking	Parking Space-Car	1	signage are not provided and the slope and/or ground surface is/are not compliant. A wheelchair space is not provided at the	Parking Lot 2	State of Washington	50 WAC 1101; ADA 502.4, 502.5	\$22,600
240885		Juanita Beach Park	Volleyball Courts	Player Seating	2	seating for the volleyball courts. The gate does not have a smooth surface within	Volleyball Court (VC)	ADA	221.2.1.4; 802.1	\$71
240905		Juanita Beach Park	Exterior Access Route	Gate	2	10" of the ground.	Tennis Court (TC)	ADA	404.2.10	\$320

				Ph	nase 2				
ld Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
240906	Juanita Beach Park	Baseball/Softball Field	Player Seating	2	A wheelchair space is not provided at each team bench area at the ball field. The required number of wheelchair spaces is not provided at the bleacher seating for the ball	Ball Field 1 (BF1)	ADA	221.2.1.4; 802.1	\$142
240907	Juanita Beach Park	Baseball/Softball Field	Bleacher Seating	2	field. A wheelchair space is not provided at each team	Ball Field 1 (BF1)	ADA	221; 802.2; 802.3	\$283
240909	Juanita Beach Park	Baseball/Softball Field	Player Seating	2	bench area at the ball field. The required number of wheelchair spaces is not provided at the bleacher seating for the ball	Ball Field 2 (BF2)	ADA	221.2.1.4; 802.1	\$142
240910	Juanita Beach Park	Baseball/Softball Field	Bleacher Seating	2	field. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Ball Field 2 (BF2)	ADA	221; 802.2; 802.3	\$283
240866	Juanita Beach Park	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Playground (PG)	IBC	2009 ANSI A117.1 504.5.1	\$845
240867	Juanita Beach Park	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface.	Stair 1 (ST1)	IBC	2009 ANSI A117.1: 504.5.1 309, 404.2.7, 604.5.1, 604.6, 604.7, 604.8.1.1, 604.8.1.2,	\$106
240887	Juanita Beach Park	Restroom	Restroom/Bathroom - Toilet Stall	3	A wheelchair stall is not provided in a multi-user restroom.	Women's Restroom (WRR)	ADA	604.8.1.5, 604.9, 609.3 309, 404.2.7, 604.5.1, 604.6, 604.7, 604.8.1.1, 604.8.1.2,	\$2,750
240891	Juanita Beach Park	Restroom	Restroom/Bathroom - Toilet Stall	3	A wheelchair stall is not provided in a multi-user restroom.	Men's Restroom (MRR)	ADA	604.8.1.5, 604.9, 609.3	\$2,750
					The accessible door does not have the required	, ,		404.2.4.1; Table	
240912	Juanita Beach Park	Portable Restroom	Restroom/Bathroom-Door	3	PUSH SIDE maneuvering clearances. The force required to open the interior, hinged,	Portable Restroom (PRR)	ADA	404.2.4.1	\$7,465
240914	Juanita Beach Park	Restroom	Restroom/Bathroom - Door	3	non-fire door is more than 5 pounds. The accessible door with door closer has a sweep period of less than 5 seconds from 90	Unisex Restrooms (URR)	ADA	404.2.9	\$732
240915	Juanita Beach Park	Restroom	Restroom/Bathroom - Door	3	degrees to a position 12 degrees from latch. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Unisex Restrooms (URR)	ADA	404.2.8	\$0
240917	Juanita Beach Park	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: A van stall, access aisle, and	Stair 2 (ST2)	IBC	2009 ANSI A117.1 504.5.1 WA Bldg Code 51-	\$70
243960	North Rose Hill Woodlands Park	Accessible Parking	Parking Space-Van	1	signage are not provided and the slope and/or ground surface is/are not compliant.	On-Street Parking	State of Washington	50 WAC 1101; ADA 502.4, 502.5	\$11,300

					Ph	ase 2				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243961		North Rose Hill Woodlands Park	Exterior Access Route	Gate	1	The gate maneuvering clearance area is not compliant. The accessible route has areas of vertical level	Entrance Gate 1 (E1)	ADA	404; 404.2.3, 404.2.4	\$568
243962		North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	changes in excess of 1/4" that are not beveled or ramped.	Entrance Gate 1 (E1)	ADA	303 WA Bldg Code 51	\$59 -
243964		North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from E1 to Play Area 1	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$14,400
243968		North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Picnic Area near Play Area 1	State of Washington	50 WAC 1101.2.1; 403.3	\$400
243970		North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Bench near Play Area 1	State of Washington	WA Bldg Code 51: 50 WAC 1101.2.1; 403.3	
243972		North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway at Play Area 1	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3	
243372		Woodianas Fark	Extensi Access notice	Exterior Accessiste route	-	accessible route are not compilant.	walkway at hay Area 1	Washington	WA Bldg Code 51: 50 WAC 1101.6; ADA 406; 405.2	
243975		North Rose Hill Woodlands Park	Exterior Access Route	Ramp	1	WASHINGTON: The slopes of the ramp are not compliant. WASHINGTON: Handrails are not provided	Ramp 1 (R1)	State of Washington	thru 405.5; Table 405.2; 403.5.1 ADA 505.6; WA	\$7,944
243977		North Rose Hill Woodlands Park	Exterior Access Route	Ramp	1	where the ramp rises more than 6" or are not compliant.	Ramp 1 (R1)	State of Washington	Bldg Code 51-50 WAC 1101.2.1	\$652
243978		North Rose Hill Woodlands Park	Exterior Access Route	Ramp	1	WASHINGTON: The slopes of the ramp are not compliant.	Ramp 2 (R2)	State of Washington	WA Bldg Code 51 50 WAC 1101.6; ADA 406; 405.2 thru 405.5; Table 405.2; 403.5.1	- \$3,972
									WA Bldg Code 51 50 WAC 1101.6; ADA 406; 405.2	-
243981		North Rose Hill Woodlands Park	Exterior Access Route	Ramp	1	WASHINGTON: The slopes of the ramp are not compliant. The accessible route has areas of vertical level	Ramp 3 (R3)	State of Washington	thru 405.5; Table 405.2; 403.5.1	\$7,944
243982		North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	changes in excess of 1/4" that are not beveled or ramped. The accessible route has areas of vertical level	Ramp 3 (R3)	ADA	303	\$0
243983		North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	changes in excess of 1/4" that are not beveled or ramped.	Ramp 4 (R4)	ADA	303	\$143

Phase 2									
Id Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243991	North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Play Area 1 to NE 95th St	State of Washington	WA Bldg Code 51 50 WAC 1101.2.1; 403.3 WA Bldg Code 51	; \$8,000
243992	North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Play Area 1 to NE 95th St	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	; \$1,600
243993	North Rose Hill Woodlands Park North Rose Hill	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. An accessible route to the portable restroom	Walkway from Play Area 1 to NE 95th St	State of Washington	50 WAC 1101.2.1; 403.3	
243996	Woodlands Park	Portable Restroom	Portable Restroom	1	has not been provided.	Portable Restroom (RR1)	ADA	402, 404 WA Bldg Code 51	\$2,124
243998	North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Play Area 1 to NE 95th St	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	; \$2,400
243999	North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route has areas of vertical level	Walkway from Play Area 1 to NE 95th St	State of Washington	50 WAC 1101.2.1; 403.3	
244000	North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	changes in excess of 1/4" that are not beveled or ramped. The accessible route has areas of vertical level	Walkway from Play Area 1 to NE 95th St	ADA	303	\$54
244001	North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	changes in excess of 1/4" that are not beveled or ramped.	Walkway from Play Area 1 to NE 95th St	ADA	303 WA Bldg Code 51	\$54
244002	North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route has areas of vertical level	Walkway from Play Area 1 to NE 95th St	State of Washington	50 WAC 1101.2.1; 403.3	
244003	North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	changes in excess of 1/4" that are not beveled or ramped.	Walkway from Play Area 1 to NE 95th St	ADA	303 WA Bldg Code 51	\$72
244004	North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Play Area 1 to Shelter Picnic Area	State of Washington	50 WAC 1101.2.1; 403.3	; \$4,800
244005	North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Play Area 1 to Shelter Picnic Area	State of Washington	WA Bldg Code 51 50 WAC 1101.2.1; 403.3	
244006	North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	The accessible route does not have 80" vertical clearance. The accessible route has areas of vertical level	Walkway from Play Area 1 to Shelter Picnic Area	ADA	307.4	\$250
244007	North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	changes in excess of 1/4" that are not beveled or ramped.	r Walkway from Play Area 1 to Shelter Picnic Area	ADA	303 WA Bldg Code 51	\$45
244008	North Rose Hill Woodlands Park North Rose Hill	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route does not have 80" vertical	Walkway from Play Area 1 to Shelter Picnic Area Walkway from Play Area 1 to	State of Washington	50 WAC 1101.2.1; 403.3	; \$2,800
244009	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	clearance.	Shelter Picnic Area	ADA	307.4	\$250

Phase 2										
ld Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total	
	North Rose Hill			·	WASHINGTON: The slopes of the exterior	Walkway from Play Area 1 to	State of	WA Bldg Code 51 50 WAC 1101.2.1;		
244010	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant. The accessible route has areas of vertical level	Shelter Picnic Area	Washington	403.3	\$5,600	
244011	North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	changes in excess of 1/4" that are not beveled o ramped.	r Walkway from Play Area 1 to Shelter Picnic Area	ADA	303	\$0	
	North Rose Hill				WASHINGTON: The slopes of the exterior	Walkway from Play Area 1 to	State of	WA Bldg Code 51 50 WAC 1101.2.1;		
244012	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant. The accessible route has areas of vertical level	Shelter Picnic Area	Washington	403.3	\$4,800	
	North Rose Hill		5		changes in excess of 1/4" that are not beveled o	•		202	40	
244013	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	ramped.	Shelter Picnic Area	ADA	303 WA Bldg Code 51		
244015	North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Shelter Picnic Area to NE 100 St	State of Washington	50 WAC 1101.2.1; 403.3	\$16,000	
244013	Woodiands Fark	Exterior Access Noute	Exterior Accessible Route	-	The accessible route has areas of vertical level	to NE 100 St	wasiiiigtoii	403.3	710,000	
	North Rose Hill				changes in excess of 1/4" that are not beveled o	•				
244016	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	ramped.	to NE 100 St	ADA	303 WA Bldg Code 51	\$108 -	
	North Rose Hill				WASHINGTON: The slopes of the exterior	Walkway from Shelter Picnic Area	State of	50 WAC 1101.2.1;		
244017	Woodlands Park North Rose Hill	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant. The accessible route does not have 80" vertical	to NE 124th Ave Walkway from Shelter Picnic Area	Washington	403.3	\$14,000	
244018	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	clearance.	to NE 124th Ave	ADA	307.4 WA Bldg Code 51	\$250	
	North Rose Hill				WASHINGTON: The slopes of the exterior	Walkway from Shelter Picnic Area	State of	50 WAC 1101.2.1;		
244019	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	to NE 124th Ave	Washington	403.3 WA Bldg Code 51	\$14,400 -	
	North Rose Hill				WASHINGTON: The slopes of the exterior	Walkway from Shelter Picnic Area	State of	50 WAC 1101.2.1;		
244020	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant. The accessible route has areas of vertical level	to NE 124th Ave	Washington	403.3	\$3,200	
	North Rose Hill			_	changes in excess of 1/4" that are not beveled o	•			4	
244021	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	ramped.	to NE 124th Ave	ADA	303 WA Bldg Code 51		
244022	North Rose Hill	Exterior Assess Douts	Futorior Associble Doute	1	WASHINGTON: The slopes of the exterior	Walkway Loop at Shelter Picnic	State of	50 WAC 1101.2.1;		
244022	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Area	Washington	403.3 WA Bldg Code 51		
244022	North Rose Hill	Exterior Assess Douts	Futorior Associble Doute	1	WASHINGTON: The slopes of the exterior	North Walkway Loop at Shelter	State of	50 WAC 1101.2.1;		
244023	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Picnic Area	Washington	403.3 WA Bldg Code 51		
244025	North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	South Walkway Loop at Shelter Picnic Area	State of Washington	50 WAC 1101.2.1; 403.3	\$9,600	
2 44 023	North Rose Hill	Exterior Access houte	Exterior Accessible Route	1	The accessible route has gaps in the surface	South Walkway Loop at Shelter	vvasiiiigtoii	- 103.3	<i>γ3,</i> 000	
244026	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide.	Picnic Area	ADA	302.3	\$0	

	Phase 2										
Id Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total		
	North Rose Hill				WASHINGTON: The slopes of the exterior	Walkway from Shelter Picnic Area	State of	WA Bldg Code 51 50 WAC 1101.2.1;			
244027	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	to NE 100th St and 128th Ave NE	Washington	403.3	\$2,000		
								WA Bldg Code 51			
244028	North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Shelter Picnic Area to NE 100th St and 128th Ave NE	State of Washington	50 WAC 1101.2.1; 403.3	\$2,400		
211020	TT GG GLIGHT GG T GLIN	Exterior recess rioute	Exterior recessions reduce	-	accessione route and not compliant.	to 112 200th of and 220th / 110 112		WA Bldg Code 51			
	North Rose Hill				WASHINGTON: The slopes of the exterior	Walkway from Shelter Picnic Area	State of	50 WAC 1101.2.1;			
244029	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	to NE 100th St and 128th Ave NE	Washington	403.3 WA Bldg Code 51	\$1,600 -		
	North Rose Hill				WASHINGTON: The slopes of the exterior	Walkway from Shelter Picnic Area	State of	50 WAC 1101.2.1;			
244030	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	to NE 100th St	Washington	403.3	\$4,800		
					The accessible route has areas of vertical level						
244031	North Rose Hill Woodlands Park	Exterior Assess Bouts	Exterior Accessible Route	1	changes in excess of 1/4" that are not beveled or	r Walkway from Shelter Picnic Area to NE 100th St	ADA	202	\$72		
244031	North Rose Hill	Exterior Access Route	Exterior Accessible Route	1	ramped. The sidewalk does not have 80" vertical	Walkway from Shelter Picnic Area	ADA	303	\$72		
244032	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	clearance.	to NE 100th St	ADA	307.4	\$250		
					The accessible route has areas of vertical level						
	North Rose Hill			,	changes in excess of 1/4" that are not beveled or	•		202	470		
244033	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	ramped.	to NE 100th St	ADA	303 WA Bldg Code 51	\$72 -		
	North Rose Hill				WASHINGTON: The slopes of the exterior	Walkway from Shelter Picnic Area	State of	50 WAC 1101.2.1;			
244034	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	to NE 100th St	Washington	403.3	\$6,800		
	Nanth Dass IIII				The accessible route has areas of vertical level	. Mallana faras Chaltas Diasis Assa					
244035	North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	changes in excess of 1/4" that are not beveled or ramped.	r Walkway from Shelter Picnic Area to NE 100th St	ADA	303	\$0		
244033	Woodianus Fank	Exterior Access Noute	Exterior Accessible Route	•	rumped.	10 NE 100til 3t	ADA	WA Bldg Code 51			
	North Rose Hill				WASHINGTON: The slopes of the exterior	Walkway from Shelter Picnic Area	State of	50 WAC 1101.2.1;			
244036	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	to 128th Ave NE	Washington	403.3	\$8,000		
	North Rose Hill				The accessible route has areas of vertical level changes in excess of 1/4" that are not beveled or	. Walkway from Shelter Picnic Area					
244037	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	ramped.	to 128th Ave NE	ADA	303	\$72		
					The accessible route has areas of vertical level						
	North Rose Hill				changes in excess of 1/4" that are not beveled or	•			4		
244038	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	ramped.	to 128th Ave NE	ADA	303 WA Bldg Code 51	\$72		
	North Rose Hill				WASHINGTON: The slopes of the exterior	Walkway from Shelter Picnic Area	State of	50 WAC 1101.2.1;			
244039	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	to 128th Ave NE	Washington	403.3	\$800		
								WA Bldg Code 51			
244040	North Rose Hill Woodlands Park	Exterior Access Bouts	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Shelter Picnic Area to 128th Ave NE	State of Washington	50 WAC 1101.2.1; 403.3	\$1,600		
244040	WOOdiailus Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	TO 120TH AVE INE	vvasiiiigtofi	WA Bldg Code 51			
	North Rose Hill				WASHINGTON: The slopes of the exterior	Walkway from Shelter Picnic Area	State of	50 WAC 1101.2.1;			
244041	Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	to 128th Ave NE	Washington	403.3	\$2,000		

					Ph	ase 2				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
244042		North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	The accessible route does not have 80" vertical clearance. The accessible route has areas of vertical level	Walkway from Shelter Picnic Area to 128th Ave NE	ADA	307.4	\$250
244043		North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	changes in excess of 1/4" that are not beveled or ramped.	Walkway from Shelter Picnic Area to 128th Ave NE	ADA	303 WA Bldg Code 51	\$179
244044		North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Walkway from Shelter Picnic Area to 128th Ave NE	State of Washington	50 WAC 1101.2.1 403.3	
244045		North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	The accessible route does not have 80" vertical clearance.	Walkway from Shelter Picnic Area to 128th Ave NE	ADA	307.4 WA Bldg Code 51	\$250 1-
244046		North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route has areas of vertical level	Walkway to Play Area 2	State of Washington	50 WAC 1101.2.1 403.3	; \$1,280
244047		North Rose Hill Woodlands Park	Exterior Access Route	Exterior Accessible Route	1	changes in excess of 1/4" that are not beveled or ramped.	Walkway to Play Area 2	ADA	303	\$358
244051		North Rose Hill Woodlands Park	Exterior Access Route	Protruding Object	1	Protruding objects in the 27" to 80" range above finished floor protrude more than 4" into the circulation path along the accessible route.	Drinking Fountain 1 (DF1)	ADA	307.2	\$728
									WA Bldg Code 51 50 WAC 1101.6; ADA 406; 405.2	L -
244468		North Rose Hill Woodlands Park North Rose Hill	Exterior Access Route	Ramp	1	WASHINGTON: The slopes of the ramp are not compliant. The sidewalk does not have 80" vertical	Ramp 4 (R4) North Walkway Loop at Shelter	State of Washington	thru 405.5; Table 405.2; 403.5.1	\$3,972
244585		Woodlands Park North Rose Hill	Exterior Access Route	Exterior Accessible Route	1	clearance. The gate does not have a smooth surface within	Picnic Area	ADA	307.4	\$250
243963		Woodlands Park North Rose Hill	Exterior Access Route	Gate	2	10" of the ground. The picnic table does not allow a clear space for forward wheelchair approach with knee and toe	Entrance Gate 1 (E1)	ADA	404.2.10	\$160
243967		Woodlands Park	Picnic Area	Picnic Table	2	clearance. The picnic table does not allow a clear space for	Picnic Area near Play Area 1	ADA	902.2; 902.4	\$120
243973		North Rose Hill Woodlands Park North Rose Hill	Picnic Area	Picnic Table	2	forward wheelchair approach with knee and toe clearance. The checkers table does not have compliant	Checkers Table at Play Area 1	ADA	902.2; 902.4	\$336
243974		Woodlands Park North Rose Hill	Common Areas	Dining And Work Surface	2	knee and toe clearance. 50% or more of the elevated play components	Checkers Table at Play Area 1	ADA	306.3	\$1,000
243985 243986		Woodlands Park North Rose Hill	Playground	Play Component	2	A transfer space is not provided at the platform	Play Area 1	ADA ADA	240.2.2 1008.3.1.3	\$50,000 \$0
243980		Woodlands Park North Rose Hill	Playground	Transfer System	2	A transfer space is not provided at the platform. The transfer platform connecting to elevated play elements has a non-compliant height lower	riay Alea 1	AUA	1000.5.1.3	ŞU
243988		Woodlands Park	Playground	Transfer System	2	than 11" or higher than 18".	Play Area 1	ADA	1008.3.1	\$0

	Phase 2										
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total	
243989		North Rose Hill Woodlands Park	Playground	Play Component-Swing	2	A turning space is not provided at a school-age swing. The entry points to a play component requiring	Play Area 1	ADA	1008.4.1	\$0	
243990		North Rose Hill Woodlands Park	Playground	Play Component	2	transfer to entry points or seats is lower than 11" and higher than 24". The picnic table does not allow a clear space for	Play Area 1	ADA	1008.4.4	\$400	
243994		North Rose Hill Woodlands Park	Picnic Area	Picnic Table	2	forward wheelchair approach with knee and toe clearance. Clear ground space is not provided at each	South Picnic Area	ADA	902.2; 902.4	\$120	
244053		North Rose Hill Woodlands Park	Playground	Play Component	2	ground play component, and each elevated play component connected by a ramp. The play component requires transfer to entry	Play Area 2	ADA	1008.4.2	\$0	
244054		North Rose Hill Woodlands Park	Playground	Play Component	2	points or seats, but at least one means of support is not provided.	Play Area 2	ADA	1008.4.5	\$5,000	
244055		North Rose Hill Woodlands Park	Playground	Play Component	2	The entry points to a play component requiring transfer to entry points or seats is lower than 11" and higher than 24".	Play Area 2	ADA	1008.4.4	\$400	
						The play table does not provide knee clearance 24" high minimum, 17" deep minimum, and 30" wide minimum, and/or the tops of rims, curbs,					
244056		North Rose Hill Woodlands Park North Rose Hill	Playground	Play Component - Play Table	2	or other obstructions at the play table are higher than 31". The dining table does not have 30" x 48" clear	Play Area 2	ADA	1008.4.3	\$1,103	
244057		Woodlands Park North Rose Hill	Common Areas	Dining And Work Surface	2	floor space positioned for a forward approach.	Play Area 2	ADA	305.3	\$0	
243966		Woodlands Park North Rose Hill	Exterior Access Route	Clear Space	3	Clear space is not provided at the operable part.	Walkway from E1 to Play Area 1	ADA	305; 309.2	\$120	
243997		Woodlands Park North Rose Hill	Portable Restroom	Portable Restroom	3	An ADA portable restroom is not provided.	Portable Restroom (RR1)	ADA	213.2; 402.2	\$3,000	
243969		Woodlands Park North Rose Hill	Picnic Area	Picnic Table	4	A compliant picnic table is not provided.	Picnic Area near Play Area 1	ADA	902	\$1,300	
243995		Woodlands Park North Rose Hill	Picnic Area	Picnic Table	4	A compliant picnic table is not provided.	South Picnic Area	ADA	902	\$1,300	
244014		Woodlands Park North Rose Hill	Picnic Area	Picnic Table Drinking Fountain/Water	4	A compliant picnic table is not provided. A clear space is not positioned at the lower level drinking fountain for a forward approach and	Shelter Picnic Area	ADA	902	\$1,300	
244048		Woodlands Park North Rose Hill	Site Furnishings	Cooler Drinking Fountain/Water	4	centered on the unit. The minimum number and types of drinking	Drinking Fountain 1 (DF1)	ADA	602.2	\$120	
244049		Woodlands Park North Rose Hill	Site Furnishings	Cooler	4	fountains are not provided.	Drinking Fountain 1 (DF1)	ADA	211.2; 602; 309	\$8,000	
244058		Woodlands Park	Picnic Area	Picnic Table	4	A compliant picnic table is not provided. The accessible door with door closer has a sweep period of less than 5 seconds from 90	Play Area 2	ADA	902	\$1,300	
253462	Juanita Bay Park	RESTROOMS	Entrance to Building	Building Entrance - Door	1	degrees to a position 12 degrees from latch.	Men's Restroom	ADA	404.2.8	\$366	

					Ph	ase 2				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
					,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	The opening force of the fire door is more than				
253463	Juanita Bay Park	RESTROOMS	Exterior Access Route	Door	1	the minimum allowable by the appropriate administrative authority.	Men's Restroom	ADA	404.2.9	\$0
	•					The push side of the accessible door does not			404.2; Table	
253473	Juanita Bay Park	RESTROOMS	Exterior Access Route	Door	1	have the required maneuvering clearances. The opening force of the fire door is more than	Men's Restroom	ADA	404.2.4.1	\$50
						the minimum allowable by the appropriate				
253476	Juanita Bay Park	RESTROOMS	Exterior Access Route	Door	1	administrative authority. The accessible door with door closer has a	Women's Restroom	ADA	404.2.9	\$0
						sweep period of less than 5 seconds from 90				
253477	Juanita Bay Park	RESTROOMS	Entrance to Building	Building Entrance - Door	1	degrees to a position 12 degrees from latch.	Women's Restroom	ADA	404.2.8	\$366
253478	Juanita Bay Park	RESTROOMS	Exterior Access Route	Door	1	The push side of the accessible door does not have the required maneuvering clearances.	Women's Restroom	ADA	404.2; Table 404.2.4.1	\$50
	•					The swinging door does not have a smooth				·
						surface within 10" of the ground measured vertically on the push side extending the full				
253460	Juanita Bay Park	RESTROOMS	Exterior Access Route	Door	2	width of the door.	Men's Restroom	ADA	404.2.10	\$200
						The swinging door does not have a smooth surface within 10" of the ground measured				
						vertically on the push side extending the full				
253475	Juanita Bay Park	RESTROOMS	Exterior Access Route	Door	2	width of the door.	Women's Restroom	ADA	404.2.10	\$200
						The restroom does not have compliant signage			216.2, 703.1,	
						at the door with the International Symbol of			703.2, 703.5,	
253461	Juanita Bay Park	RESTROOMS	Restroom	Restroom/Bathroom-Signage Restroom/Bathroom -	3	Accessibility, raised characters, and Braille.	Men's Restroom	ADA	703.6	\$55
253464	Juanita Bay Park	RESTROOMS	Restroom	Lavatory	3	Pipes are not insulated.	Men's Restroom	ADA	606.5	\$65
253465	Juanita Bay Park	RESTROOMS	Restroom	Restroom/Bathroom - Urinal	3	The urinal dimensions are not compliant.	Men's Restroom	ADA	605.2	\$935
255405	Judilita Bay Park	RESTROOMS	Restroom	Restroom Batmoom - Ormal	•3	The flush control is located on the closed side	Well's Restroom	ADA	603.2	و و و و
						and is more than 48" high, for an obstructed				
253466	Juanita Bay Park	RESTROOMS	Restroom	Restroom/Bathroom - Urinal	3	forward reach range of maximum 20" horizontally.	Men's Restroom	ADA	605.4; 309	\$313
	•			Restroom/Bathroom -		The lavatory is mounted higher than 34" to the				
253467	Juanita Bay Park	RESTROOMS	Restroom	Lavatory	3	higher of the rim or counter. The mirror is mounted higher than 40" above	Men's Restroom	ADA	606.2 and 606.3	\$720
						finish floor to the bottom of the reflective				
252460	luanita Dau Daul	DECEDOOMS	Destroyer	Dantura and /Dathara and Adinasa	2	surface, where it is installed above a lavatory or	Maria Dastra and	404	242.2 5. 602.2	¢200
253468	Juanita Bay Park	RESTROOMS	Restroom	Restroom/Bathroom - Mirror	3	counter.	Men's Restroom	ADA	213.3.5; 603.3 ADA 604.7, 609.3;	\$200
				Restroom/Bathroom - Toilet		WASHINGTON: The toilet paper dispenser		State of	2009 ANSI A117.1-	
253469	Juanita Bay Park	RESTROOMS	Restroom	Stall	3	location is not compliant. The centerline of the toilet in the wheelchair	Men's Restroom	Washington	604.7	\$293
				Restroom/Bathroom - Water		stall is not 16" minimum to 18" maximum from				
253470	Juanita Bay Park	RESTROOMS	Restroom	Closet	3	the sidewall.	Men's Restroom	ADA	604.2	\$630

					Ph	ase 2				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
253471	Juanita Bay Park	RESTROOMS	Restroom	Restroom/Bathroom - Water Closet Restroom/Bathroom - Water	3	The rear grab bar at the water closet is not compliant. The flush control is located on the closed side	Men's Restroom	ADA	604.5.2	\$355
253472	Juanita Bay Park	RESTROOMS	Restroom	Closet	3	and/or is not within reach range.	Men's Restroom	ADA	604.6	\$313
253474	Juanita Bay Park	RESTROOMS	Restroom	Restroom/Bathroom-Signage Restroom/Bathroom -	3	The provided signage is not mounted at the latch side of the door or at a compliant height.	Women's Restroom	ADA	216.2,703.1, 703.2, 703.5	\$55
253479	Juanita Bay Park	RESTROOMS	Restroom	Lavatory Restroom/Bathroom -	3	Pipes are not insulated. The lavatory is mounted higher than 34" to the	Women's Restroom	ADA	606.5	\$65
253480	Juanita Bay Park	RESTROOMS	Restroom	Lavatory	3	higher of the rim or counter. The mirror is mounted higher than 40" above finish floor to the bottom of the reflective surface, where it is installed above a lavatory or	Women's Restroom	ADA	606.2 and 606.3	\$720
253481	Juanita Bay Park	RESTROOMS	Restroom	Restroom/Bathroom - Mirror	3	counter.	Women's Restroom	ADA	213.3.5; 603.3 ADA 604.7, 609.3;	
253482	Juanita Bay Park	RESTROOMS	Restroom	Restroom/Bathroom - Toilet Stall	3	WASHINGTON: The toilet paper dispenser location is not compliant. The centerline of the toilet in the wheelchair	Women's Restroom	State of Washington	2009 ANSI A117.1- 604.7	\$293
253483	Juanita Bay Park	RESTROOMS	Restroom	Restroom/Bathroom - Water Closet Restroom/Bathroom - Water	3	stall is not 16" minimum to 18" maximum from the sidewall. The rear grab bar at the water closet is not	Women's Restroom	ADA	604.2	\$630
253484	Juanita Bay Park	RESTROOMS	Restroom	Closet	3	compliant.	Women's Restroom	ADA	604.5.2	\$355

\$1,286,337

			Pl	hase 3					
ld Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
								WA Bldg Code 51 50 WAC 1101.6; ADA 406; 405.2	-
239449	Brookhaven Park x	Exterior Access Route	Curb Ramp	1	WASHINGTON: The slope of the curb ramp run is not compliant. WASHINGTON: A van stall, access aisle, and	Curb Ramp 1 (CR1)	State of Washington	thru 405.5; Table 405.2; 403.5.1 WA Bldg Code 51	\$0 L-
239450	Brookhaven Park x	Accessible Parking	Parking Space-Van	1	signage are not provided and the slope and/or ground surface is/are not compliant.	On-Street Parking	State of Washington	50 WAC 1101; ADA 502.4, 502.5	\$11,300
239451	Brookhaven Park x	Exterior Access Route	Curb Ramp	1	The parallel curb ramp landing is not compliant.	Curb Ramp 1 (CR1)	ADA	304, 406.4	\$0
239452	Brookhaven Park x	Exterior Access Route	Curb Ramp	1	The curb ramp surface has vertical height changes greater than 1/4" that are not ramped.	Curb Ramp 1 (CR1)	ADA	303, 403.4 WA Bldg Code 51	\$0
239453	Brookhaven Park x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Public Sidewalk to Trash Receptacle	· ·	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$991 L-
239454	Brookhaven Park x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Education Area / Information Signs		50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$1,434 L-
239455	Brookhaven Park x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. The picnic table does not allow a clear space for the picnic table does not allow a clear space for the picnic table of tab		State of Washington	50 WAC 1101.2.1; 403.3	; \$1,434
239456	Brookhaven Park x	Picnic Area	Picnic Table	2	forward wheelchair approach with knee and toe clearance.	Picnic Area	ADA	902.2; 902.4 WA Bldg Code 51	
239395	Bud Homan Park x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. WASHINGTON: A van stall, access aisle, and	Picnic Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$717
240236	Bud Homan Park x	Accessible Parking	Parking Space-Van	1	signage are not provided and the slope and/or ground surface is/are not compliant.	On-street Parking	State of Washington	50 WAC 1101; ADA 502.4, 502.5	\$11,300
								WA Bldg Code 51 50 WAC 1101.6; ADA 406; 405.2	ē
240237	Bud Homan Park x	Exterior Access Route	Curb Ramp	1	WASHINGTON: The slope of the curb ramp run is not compliant.	Curb Ramp 1 (CR1)	State of Washington	thru 405.5; Table 405.2; 403.5.1	\$0
240238	Bud Homan Park x	Exterior Access Route	Curb Ramp	1	The parallel curb ramp landing is not compliant.	Curb Ramp 1 (CR1)	ADA	304, 406.4	\$0
240239 239399	Bud Homan Park x Bud Homan Park x	Exterior Access Route Picnic Area	Curb Ramp Picnic Table	1 4	The curb ramp surface has vertical height changes greater than 1/4" that are not ramped. A compliant picnic table is not provided.	Curb Ramp 1 (CR1) Picnic Area	ADA ADA	303, 403.4 902 WA Bldg Code 51	\$0 \$1,300
243190	Carillon Woods x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 1 (W1)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	; \$3,520
243191	Carillon Woods x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 2 (W2)	State of Washington	50 WAC 1101.2.1; 403.3	; \$4,400

			Ph	hase 3				
ld Facility	Building	Assembly	Туре	Barrier Detail Priority	Location Description	ADA	Ref. Number	Total
							WA Bldg Code 51- 50 WAC 1101.2.1; ADA 406; 405.2	
				WASHINGTON: The clear width of the	ramp is	State of	thru 405.5; Table	
243192	Carillon Woods	x Exterior Access Route	Exterior Accessible Route	 less than 44". WASHINGTON: An exterior accessible remaining 	Playground 1 (PG1)	Washington	405.2; 403.5.1 WA Bldg Code 51-	
243196	Carillon Woods	x Exterior Access Route	Exterior Accessible Route	1 not provided.	Playground 2 (PG2)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$79
243199	Carillon Woods	x Exterior Access Route	Exterior Accessible Route	WASHINGTON: The slopes of the exter accessible route are not compliant.	ior Walkway 3 (W3)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$3,240
				WASHINGTON: An exterior accessible in	oute is	State of	50 WAC 1101.2.1;	
243200	Carillon Woods	x Exterior Access Route	Exterior Accessible Route	 not provided. The ground surface has not been insper 	Playground 3 (PG3) cted and	Washington	403.3	\$79
243193	Carillon Woods	x Playground	Ground Surface - Fibar	2 maintained regularly.	Playground 1 (PG1)	ADA	1008.2	\$905
243195	Carillon Woods	x Playground	Play Component	The number of existing ground level components is less than the required m The ground surface has not been inspe	, ,	ADA	240	\$5,000
243197	Carillon Woods	x Playground	Ground Surface - Fibar	2 maintained regularly. The ground surface has not been insperational control of the c	Playground 2 (PG2)	ADA	1008.2	\$245
243201	Carillon Woods	x Playground	Ground Surface - Fibar	2 maintained regularly. WASHINGTON: The stair treads do not visual contrast of dark-on-light or light-		ADA	1008.2	\$384
243194	Carillon Woods	x Exterior Access Route	Stairs	on the leading 2" of the tread from the remaining portion of the tread surface.	Playground 1 (PG1)	IBC	2009 ANSI A117.1 504.5.1 WA Bldg Code 51-	\$282
				WASHINGTON: An exterior accessible i	oute is	State of	50 WAC 1101.2.1;	
243284	Cedar View Park	x Exterior Access Route	Exterior Accessible Route	1 not provided.	Walkway to Park NE 90th St	Washington	403.3 WA Bldg Code 51-	
243287	Cedar View Park	x Exterior Access Route	Exterior Accessible Route	WASHINGTON: An exterior accessible and provided.	oute is Play Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$0
				WASHINGTON: An exterior accessible i	oute is	State of	50 WAC 1101.2.1;	
243293	Cedar View Park	x Exterior Access Route	Exterior Accessible Route	1 not provided.	Walkway to Park from NE 88th St	_	403.3 WA Bldg Code 51-	
243294	Cedar View Park	x Exterior Access Route	Exterior Accessible Route	WASHINGTON: The slopes of the exter accessible route are not compliant.	ior Walkway to Park from NE 88th St	State of Washington	50 WAC 1101.2.1; 403.3	\$634
				The accessible route has gaps in the su	rface			
243295	Cedar View Park	x Exterior Access Route	Exterior Accessible Route	1 greater than 1/2" wide. WASHINGTON: A van stall, access aisle signage are not provided and the slope		ADA State of	302.3 WA Bldg Code 51- 50 WAC 1101;	\$375 -
243296	Cedar View Park	x Accessible Parking	Parking Space-Van	1 ground surface is/are not compliant. The entry points to a play component transfer to entry points or seats is lowe	On-Street Parking requiring	Washington	ADA 502.4, 502.5	\$11,300
243288	Cedar View Park	x Playground	Play Component	2 11" and higher than 24". A turning space is not provided at a sch	Play Area	ADA	1008.4.4	\$400
243289	Cedar View Park	x Playground	Play Component - Swing	2 swing.	Play Area	ADA	1008.4.1	\$0

				Ph	ase 3					
ld Facility	Building		Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243290	Cedar View Park	х	Playground	Ground Surface-Fibar	2	The ground surface has not been inspected and maintained regularly. Clear ground space is not provided at each ground play component, and each elevated play	Play Area	ADA	1008.2	\$750
243291	Cedar View Park	x	Playground	Play Component	2	component connected by a ramp.	Play Area	ADA	1008.4.2	\$0
243285	Cedar View Park	X	Picnic Area	Picnic Table	4	A compliant picnic table is not provided. WASHINGTON: The slopes of the exterior	Picnic Table	ADA State of	902 WA Bldg Code 51- 50 WAC 1101.2.1;	
240705	Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant. WASHINGTON: A van stall, access aisle, and signage are not provided and the slope and/or	Northeast Entrance Walkway	Washington State of	403.3 WA Bldg Code 51- 50 WAC 1101;	\$1,500
240706	Mark Twain Park	x	Accessible Parking	Parking Space-Van	1	ground surface is/are not compliant. The accessible route does not have 80" vertical	Parking	Washington	ADA 502.4, 502.5	\$11,300
240707	Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	clearance.	Northeast Entrance Walkway	ADA	307.4 WA Bldg Code 51	
240708	Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. WASHINGTON: The slopes of the exterior	Southeast Entrance Walkway	State of Washington State of	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$3,000
240709	Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	East Loop Walk	Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$6,000
240710	Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route does not have 80" vertical	North Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3	\$360
240711	Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	clearance.	North Loop Walk	ADA	307.4 WA Bldg Code 51	
240712	Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	North Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$900
240713	Mark Twain Park	X	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	North Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3	\$4,200
						The accessible route does not have 80" vertical	·	_		
240714	Mark Twain Park	х	Exterior Access Route	Exterior Accessible Route	1	clearance. WASHINGTON: The slopes of the exterior	North Loop Walk	ADA State of	307.4 WA Bldg Code 51- 50 WAC 1101.2.1;	
240715	Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant. The accessible route has gaps in the surface	North Loop Walk	Washington	403.3	\$4,200
240716	Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide.	North Loop Walk	ADA	302.3 WA Bldg Code 51	\$100
240717	Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	North Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$143
240718	Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	North Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$4,800
240719	Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	North Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$3,000
240720	Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Loop Walk to Natural Area	State of Washington	50 WAC 1101.2.1; 403.3	

			Pl	nase 3					
ld Facility	Building	Assembly	Туре	Barrier Detail Priority		Location Description	ADA	Ref. Number	Total
240721	Mark Twain Park x	Exterior Access Route	Exterior Accessible Route	WASHINGTO	ON: The slopes of the exterior ute are not compliant.	Walkway from Loop Walk to Natural Area	State of Washington	WA Bldg Code 51 50 WAC 1101.2.1; 403.3	\$4,000
240722	Mark Twain Park x	Exterior Access Route	Exterior Accessible Route		ON: The slopes of the exterior ute are not compliant.	Northeast Walkway from Natural Area	State of Washington	WA Bldg Code 51 50 WAC 1101.2.1; 403.3	
240723	Mark Twain Park x	Exterior Access Route	Exterior Accessible Route		areas of vertical level changes in " that are not ramped.	Northeast Walkway from Natural Area	ADA	303 WA Bldg Code 51	\$80
240724	Mark Twain Park x	Exterior Access Route	Exterior Accessible Route	1 accessible rou	DN: The slopes of the exterior ute are not compliant.	Northwest Walkway from Natural Area Northwest Walkway from Natural	State of Washington	50 WAC 1101.2.1; 403.3	
240725	Mark Twain Park x	Exterior Access Route	Exterior Accessible Route	1 greater than	- 1	Area	ADA	302.3 WA Bldg Code 51	\$100
240726	Mark Twain Park x	Exterior Access Route	Exterior Accessible Route	1 accessible rou	N: The slopes of the exterior ute are not compliant. areas of vertical level changes in	Northwest Walkway from Natural Area Northwest Walkway from Natural	State of Washington	50 WAC 1101.2.1; 403.3	\$600
240727	Mark Twain Park x	Exterior Access Route	Exterior Accessible Route		" that are not ramped.	Area	ADA	303 WA Bldg Code 51	\$80
240729	Mark Twain Park x	Exterior Access Route	Exterior Accessible Route	WASHINGTO not provided.	ON: An exterior accessible route is	Picnic Table near West Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$896
240730	Mark Twain Park x	Exterior Access Route	Exterior Accessible Route	1 accessible rou	ON: The slopes of the exterior ute are not compliant.	West Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3	\$7,800
240731	Mark Twain Park x	Exterior Access Route	Exterior Accessible Route	1 excess of 1/4	" that are not ramped.	West Loop Walk	ADA	303 WA Bldg Code 51	
240732	Mark Twain Park x	Exterior Access Route	Exterior Accessible Route		ON: The slopes of the exterior ute are not compliant.	West Loop Walkway to NE 106th Place	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$2,500
240734	Mark Twain Park x	Exterior Access Route	Exterior Accessible Route	1 accessible rou	ON: The slopes of the exterior ute are not compliant. Je route does not have 80" vertical	South Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3	\$6,000
240735	Mark Twain Park x	Exterior Access Route	Exterior Accessible Route	1 clearance.		South Loop Walk	ADA	307.4 WA Bldg Code 51	
240736	Mark Twain Park x	Exterior Access Route	Exterior Accessible Route		N: The slopes of the exterior ute are not compliant.	South Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$1,200
240737	Mark Twain Park x	Exterior Access Route	Exterior Accessible Route		ON: The slopes of the exterior ute are not compliant.	South Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$4,800
240738	Mark Twain Park x	Exterior Access Route	Exterior Accessible Route		ON: The slopes of the exterior ute are not compliant.	South Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$1,800
240739	Mark Twain Park x	Exterior Access Route	Exterior Accessible Route	1 accessible rou	ON: The slopes of the exterior ute are not compliant.	South Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3	
240740	Mark Twain Park x	Exterior Access Route	Exterior Accessible Route	1 clearance.	ne route does not have 80 Vertical	South Loop Walk	ADA	307.4	\$200

					Pł	nase 3					
Id	Facility	Building		Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
240741		Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	South Loop Walk	State of Washington	WA Bldg Code 51 50 WAC 1101.2.1; 403.3	
240742		Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	Sidewalk has areas of vertical level changes in excess of 1/4" that are not ramped.	Walkway to Ground Play Components	ADA	303 WA Bldg Code 51	\$180
240748		Mark Twain Park	х	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Ground Play Components to Basketball Court	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$3,964
240750		Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The clear width of the exterior accessible route is less than 44". The accessible route has gaps in the surface	Walkway from Ground Play Components to Basketball Court Walkway from Ground Play	State of Washington	50 WAC 1101.2.1; 403.3	\$200
240751		Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide. Sidewalk has areas of vertical level changes in	Components to Basketball Court Walkway to Picnic Table and	ADA	302.3	\$119
240752		Mark Twain Park	Х	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Basketball Court	ADA	303 WA Bldg Code 51	
240753		Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. Sidewalk has areas of vertical level changes in	Walkway to Picnic Table and Basketball Court	State of Washington	50 WAC 1101.2.1; 403.3	\$1,200
240757		Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped. Sidewalk has areas of vertical level changes in	Basketball Court	ADA	303	\$396
240758		Mark Twain Park	X	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Walkway to Elevated Play Structure		303 WA Bldg Code 51	
240759		Mark Twain Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. An accessible route does not directly connect	Walkway to Elevated Play Structure	State of Washington	50 WAC 1101.2.1; 403.3	\$1,189
243930		Mark Twain Park	x	Basketball Court	Sport Court	1	each side of the court outside of play lines. The picnic table does not allow a clear space for	Basketball Court	ADA	206.2.12; 403	\$1,192
240728		Mark Twain Park	x	Picnic Area	Picnic Table	2	forward wheelchair approach with knee and toe clearance.	Picnic Table near West Loop Walk	ADA	902.2; 902.4	\$1,300
240733		Mark Twain Park	x	Site Furnishings	Trash Receptacle Without Operable Lid	2	A trash receptacle is not located on an accessible route and within reach range. An accessible route to at least one of each type	West Loop Walkway to NE 106th Place	ADA	228.1, 308	\$150
240743		Mark Twain Park	X	Playground	Exterior Accessible Route	2	of ground component within the play area has not been provided. Clear ground space is not provided at each	Ground Play Components	ADA	240.2.1.1	\$0
240744		Mark Twain Park	x	Playground	Play Component	2	ground play component, and each elevated play component connected by a ramp. A turning space is not provided at a school-age	Ground Play Components	ADA	1008.4.2	\$0
240746		Mark Twain Park	х	Playground	Play Component - Swing	2	swing. The ground surface has not been inspected and	Ground Play Components	ADA	1008.4.1	\$0
240747		Mark Twain Park	x	Playground	Ground Surface-Fibar	2	maintained regularly. The entry points to a play component requiring	Ground Play Components	ADA	1008.2	\$1,000
240749		Mark Twain Park	X	Playground	Play Component	2	transfer to entry points or seats is lower than 11" and higher than 24". The picnic table does not allow a clear space for forward wheelchair approach with knee and toe		ADA	1008.4.4	\$400
240754		Mark Twain Park	х	Picnic Area	Picnic Table	2	clearance. The ground surface has not been inspected and	Picnic Table at Play Area	ADA	902.2; 902.4	\$496
240761		Mark Twain Park	x	Playground	Ground Surface-Fibar	2	maintained regularly.	Elevated Play Component	ADA	1008.2	\$400

					Pł	nase 3					
Id	Facility	Building		Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
240762		Mark Twain Park	x	Playground	Transfer System	2	A transfer space is not provided at the platform. The transfer platform connecting to elevated play elements has a non-compliant height lower	Elevated Play Component	ADA	1008.3.1.3	\$0
240763		Mark Twain Park	x	Playground	Transfer System	2	than 11" or higher than 18".	Elevated Play Component	ADA	1008.3.1	\$5,000
240755		Mark Twain Park	х	Picnic Area	Picnic Table	4	A compliant picnic table is not provided.	Picnic Table at Play Area	ADA	902	\$1,300
	North Kirkland	North Kirkland									
243435	Community Center and	North Kirkland Community Center	x	Exterior Access Route	Stairs	1	Handrail extensions are not compliant.	Stair 4 (ST4)	ADA	505.1	\$652
243433	North Kirkland	community center	^	Exterior Access Noute	Stall3	-	Transfer extensions are not compliant.	Stan 4 (314)	ADA	505.1	7 032
	Community Center and	North Kirkland									
243443	Park	Community Center	x	Exterior Access Route	Stairs	1	Handrails are not compliant.	Stair 5 (ST5)	ADA	505	\$1,956
	North Kirkland Community Center and	North Kirkland					The hardware at the accessible door (including sliding doors - both sides) requires tight grasping, pinching or twisting of the wrist to				
243444	Park	Community Center	Х	Entrance to Building	Building Entrance - Door	1	operate OR is mounted below 34" or above 48".	Community Center	ADA	309, 404.2.7	\$2,028
	North Kirkland						Protruding objects in the 27" to 80" range above finished floor protrude more than 4" into				
	Community Center and	North Kirkland					the circulation path along the interior accessible	Community Center Upper Level			
243455	•	Community Center	х	Interior Access Route	Protruding Object	1	route.	Entrance Lobby	ADA	307.2	\$728
243479	North Kirkland Community Center and Park	North Kirkland Community Center	x	Interior Access Route	Door	1	The hardware at the accessible door (including sliding doors - both sides) requires tight grasping, pinching or twisting of the wrist to operate OR is mounted below 34" or above 48".	Community Center Throughout Building	ADA	309, 404.2.7	\$1,465
	North Kirkland							•			
243480	Community Center and	North Kirkland Community Center	x	Interior Access Route	Elevator	1	The building does not have elevator access between stories.	Community Center	ADA	206.2.3	\$80,000
243400	North Kirkland	community center	^	menor Access noute	Licvator	-	between stories.	community center	ADA	200.2.5	300,000
	Community Center and	North Kirkland					The interior accessible route has less than 36"	Community Center Lower Level		403.5.1 thru	
243481	Park	Community Center	х	Interior Access Route	Accessible Route	1	clear width.	Classroom 1	ADA	403.5.3	\$540
	North Kirkland						Protruding objects in the 27" to 80" range above finished floor protrude more than 4" into				
	Community Center and	North Kirkland					the circulation path along the interior accessible	Community Center Lower Level			
243484	•	Community Center	х	Interior Access Route	Protruding Object	1	route.	Classroom 1	ADA	307.2	\$728
	North Kirkland										
	Community Center and	North Kirkland			0		The height of controls throughout the common				4=00
243485	Park North Kirkland	Community Center	Х	Interior Access Route	Controls And Dispensers	1	area are not compliant.	Community Center Lower Level	ADA	308	\$500
	Community Center and	North Kirkland					The height of controls throughout the common	Community Center Lower Level			
243509	Park	Community Center	х	Interior Access Route	Controls And Dispensers	1	area are not compliant.	Movement & Dance Room	ADA	308	\$500
	North Kirkland	No abagath of					The health of a constant	C			
243511	Community Center and	North Kirkland Community Center	x	Interior Access Route	Controls And Dispensers	1	The height of controls throughout the common area are not compliant.	Community Center Throughout Building	ADA	308	\$500
243311	North Kirkland	Community Center	^	intendi Access noute	Controls And Dispensers	1	The accessible door with door closer has a	Dulluling	ADA	300	3300
	Community Center and	North Kirkland					sweep period of less than 5 seconds from 90	Community Center Throughout			
243514	Park	Community Center	x	Interior Access Route	Door	1	degrees to a position 12 degrees from latch.	Building	ADA	404.2.8	\$6,588

					Pł	nase 3					
Id	Facility	Building		Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
	North Kirkland	North Kirkland				,	The besides of constraint throughout the constraint	Community Contant Throughout			
243516	Community Center and Park	Community Center	x	Interior Access Route	Controls And Dispensers	1	The height of controls throughout the common area are not compliant.	Community Center Throughout Building	ADA	308	\$2,000
	North Kirkland	No alle 12 d le cal						Comment Controlleration			
243517	Community Center and Park	North Kirkland Community Center	X	Interior Access Route	Controls And Dispensers	1	Clear space is not provided at the control or operating mechanism.	Community Center Upper Level Entrance Lobby	ADA	305	\$500
	North Kirkland							,			
243518	Community Center and Park	North Kirkland Community Center	x	Interior Access Route	Controls And Dispensers	1	The height of controls throughout the common area are not compliant.	Community Center Throughout Building	ADA	308	\$2,500
	North Kirkland	•			·			J		WA Bldg Code 51-	
243519	Community Center and Park	North Kirkland Community Center	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Community Center Library	State of Washington	50 WAC 1101.2.1; 403.3	\$99
243313	North Kirkland	community conten		Externor ribbess ribute	Exterior redessione reduce	-	ince provided.	community center Elbrury	rrasiii.g.co	.00.0	γSS
244469	Community Center and	North Kirkland Community Center	x	Exterior Access Route	Stairs	1	Stairs have open risers.	Stair 5 (ST5)	ADA	504.3	\$7,560
244409	raik	Community Center	^	Exterior Access Noute	Stalls	1	Items requiring an unobstructed side reach	Stail 5 (515)	ADA	304.3	77,500
	North Kirkland	Ni anth IV: alaba al					motion are higher than 48" maximum and/or				
243445	Community Center and Park	North Kirkland Community Center	x	Exterior Access Route	Reach Range	2	lower than 15" minimum height above finish floor.	Community Center	ADA	308, 309	\$180
	North Kirkland	N. H. W. H. L.									
243452	Community Center and Park	North Kirkland Community Center	x	Interior Access Route	Interior Access Route	2	***** *******************************	Community Center Upper Level Entrance Lobby	ADA	904.4	\$1,805
	North Kirkland										
243453	Community Center and Park	North Kirkland Community Center	x	Common Areas	Vending Machine	2	The vending machines have operable parts which are not within reach range.	Community Center Upper Level Entrance Lobby	ADA	228.1; 305; 308; 309	\$3,254
		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,					Tactile means of egress signage is not provided	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,			, - , -
	North Kirkland Community Center and	North Kirkland					at the latch side of the door. (Applies to designated egress stairways, exit doors, areas of	Community Center Throughout			
243456	•	Community Center	x	Interior Access Route	Signage	2	refuge)	Building	ADA	216.4, 703	\$550
	North Kirkland						The restroom circulation path is not free of objects protruding more than 4" from wall in the				
	Community Center and	North Kirkland					space between 27" and 80" height above finish	Community Center Upper Level			
243468	Park	Community Center	х	Restroom	Protruding Object	2	floor. The restroom circulation path is not free of	Women's Restroom	ADA	307.2	\$600
	North Kirkland						objects protruding more than 4" from wall in the				
242470	Community Center and	North Kirkland		Destructor	Destructive Object	2	space between 27" and 80" height above finish	Community Center Upper Level	ADA	207.2	Ć10C
243470	North Kirkland	Community Center	х	Restroom	Protruding Object	2	floor. The sales or service counter does not have an	Men's Restroom	ADA	307.2	\$186
	Community Center and	North Kirkland					accessible portion with maximum 36" height	Community Center Multipurpose			44.005
243477	Park North Kirkland	Community Center	х	Common Areas	Counter	2	surface above finish floor or ground. The surface of the door within 10 inches of the	Room	ADA	904.4	\$1,805
	Community Center and	North Kirkland					finish floor or ground for the full width of the				
243478	Park North Kirkland	Community Center	х	Entrance to Building	Building Entrance - Door	2	door on the push side is not smooth. The sink rim is higher than 34", and does not	Community Center Entrance Doors	ADA	404.2.10	\$1,600
	Community Center and	North Kirkland					have knee and toe clearance (does not apply to	Community Center Lower Level			
243482	Park	Community Center	X	Interior Access Route	Sink	2	mop basins, utility sinks, or bar sinks). The restroom circulation path is not free of	Classroom 1	ADA	306.2 and 606.3	\$720
	North Kirkland						objects protruding more than 4" from wall in the				
2/2/01	Community Center and	North Kirkland	v	Pastroom	Protruding Object	า	space between 27" and 80" height above finish floor.	Community Center Lower Level Men's & Women's Restroom	ADA	307.2	\$600
243491	raiK	Community Center	Х	Restroom	Protruding Object	2	noor.	ivien s & women's Restroom	ADA	307.2	\$600

						Phase 3					
Id	Facility	Building		Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243506	North Kirkland Community Center and Park North Kirkland	North Kirkland Community Center	х	Interior Access Route	Signage	2	The existing signage is not mounted at the latch side of the door or at a compliant height. The sink rim is higher than 34", and does not	Community Center Throughout Building	ADA	703.4	\$880
243507	Community Center and	North Kirkland Community Center	x	Common Areas	Sink	2	have knee and toe clearance (does not apply to mop basins, utility sinks, or bar sinks). The sink rim is higher than 34", and does not	Community Center Lower Level Art Room	ADA	306.2 and 606.3	\$720
243508	Community Center and Park North Kirkland	North Kirkland Community Center	x	Common Areas	Sink	2	have knee and toe clearance (does not apply to mop basins, utility sinks, or bar sinks).	Community Center Lower Level Movement & Dance Room	ADA	306.2 and 606.3	\$720
243512	Community Center and Park North Kirkland	North Kirkland Community Center	x	Interior Access Route	Door	2	The bottom of the door vision light is higher than 43" and less than 66".	Community Center Multipurpose Room	ADA	404.2.11	\$2,600
243515		North Kirkland Community Center	x	Common Areas	Assembly Area	2	An assistive listening system is required, but not provided. WASHINGTON: The stair treads do not have	Community Center Multipurpose Room	ADA	216.10; 219; 706	\$250
243433	North Kirkland Community Center and Park	North Kirkland Community Center	х	Exterior Access Route	Stairs	3	visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have	Stair 3 (ST3)	IBC	2009 ANSI A117.1 504.5.1	1- \$211
243434	North Kirkland Community Center and Park	North Kirkland Community Center	x	Exterior Access Route	Stairs	3	visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have	Stair 4 (ST4)	IBC	2009 ANSI A117.1 504.5.1	1- \$317
243442	North Kirkland Community Center and Park North Kirkland	North Kirkland Community Center	x	Exterior Access Route	Stairs	3	visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the remaining portion of the tread surface.	Stair 5 (ST5)	IBC	2009 ANSI A117.1 504.5.1	1- \$317
243457	Community Center and	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - Signage	3	The provided signage is not mounted at the latch side of the door or at a compliant height.	Community Center Upper Level Men's & Women's Restroom	ADA	216.2,703.1, 703.2, 703.5	\$110
243458	North Kirkland	North Kirkland Community Center	x	Restroom	Restroom/B <mark>ath</mark> room - D	Door 3	The force required to open the interior, hinged, non-fire door is more than 5 pounds. The accessible door with door closer has a	Community Center Upper Level Men's & Women's Restroom	ADA	404.2.9	\$732
243459	North Kirkland	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - D	Door 3	sweep period of less than 5 seconds from 90 degrees to a position 12 degrees from latch.	Community Center Upper Level Men's & Women's Restroom	ADA	404.2.8	\$0
243460	Community Center and Park North Kirkland	North Kirkland Community Center	х	Restroom	Restroom/Bathroom - D	Door 3	The pull side of the accessible door does not have the required maneuvering clearances.	Community Center Upper Level Women's Restroom	ADA	404.2; Table 404.2.4.1	\$1,250
243461	Community Center and Park North Kirkland	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - Lavatory	3	Pipes are not insulated.	Community Center Upper Level Men's & Women's Restroom	ADA	606.5	\$130
243462	Community Center and Park North Kirkland	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - V Closet	Water 3	The height of the water closet is not 17" minimum to 19" maximum above finished floor.	Community Center Men's & Women's Restroom	ADA	604.4	\$1,260
243463	Community Center and Park	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - V Closet	Water 3	The flush control is located on the closed side and/or is not within reach range.	Community Center Upper Level Women's Restroom	ADA	604.6	\$313

					Phas	e 3					
Id	Facility	Building		Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243464	North Kirkland Community Center and Park North Kirkland	North Kirkland Community Center	х	Restroom	Restroom/Bathroom - Water Closet	3	The centerline of the toilet in the wheelchair stall is not 16" minimum to 18" maximum from the sidewall.	Community Center Upper Level Women's Restroom	ADA	604.2	\$630
243465	Community Center and	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - Water Closet	3	The grab bars at the water closet are not compliant.	Community Center Upper Level Women's Restroom	ADA	604.5.2	\$710
243466	Community Center and Park	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - Coat Hook	3	The coat hook is not within an allowable reach range.	Community Center Upper Level Men's & Women's Restroom	ADA	308	\$230
243467		North Kirkland Community Center	x	Restroom	Restroom/Bathroom-Toilet Stall	3	The wheelchair stall with a floor mounted water closet, in a multi-stall restroom, is less than 60" wide and 59" deep.	Community Center Upper Level Men's & Women's Restroom	ADA	604.8.1.1	\$2,736
243469	North Kirkland Community Center and Park	North Kirkland Community Center	x	Restroom	Controls And Dispensers	3	The height of controls are not compliant.	Community Center Upper Level Women's Restroom	ADA	606.1; 309.3	\$400
243471		North Kirkland Community Center	x	Restroom	Controls And Dispensers	3	The height of controls are not compliant.	Community Center Upper Level Men's Restroom	ADA	606.1; 309.3	\$200
243472		North Kirkland Community Center	x	Restroom	Restroom/Bathroom-Door	3	The hardware at the wheelchair stall door is not compliant.	Community Center Upper Level Men's Restroom	ADA	309, 404.2.7, 604.8.1.2	\$293
243473	North Kirkland Community Center and Park	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - Water Closet	3	The rear grab bar at the water closet is not compliant.	Community Center Upper Level Men's Restroom	ADA	604.5.2	\$355
243474	North Kirkland Community Center and Park	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - Toilet Stall	3	WASHINGTON: A vertical side grab bar is not present in the wheelchair stall.	Community Center Upper Level Men's & Women's Restroom	ANSI A117.1	2009 ANSI A117.1- 604.5.1 and A117.1-604.9.6	\$710
243475	North Kirkland Community Center and	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - Water Closet	3	WASHINGTON: The toilet paper dispenser location is not compliant.	Community Center Upper Level Men's Restroom	State of Washington	ADA 604.7, 609.3; 2009 ANSI A117.1- 604.7	
243476	North Kirkland Community Center and	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - Door	3	The push side of the door does not have the	Community Center Upper Level Men's Restroom	ADA	404.2.4	\$1,250
	North Kirkland Community Center and	North Kirkland			Restroom/Bathroom -		required maneuvering clearances. The provided signage is not mounted at the	Community Center Lower Level		216.2,703.1,	
243486	North Kirkland Community Center and	Community Center North Kirkland	X	Restroom	Signage	3	latch side of the door or at a compliant height. The force required to open the interior, hinged,	Men's & Women's Restroom Community Center Lower Level	ADA	703.2, 703.5	\$110
243487	Park North Kirkland Community Center and	Community Center North Kirkland	х	Restroom	Restroom/Bathroom - Door	3	non-fire door is more than 5 pounds. The accessible door with door closer has a sweep period of less than 5 seconds from 90	Men's & Women's Restroom Community Center Lower Level	ADA	404.2.9	\$732
243488	Park North Kirkland Community Center and	Community Center North Kirkland	X	Restroom	Restroom/Bathroom - Door Restroom/Bathroom -	3	degrees to a position 12 degrees from latch.	Men's & Women's Restroom Community Center Lower Level	ADA	404.2.8	\$0
243489	Park North Kirkland	Community Center	x	Restroom	Lavatory	3	Pipes are not insulated.	Men's & Women's Restroom	ADA	606.5	\$130
243490	Community Center and Park	North Kirkland Community Center	x	Restroom	Controls And Dispensers	3	Controls on dispensers are not compliant.	Community Center Lower Level Men's & Women's Restroom	ADA	606.1; 309.4	\$0

					Phas	se 3					
Id	Facility	Building		Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243492	North Kirkland Community Center and Park North Kirkland	North Kirkland Community Center	х	Restroom	Restroom/Bathroom-Door	3	The hardware at the wheelchair stall door is not compliant. The wheelchair stall with a floor mounted water	Community Center Lower Level Men's & Women's Restroom	ADA	309, 404.2.7, 604.8.1.2	\$586
243493	Community Center and Park North Kirkland	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - Toilet Stall	3	closet, in a multi-stall restroom, is less than 60" wide and 59" deep.	Community Center Lower Level Women's Restroom	ADA	604.8.1.1	\$1,368
243494	Community Center and	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - Water Closet	3	The side grab bar at the water closet is not compliant.	Community Center Lower Level Men's & Women's Restroom	ADA	604.5.1	\$710
243495	Community Center and Park North Kirkland	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - Water Closet	3	The height of the water closet is not 17" minimum to 19" maximum above finished floor.	Community Center Lower Level Men's & Women's Restroom	ADA	604.4 ADA 604.7, 609.3;	\$1,260
243496	Community Center and	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - Water Closet	3	WASHINGTON: The toilet paper dispenser location is not compliant.	Community Center Lower Level Men's & Women's Restroom	State of Washington	2009 ANSI A117.1- 604.7	\$586
243497		North Kirkland Community Center	x	Restroom	Restroom/Bathroom - Toilet Stall	3	WASHINGTON: A vertical side grab bar is not present in the wheelchair stall.	Community Center Lower Level Men's & Women's Restroom	ANSI A117.1	2009 ANSI A117.1- 604.5.1 and A117.1-604.9.6	\$710
243499	North Kirkland Community Center and Park North Kirkland	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - Coat Hook	3	The coat hook is not within an allowable reach range.	Community Center Lower Level Women's Restroom	ADA	308	\$115
243500	Community Center and Park North Kirkland	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - Coat Hook	3	The coat hook is not within an allowable reach range. The wheelchair stall with a floor mounted water	Community Center Lower Level Men's & Women's Restroom	ADA	308	\$230
243501	North Kirkland	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - Toilet Stall	3	closet, in a multi-stall restroom, is less than 60" wide and 59" deep.	Community Center Lower Level Men's Restroom	ADA	604.8.1.1	\$1,368
243502	Community Center and Park North Kirkland	North Kirkland Community Center	х	Restroom	Restroom/Bathroom - Water Closet	3	The flush control is located on the closed side and/or is not within reach range.	Community Center Lower Level Men's Restroom	ADA	604.6	\$313
243503	Community Center and Park North Kirkland	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - Water Closet	3	The rear grab bar at the water closet is not compliant. The mirror is mounted higher than 35" above finish floor to the bottom of the reflective	Community Center Lower Level Men's Restroom	ADA	604.5.2	\$355
243504	Community Center and Park	North Kirkland Community Center	x	Restroom	Restroom/Bathroom - Mirror	3	surface, where it is not installed above a lavatory or counter. The minimum number of drinking fountains is not provided. If the minimum number is	Community Center Lower Level Men's & Women's Restroom	ADA	213.3.5; 603.3	\$400
243454	North Kirkland Community Center and Park North Kirkland	North Kirkland Community Center	x	Interior Access Route	Drinking Fountain/Water Cooler	4	provided, two levels or a hi-lo are not provided. If more than 2 are provided, less than 50% are high or less than 50% are low.	Community Center Upper Level Entrance Lobby	ADA	211.1; 211.2; 602; 309	\$5,440
243483	Community Center and Park	North Kirkland Community Center	x	Interior Access Route	Controls And Dispensers	4	Controls and/or dispensers are not within an allowable reach range.	Community Center Lower Level Classroom 1	ADA	606.1; 308	\$1,098

					Pha	ise 3					
Id	Facility	Building		Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243505	North Kirkland Community Center and Park North Kirkland	North Kirkland Community Center	х	Interior Access Route	Drinking Fountain/Water Cooler	4	The minimum number of drinking fountains is not provided. If the minimum number is provided, two levels or a hi-lo are not provided. If more than 2 are provided, less than 50% are high or less than 50% are low.	Community Center Lower Level	ADA	211.1; 211.2; 602; 309	\$5,440
243510	Community Center and Park North Kirkland Community Center and	North Kirkland Community Center	x	Interior Access Route	Controls And Dispensers	4	Controls and/or dispensers are not within an allowable reach range. WASHINGTON: Signage is not located at the required height for the van accessible space or	Community Center Throughout Building	ADA	606.1; 308 502.6; WA Bldg Code 51-50 WAC	\$2,000
243389	•	North Kirkland Park	х	Accessible Parking	Parking Space - Van	1	washington: A van stall, access aisle, and signage are not provided and the slope and/or	Parking Lot 1 - Stalls P1 & P2	ADA State of	1101.2.6 WA Bldg Code 51- 50 WAC 1101;	\$560
243391	•	North Kirkland Park	х	Accessible Parking	Parking Space - Van	1	ground surface is/are not compliant. WASHINGTON: A van stall, access aisle, and signage are not provided and the slope and/or	Parking Lot 1 - Stall P1	Washington State of	ADA 502.4, 502.5 WA Bldg Code 51- 50 WAC 1101;	\$11,300
243393	·	North Kirkland Park	х	Accessible Parking	Parking Space - Van	1	ground surface is/are not compliant. The accessible route has gaps in the surface	Parking Lot 1 - Stall P2	Washington	ADA 502.4, 502.5	\$11,300
243395	•	North Kirkland Park	х	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide. WASHINGTON: The slopes of the exterior	Drinking Fountain 1 (DF1)	ADA State of	302.3 WA Bldg Code 51- 50 WAC 1101.2.1;	\$220
243400	·	North Kirkland Park	х	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant. WASHINGTON: The slopes of the exterior	Walkway 1 (W1)	Washington State of	403.3 WA Bldg Code 51- 50 WAC 1101.2.1;	\$23,943
243401	•	North Kirkland Park	х	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant. Sidewalk has areas of vertical level changes in	Walkway 2 (W2)	Washington	403.3	\$32,980
243402	,	North Kirkland Park	х	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped. WASHINGTON: The slopes of the exterior	Walkway 2 (W2)	ADA State of	303 WA Bldg Code 51- 50 WAC 1101.2.1;	\$159
243405	Park North Kirkland	North Kirkland Park	X	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Walkway 3 (W3)	Washington	403.3 WA Bldg Code 51- 50 WAC 1101.2.1;	\$10,148
243406	North Kirkland	North Kirkland Park	х	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 4 (W4)	State of Washington	403.3	\$12,843
243408	Community Center and Park	North Kirkland Park	х	Restroom	Restroom/Bathroom - Door	1	The maneuvering clearance at the accessible door is not level and clear.	Unisex Restroom (URR)	ADA	305.2; 404.2	\$1,250
	North Kirkland Community Center and	North Will 15			D		WASHINGTON: The slopes of the ramp are not	D 4 /04)	State of	WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2 thru 405.5; Table	
243415	North Kirkland Community Center and	North Kirkland Park	X	Exterior Access Route	Ramp	1	compliant. WASHINGTON: Handrails are not provided where the ramp rises more than 6" or are not	Ramp 1 (R1)	Washington State of	405.2; 403.5.1 ADA 505.6; WA Bldg Code 51-50	\$33,100
243416	rafK	North Kirkland Park	Х	Exterior Access Route	Ramp	1	compliant.	Ramp 1 (R1)	Washington	WAC 1101.2.1	\$8,150

					Ph	ase 3					
Id	Facility	Building		Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
	North Kirkland									WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2	
	Community Center and						WASHINGTON: The slope of the curb ramp run		State of	thru 405.5; Table	
243417	Park North Kirkland Community Center and	North Kirkland Park	х	Exterior Access Route	Curb Ramp	1	is not compliant. The adjacent surfaces at transitions to adjoining walks, gutters and streets at the curb ramp are	Curb Ramp 1 (CR1)	Washington	405.2; 403.5.1	\$1,750
243418	Park North Kirkland	North Kirkland Park	x	Exterior Access Route	Curb Ramp	1	not at the same level. WASHINGTON: A van stall and access aisle are	Curb Ramp 2 (CR2)	ADA State of	303; 406.2	\$1,750
243419	North Kirkland	North Kirkland Park	x	Accessible Parking	Parking Space - Van	1	not marked and signage is not provided. WASHINGTON: A van stall, access aisle, and	Parking Lot 2	State of Washington	WA Bldg Code 51- 50 WAC 1101 WA Bldg Code 51-	\$1,400
243420	North Kirkland	North Kirkland Park	х	Accessible Parking	Parking Space-Van	1	signage are not provided and the slope and/or ground surface is/are not compliant.	Parking Lot 3 - Stall P3	State of Washington	50 WAC 1101; ADA 502.4, 502.5 WA Bldg Code 51-	\$11,300
243423	North Kirkland	North Kirkland Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Picnic Area 1 (PA1)	State of Washington	50 WAC 1101.2.1; 403.3	\$1,183
243425	North Kirkland	North Kirkland Park	x	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided.	Stair 1 (ST1)	ADA	505	\$1,956
243427	North Kirkland	North Kirkland Park	х	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided.	Stair 2 (ST2)	ADA	505	\$7,824
243428	North Kirkland	North Kirkland Park	x	Exterior Access Route	Stairs	1	Treads have slopes greater than 1:48.	Stair 2 (ST2)	ADA	504.2, 504.4 WA Bldg Code 51-	\$9,180
243429	Community Center and Park North Kirkland	North Kirkland Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Basketball Court	State of Washington	50 WAC 1101.2.1; 403.3 206.2.12; 403; WA Bldg Code 51-	\$2,957
243430	Community Center and	North Kirkland Park	x	Basketball Court	Sport Court	1	An accessible route does not directly connect each side of the court outside of play lines.	Basketball Court	ADA	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$2,500
243432	Community Center and	North Kirkland Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Parking Lot 3	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$1,540
243437	Community Center and Park	North Kirkland Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 5 (W5)	State of Washington	50 WAC 1101.2.1; 403.3	\$1,903
	North Kirkland									WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2	
243438	Community Center and	North Kirkland Park	x	Exterior Access Route	Ramp	1	WASHINGTON: The slopes of the ramp are not compliant. WASHINGTON: Handrails are not provided	Ramp 2 (R2)	State of Washington	thru 405.5; Table 405.2; 403.5.1 ADA 505.6; WA	\$17,212
243439	Community Center and	North Kirkland Park	x	Exterior Access Route	Ramp	1	where the ramp rises more than 6" or are not compliant.	Ramp 2 (R2)	State of Washington	Bldg Code 51-50 WAC 1101.2.1	\$9,128

					Pha	se 3					
Id	Facility	Building		Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243446	North Kirkland Community Center and Park North Kirkland	North Kirkland Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. WASHINGTON: A van stall, access aisle, and	Crosswalk 1 (CW1)	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$3,500
243447	North Kirkland	North Kirkland Park	x	Accessible Parking	Parking Space - Van	1	signage are not provided and the slope and/or ground surface is/are not compliant. WASHINGTON: A car stall, access aisle, and	Community Center Street Parking Stall P4	State of Washington	50 WAC 1101; ADA 502.4, 502.5 WA Bldg Code 51-	\$11,300
243450	North Kirkland	North Kirkland Park	x	Accessible Parking	Parking Space-Car	1	signage are not provided and the slope and/or ground surface is/are not compliant. WASHINGTON: A car stall, access aisle, and	Community Center Street Parking Stall P5	State of Washington	50 WAC 1101; ADA 502.4, 502.5 WA Bldg Code 51-	\$11,300
243778	Community Center and Park North Kirkland Community Center and	North Kirkland Park	x	Accessible Parking	Parking Space-Car	1	signage are not provided and the slope and/or ground surface is/are not compliant. The ground surface has not been inspected and	Parking Lot 2	State of Washington	50 WAC 1101; ADA 502.4, 502.5	\$11,300
243396	•	North Kirkland Park	x	Playground	Ground Surface - Fibar	2	maintained regularly.	Playground 1 (PG1)	ADA	1008.2	\$2,542
243399	Community Center and Park North Kirkland	North Kirkland Park	х	Playground	Transfer System	2	A means of support is not provided at the transfer platform and/or transfer steps.	Playground 1 (PG1)	ADA	1008.3.1.4, 1008.3.2.3	\$1,485
243403	North Kirkland	North Kirkland Park	x	Playground	Ground Surface - Fibar	2	The ground surface has not been inspected and maintained regularly.	Playground 2 (PG2)	ADA	1008.2	\$264
243404	North Kirkland	North Kirkland Park	х	Playground	Ground Surface - Fibar	2	The ground surface has not been inspected and maintained regularly. The restroom circulation path is not free of objects protruding more than 4" from wall in the	Playground 3 (PG3)	ADA	1008.2	\$878
243414	Community Center and Park North Kirkland	North Kirkland Park	x	Restroom	Protruding Object	2	space between 27" and 80" height above finish floor. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Unisex Restroom (URR)	ADA	307.2	\$250
243398	Community Center and	North Kirkland Park	x	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface.	Playground 1 (PG1)	IBC	2009 ANSI A117.1- 504.5.1	\$246
243407	Community Center and Park North Kirkland Community Center and	North Kirkland Park	х	Restroom	Restroom/Ba <mark>th</mark> room - Sig nage	3	The provided signage is not mounted at the latch side of the door or at a compliant height. The accessible door with door closer has a sweep period of less than 5 seconds from 90	Unisex Restroom (URR)	ADA	216.2,703.1, 703.2, 703.5	\$55
243410	•	North Kirkland Park	х	Restroom	Restroom/Bathroom - Door	3	degrees to a position 12 degrees from latch.	Unisex Restroom (URR)	ADA	404.2.8	\$366
243411	North Kirkland	North Kirkland Park	x	Restroom	Restroom/Bathroom - Lavatory	3	Pipes are not insulated. The centerline of the toilet in the wheelchair stall is not 16" minimum to 18" maximum from	Unisex Restroom (URR)	ADA	606.5	\$65
243412	Community Center and Park	North Kirkland Park	x	Restroom	Restroom/Bathroom - Water Closet	3	the sidewall.	Unisex Restroom (URR)	ADA	604.2	\$630
243413	North Kirkland Community Center and Park	North Kirkland Park	x	Restroom	Restroom/Bathroom - Toilet Stall	3	WASHINGTON: A vertical side grab bar is not present in the wheelchair stall.	Unisex Restroom (URR)	ANSI A117.1	2009 ANSI A117.1-604.5.1 and A117.1-604.9.6	\$355

					Ph	ase 3					
Id	Facility	Building		Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243424	North Kirkland	North Kirkland Park	x	Exterior Access Route	Stairs	3	WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Stair 1 (ST1)	IBC	2009 ANSI A117.1- 504.5.1	\$141
243426	Community Center and Park North Kirkland	North Kirkland Park	x	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface.	Stair 2 (ST2)	IBC	2009 ANSI A117.1- 504.5.1	\$422
243394	Community Center and Park	North Kirkland Park	x	Site Furnishings	Drinking Fountain/Water Cooler	4	The minimum number and types of drinking fountains are not provided.	Drinking Fountain 1 (DF1)	ADA	211.2; 602; 309 WA Bldg Code 51-	\$8,000
243297		Spinney Homestead Park Spinney Homestead	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. WASHINGTON: Signage is not located at the required height for the van accessible space or	Walkway from Access Aisle to CR1	State of Washington	50 WAC 1101.2.1; 403.3 502.6; WA Bldg Code 51-50 WAC	\$320
243298		Park	х	Accessible Parking	Parking Space - Van	1	access aisle.	Accessible Parking Space 1 (P1)	ADA	1101.2.6 502.6; WA Bldg	\$280
243299		Spinney Homestead Park Spinney Homestead	x	Accessible Parking	Parking Space-Van	1	WASHINGTON: Compliant signage is not provided at the van space or access aisle. The parking space slope is greater than 1:50	Accessible Parking Space 1 (P1)	ADA	Code 51-50 WAC 1101.2.6	\$280
243300		Park Spinney Homestead	x	Accessible Parking	Parking Space - Van	1	(2%). The van parking space is less than 132" wide,	Accessible Parking Space 1 (P1)	ADA	502.4	\$6,300
243301		Park Spinney Homestead	х	Accessible Parking	Parking Space - Van	1	where the van aisle is less than 96" wide.	Accessible Parking Space 1 (P1)	ADA	502.2	\$420
243302		Park Spinney Homestead	х	Accessible Parking	Parking Space - Van	1	The van parking aisle is less than 96" wide. WASHINGTON: The van access aisle signage is	Access Aisle Serving P1	ADA State of	502.2 WA Bldg Code 51-	\$420
243304		Park Spinney Homestead	x	Accessible Parking	Parking Space - Van	1	not provided.	Access Aisle Serving P1	Washington	50 WAC 1101	\$280
243305		Park Spinney Homestead	x	Accessible Parking	Parking Space - Van	1	The access aisle slope is greater than 1:50 (2%). A landing at the top of the curb ramp is not	Access Aisle Serving P1	ADA	502.4	\$5,000
243306		Park	x	Exterior Access Route	Curb Ramp	1	present.	Curb Ramp 1 (CR1)	ADA	406.4	\$1,289
243307		Spinney Homestead Park	x	Exterior Access Route	Curb Ramp	1	WASHINGTON: The slope of the curb ramp run is not compliant.	Curb Ramp 1 (CR1)	State of Washington	WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2 thru 405.5; Table 405.2; 403.5.1 WA Bldg Code 51- 50 WAC 1101.6.6;	\$1,750
243308		Spinney Homestead Park	x	Exterior Access Route	Curb Ramp	1	WASHINGTON: The curb ramp width is less than 44".	Curb Ramp 1 (CR1)	State of Washington	ADA 406; 405.2 thru 405.5; Table 405.2; 403.5.1	\$0
243309		Spinney Homestead Park	х	Exterior Access Route	Curb Ramp	1	The curb ramp surface has vertical height changes greater than 1/4" that are not ramped.	Curb Ramp 1 (CR1)	ADA	303, 403.4 WA Bldg Code 51-	\$0
243310		Spinney Homestead Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from CR1	State of Washington	50 WAC 1101.2.1; 403.3	\$1,586

				Pł	nase 3					
ld Facility	Building		Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243312	Spinney Homestead Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from NE 100th St	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3	\$5,153
243313	Spinney Homestead Park	x	Exterior Access Route	Exterior Accessible Route	1	In areas along the route there are level changes of 1/2" or greater that are not ramped.	Walkway from NE 100th St	ADA	303.4, 405, 406 WA Bldg Code 51-	\$0
243314	Spinney Homestead Park Spinney Homestead	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route has gaps in the surface	Walkway North of Parking to RR1	State of Washington	50 WAC 1101.2.1; 403.3	\$4,955
243315	Park	х	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide.	Walkway North of Parking to RR1	ADA	302.3 WA Bldg Code 51-	\$396
243316	Spinney Homestead Park Spinney Homestead	х	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. An accessible route to the portable restroom	Walkway North of Parking to RR1	State of Washington	50 WAC 1101.2.1; 403.3	\$600
243317	Park Spinney Homestead	х	Portable Restroom	Portable Restroom	1	has not been provided. WASHINGTON: The slopes of the exterior	Portable Restroom 1 (RR1)	ADA State of	402, 404 WA Bldg Code 51- 50 WAC 1101.2.1;	\$95
243319	Park Spinney Homestead	х	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant. The accessible route does not have 80" vertical	East Asphalt Walking Path	Washington	403.3	\$6,000
243320	Park	Х	Exterior Access Route	Exterior Accessible Route	1	clearance.	East Asphalt Walking Path	ADA	307.4	\$250
243321	Spinney Homestead Park	x	Exterior Access Route	Exterior Accessible Route	1	In areas along the route there are level changes of 1/2" or greater that are not ramped.	East Asphalt Walking Path	ADA	303.4, 405, 406 WA Bldg Code 51-	\$0
243322	Spinney Homestead Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	East Asphalt Walking Path	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$6,600
243324	Spinney Homestead Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	East Asphalt Walking Path	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$600
243325	Spinney Homestead Park	x	Exterior Access Route	Exterior Acc <mark>essi</mark> ble Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	East Asphalt Walking Path	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$480
243326	Spinney Homestead Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Asphalt Walking Path to NE 102nd Place	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$9,900
243327	Spinney Homestead Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	North Asphalt Walking Path	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$19,800
243328	Spinney Homestead Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Asphalt Walking Path to 117th Place NE	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$3,000
243329	Spinney Homestead Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	West Asphalt Walking Path	State of Washington	50 WAC 1101.2.1; 403.3	\$21,000
243330	Spinney Homestead Park	x	Exterior Access Route	Exterior Accessible Route	1	In areas along the route there are level changes of 1/2" or greater that are not ramped.	West Asphalt Walking Path	ADA	303.4, 405, 406	\$0
243331	Spinney Homestead Park	x	Exterior Access Route	Exterior Accessible Route	1	The accessible route does not have 80" vertical clearance.	West Asphalt Walking Path	ADA	307.4	\$250

					Pł	nase 3					
Id	Facility	Building		Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243332		Spinney Homestead Park	x	Exterior Access Route	Exterior Accessible Route	1	In areas along the route there are level changes of 1/2" or greater that are not ramped.	West Asphalt Walking Path to Playground Area	ADA	303.4, 405, 406	\$59
243333		Spinney Homestead Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	West Asphalt Walking Path to Play Area	State of Washington	WA Bldg Code 51 50 WAC 1101.2.1; 403.3	
243334		Spinney Homestead Park	x	Exterior Access Route	Exterior Accessible Route	1	The accessible route has gaps in the surface greater than 1/2" wide.	Walkway from Parking to Playground Area	ADA	302.3 WA Bldg Code 51	\$454 -
243335		Spinney Homestead Park	х	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Parking to Playground Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	; \$7,135
243337		Spinney Homestead Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Picnic Table	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$108 -
243343		Spinney Homestead Park	х	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway around Playground Area	State of Washington	50 WAC 1101.2.1; 403.3	\$1,784
243344		Spinney Homestead Park	x	Exterior Access Route	Exterior Accessible Route	1	In areas along the route there are level changes of 1/2" or greater that are not ramped.	Walkway around Playground Area	ADA	303.4, 405, 406 WA Bldg Code 51	\$59 -
243345		Spinney Homestead Park	x	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway around Playground Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$951
243346		Spinney Homestead Park	х	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway around Playground Area	State of Washington	50 WAC 1101.2.1; 403.3	\$1,189
243347		Spinney Homestead Park Spinney Homestead	x	Exterior Access Route	Exterior Accessible Route	1	In areas along the route there are level changes of 1/2" or greater that are not ramped. The accessible route has gaps in the surface	Walkway around Playground Area	ADA	303.4, 405, 406	\$59
243348		Park	x	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide. The accessible route has areas of vertical level	Walkway around Plaground Area	ADA	302.3	\$108
243349		Spinney Homestead Park	x	Exterior Access Route	Exterior Accessible Route	1	changes in excess of 1/4" that are not beveled or ramped.	Playground	ADA	303	\$36
243323		Spinney Homestead Park	x	Baseball/Softball Field	Lawn Seating	2	The lawn seating and exterior overflow seating areas, where fixed seating is not provided, do not connect to an accessible route.	Softball/Baseball Field	ADA	221.5	\$829
243338		Spinney Homestead Park	x	Site Furnishings	Picnic Table	2	The pavement at the picnic table does not allow a clear space or turning space.	Picnic Table	ADA	304, 902.2; 902.4	·
243351		Spinney Homestead Park	х	Playground	Ground Surface-Fibar	2	The ground surface has not been inspected and maintained regularly. The play component requires transfer to entry	Playground	ADA	1008.2	\$1,050
243354		Spinney Homestead Park	х	Playground	Play Component	2	points or seats, but at least one means of support is not provided. The entry points to a play component requiring	Playground	ADA	1008.4.5	\$5,000
243355		Spinney Homestead Park Spinney Homestead	x	Playground	Play Component	2	transfer to entry points or seats is lower than 11" and higher than 24". Clear space is not provided at the operable part.	Playground	ADA	1008.4.4 305, 307, 308,	\$400
243311		Park	х	Exterior Access Route	Clear Space	3	The receptacle is not within reach range.	Trash Receptacles	ADA	309.2	\$108

				Ph	ase 3					
ld Facility	Building		Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
	Spinney Homestead									
243318	Park Spinney Homestead	Х	Portable Restroom	Portable Restroom	3	An ADA portable restroom is not provided.	Portable Restroom 1 (RR1)	ADA	213.2; 402.2	\$3,000
243336	Park	х	Picnic Area	Picnic Table	4	A compliant picnic table is not provided.	Picnic Table	ADA	902	\$1,300
	Spinney Homestead			Drinking Fountain/Water		The minimum number and types of drinking				
243339	Park	x	Site Furnishings	Cooler	4	fountains are not provided.	Drinking Fountain 1 (DF1)	ADA	211.2; 602; 309	\$8,000
	Spinney Homestead			Drinking Fountain/Water		The spout height is higher than 36" at the				
243340	Park	x	Site Furnishings	Cooler	4	lower/wheelchair level drinking fountain.	Drinking Fountain 1 (DF1)	ADA	602.4	\$8,000
	Spinney Homestead			Drinking Fountain/Water		The spout and/or water flow of the lower level				
243341	Park	Х	Site Furnishings	Cooler	4	drinking fountain is not compliant.	Drinking Fountain 1 (DF1)	ADA	602.2, 602.5	\$0
						A clear space is not positioned at the lower level				
	Spinney Homestead			Drinking Fountain/Water		drinking fountain for a forward approach and				
243342	Park	X	Site Furnishings	Cooler	4	centered on the unit.	Drinking Fountain 1 (DF1)	ADA	602.2	\$238
	Spinney Homestead					The play component which requires reaching is				
243352	Park	x	Playground	Play Component	4	not within the child's reach range.	Playground	ADA	Advisory 1008.4.2	\$5,000

\$841,304

					Ph	ase 4				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
241151	McAuliffe Park	East Community Garden	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. WASHINGTON: A van stall, access aisle, and	Walkway to Garden	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$2,378
241164	McAuliffe Park	East Community Garden East Community	Accessible Parking	Parking Space-Van	1	signage are not provided and the slope and/or ground surface is/are not compliant. The accessible route has gaps in the surface	Parking Lot at Community Garden	State of Washington	50 WAC 1101; ADA 502.4, 502.5	\$11,300
241165	McAuliffe Park	Garden East Community	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide. The accessible route does not have 80" vertical	Walkway to Garden	ADA	302.3	\$750
241166	McAuliffe Park	Garden	Exterior Access Route	Exterior Accessible Route	1	clearance.	Walkway to Garden	ADA	307.4 WA Bldg Code 51	\$200
241167	McAuliffe Park	East Community Garden	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway to Garden	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$2,000
241168	McAuliffe Park	East Community Garden	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Picnic Table at Grass Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$358
241170	McAuliffe Park	East Community Garden	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Garden	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$717
241172	McAuliffe Park	East Community Garden East Community	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. Sidewalk has areas of vertical level changes in	Walkway from Garden to Gazebo	State of Washington	50 WAC 1101.2.1; 403.3	\$3,226
241173	McAuliffe Park	Garden	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Walkway from Garden to Gazebo	ADA	303 WA Bldg Code 51	\$200 -
241174	McAuliffe Park	East Community Garden East Community	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. Sidewalk has areas of vertical level changes in	Walkway from Garden to Gazebo	State of Washington	50 WAC 1101.2.1; 403.3	\$2,800
241176	McAuliffe Park	Garden	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Walkway from Garden to Gazebo	ADA	303 WA Bldg Code 51	\$50 -
241177	McAuliffe Park	East Community Garden	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway at Gazebo	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$6,000
241178	McAuliffe Park	East Community Garden East Community	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The clear width of the exterior accessible route is less than 44". Sidewalk has areas of vertical level changes in	Walkway at Gazebo	State of Washington	50 WAC 1101.2.1; 403.3	\$0
241179	McAuliffe Park	Garden East Community	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped. Sidewalk has areas of vertical level changes in	Walkway at Gazebo	ADA	303	\$0
241180	McAuliffe Park	Garden	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Gazebo	ADA	303 WA Bldg Code 51	\$60
241181	McAuliffe Park	East Community Garden	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Gazebo	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$1,075
241182	McAuliffe Park	East Community Garden	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Gazebo to Road	State of Washington	50 WAC 1101.2.1; 403.3	

					Ph	ase 4				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
									WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2	
		East Community						State of	thru 405.5; Table	
241183	McAuliffe Park	Garden	Exterior Access Route	Curb Ramp	1	WASHINGTON: The curb ramp is not compliant.	Walkway from Gazebo to Road	Washington	405.2; 403.5.1 WA Bldg Code 51-	\$1,750
		East Community				WASHINGTON: The slopes of the exterior	Walkway from Gazebo to Open	State of	50 WAC 1101.2.1;	
241184	McAuliffe Park	Garden East Community	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant. Sidewalk has areas of vertical level changes in	Area Walkway from Gazebo to Open	Washington	403.3	\$3,200
241186	McAuliffe Park	Garden	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Area	ADA	303 WA Bldg Code 51-	\$40
		East Community				WASHINGTON: The slopes of the exterior	Walkway from Community Garden	State of	50 WAC 1101.2.1;	
241192	McAuliffe Park	Garden	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	to Restroom	Washington	403.3 WA Bldg Code 51-	\$2,750
		East Community				WASHINGTON: The slopes of the exterior	Walkway from Community Garden	State of	50 WAC 1101.2.1;	
241193	McAuliffe Park	Garden East Community	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant. Sidewalk has areas of vertical level changes in	to Restroom Walkway from Community Garden	Washington	403.3	\$250
241194	McAuliffe Park	Garden East Community	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped. The accessible route does not have 80" vertical	to Restroom Drinking Fountain at Restroom 1	ADA	303	\$50
241197	McAuliffe Park	Garden	Exterior Access Route	Exterior Accessible Route	1	clearance. The picnic table does not allow a clear space for	(RR1)	ADA	307.4	\$2,500
		East Community				forward wheelchair approach with knee and toe				
241169	McAuliffe Park	Garden East Community	Picnic Area	Picnic Table	2	clearance.	Picnic Table at Grass Area	ADA	902.2; 902.4	\$1,300
241171	McAuliffe Park	Garden East Community	Exterior Access Route	Clear Space	3	Clear space is not provided at the operable part. The accessible restroom entry door does not	Water supply / hose at Grass Area	ADA	305; 309.2 2009 ANSI A117.1	\$108
241199	McAuliffe Park	Garden	Restroom	Restroom/Bathroom - Door	3	have compliant maneuvering clearances.	Unisex Restroom (RR1)	IBC	404.2.3	\$1,250
		East Community		Restroom/Bathroom -		The restroom does not have compliant signage at the door with the International Symbol of			216.2, 703.1, 703.2, 703.5,	
241200	McAuliffe Park	Garden	Restroom	Signage	3	Accessibility, raised characters, and Braille.	Unisex Restroom (RR1)	ADA	703.6	\$55
		East Community		Restroom/Bathroom -		The provided signage is not mounted at the			216.2,703.1,	
241201	McAuliffe Park	Garden	Restroom	Signage	3	latch side of the door or at a compliant height.	Unisex Restroom (RR1)	ADA	703.2, 703.5	\$55
241202	McAuliffe Park	East Community Garden	Restroom	Restroom/Bathroom - Door	3	The threshold at the accessible door is greater than ½" in height.	Unicov Postroom (PP1)	ADA	404.2.5	\$179
241202	MICAUIIIE PAIK	East Community	עבאנוטטווו	nestroully battilloull - Dool	э	tilali /2 ili ileigiit.	Unisex Restroom (RR1)	ADA	404.2.3	\$179
241203	McAuliffe Park	Garden East Community	Restroom	Restroom/Bathroom - Door	3	The door has less than 32" clear width. The entire restroom is not compliant due to	Unisex Restroom (RR1)	ADA	404.2.3	\$1,124
241204	McAuliffe Park	Garden	Restroom	Restroom/Bathroom	3	limited room dimensions.	Unisex Restroom (RR1)	ADA	603, 604, 606	\$12,000
241195	McAuliffe Park	East Community Garden	Site Furnishings	Drinking Fountain/Water Cooler	4	The minimum number and types of drinking fountains are not provided.	Drinking Fountain at Restroom 1 (RR1)	ADA	211.2; 602; 309	\$8,000

					Ph	ase 4				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
253386	J	EXTERIOR	Entrance to Building	Building Entrance - Door	1	The accessible door with door closer has a sweep period of less than 5 seconds from 90 degrees to a position 12 degrees from latch. The accessible door with door closer has a support period of less than 5 seconds from 00	Main Entrance-West	ADA	404.2.8	\$732
253428	Kirkland Teen Union Building Kirkland Teen Union	EXTERIOR	Entrance to Building	Building Entrance - Door	1	sweep period of less than 5 seconds from 90 degrees to a position 12 degrees from latch. The maneuvering clearance at the accessible	South Exit door	ADA	404.2.8	\$732
253429		EXTERIOR	Entrance to Building	Building Entrance - Door	1	door is not level and clear. The accessible door with door closer has a sweep period of less than 5 seconds from 90	Main Entrance-West	ADA	305.2; 404.2	\$1,250
253430	Building Kirkland Teen Union	EXTERIOR	Entrance to Building	Building Entrance - Door	1	degrees to a position 12 degrees from latch. WASHINGTON: A van stall and access aisle are	North Patio Door	ADA State of	404.2.8 WA Bldg Code 51	\$366
253431	Building	EXTERIOR	Accessible Parking	Parking Space-Van	1	not marked and signage is not provided.	Parking Lot	Washington	50 WAC 1101 WA Bldg Code 51	\$1,400
253432	Kirkland Teen Union Building Kirkland Teen Union	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The surface of the door within 10 inches of the finish floor or ground for the full width of the	Parking Lot	State of Washington	50 WAC 1101.2.1 403.3	; \$991
253426		EXTERIOR	Entrance to Building	Building Entrance - Door	2	door on the push side is not smooth.	South Exit door	ADA	404.2.10	\$800
242899		Forbes Creek Park	Exterior Access Route	Curb Ramp	1	WASHINGTON: The slope of the curb ramp run is not compliant. WASHINGTON: A van stall, access aisle, and	Curb Ramp 1 (CR1)	State of Washington	WA Bldg Code 51 50 WAC 1101.6; ADA 406; 405.2 thru 405.5; Table 405.2; 403.5.1 WA Bldg Code 51	\$0
242900		Forbes Creek Park	Accessible Parking	Parking Space-Van	1	signage are not provided and the slope and/or ground surface is/are not compliant.	On-Street Parking	State of Washington	50 WAC 1101; ADA 502.4, 502.5	\$11,300
									WA Bldg Code 51 50 WAC 1101.6.6 ADA 406; 405.2	;
242901		Forbes Creek Park	Exterior Access Route	Curb Ramp	1	WASHINGTON: The curb ramp width is less than 44".	Curb Ramp 1 (CR1)	State of Washington	thru 405.5; Table 405.2; 403.5.1	\$0
242902		Forbes Creek Park	Exterior Access Route	Curb Ramp	1	The curb ramp surface has vertical height changes greater than 1/4" that are not ramped. The counter slopes of adjoining gutters and streets at the curb ramp are greater than 1:20	Curb Ramp 1 (CR1)	ADA	303, 403.4	\$0
242903		Forbes Creek Park	Exterior Access Route	Curb Ramp	1	(5%).	Curb Ramp 1 (CR1)	ADA	406.2 WA Bldg Code 51	\$0 -
242905		Forbes Creek Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway to Play Area	State of Washington	50 WAC 1101.2.1 403.3	

				Pł	nase 4				
ld Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
242906	Forbes Creek Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway to Play Area	State of Washington	WA Bldg Code 51 50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$1,586
242908	Forbes Creek Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Picnic Table at Play Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$179
242909	Forbes Creek Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Play Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$36
242913	Forbes Creek Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway to Basketball/Tennis Courts	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$8,919
242914	Forbes Creek Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. Sidewalk has areas of vertical level changes in	Walkway to Tennis Courts	State of Washington	50 WAC 1101.2.1; 403.3	
242915	Forbes Creek Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Walkway to Tennis Courts	ADA	303 WA Bldg Code 51	
242917	Forbes Creek Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Walkway to Tennis Courts	State of Washington	50 WAC 1101.2.1; 403.3	\$108
					The hardware at the accessible door (including sliding doors - both sides) requires tight grasping, pinching or twisting of the wrist to				
242918	Forbes Creek Park	Entrance to Building	Building Entrance - Door	1	operate OR is mounted below 34" or above 48". The gate maneuvering clearance area is not	Tennis Courts	ADA	309, 404.2.7 404; 404.2.3,	\$676
242920	Forbes Creek Park	Exterior Access Route	Gate	1	compliant.	Tennis Courts	ADA	404.2.4 WA Bldg Code 51	
242921	Forbes Creek Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. Sidewalk has areas of vertical level changes in	Walkway to Basketball Court	State of Washington	50 WAC 1101.2.1; 403.3	\$1,982
242922	Forbes Creek Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped. One of each type of ground level component is	Walkway to Basketball Court	ADA	303	\$238
242910	Forbes Creek Park	Playground	Play Component	2	not on an accessible route. The ground surface has not been inspected and	Play Area	ADA	240.2.1.1	\$0
242911	Forbes Creek Park	Playground	Ground Surface-Fibar	2	maintained regularly.	Play Area	ADA	1008.2	\$900
242912	Forbes Creek Park	Playground	Transfer System	2	A transfer space is not provided at the platform. The gate does not have a smooth surface within	•	ADA	1008.3.1.3	\$0
242919 242907	Forbes Creek Park Forbes Creek Park	Exterior Access Route Picnic Area	Gate Picnic Table	2 4	10" of the ground. A compliant picnic table is not provided.	Tennis Courts Picnic Table at Play Area	ADA ADA	404.2.10 902 WA Bldg Code 51	\$160 \$1,300
243938	Forbes Lake Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Walkway to Park	State of Washington	50 WAC 1101.2.1; 403.3	

					Ph	ase 4				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243939		Forbes Lake Park	Accessible Parking	Parking Space - Van	1	WASHINGTON: A van stall, access aisle, and signage are not provided and the slope and/or ground surface is/are not compliant. WASHINGTON: A van stall, access aisle, and signage are not provided and the slope and/or	Parking	State of Washington State of	WA Bldg Code 51- 50 WAC 1101; ADA 502.4, 502.5 WA Bldg Code 51- 50 WAC 1101;	\$11,300
239123	Peter Kirk Park	General Site	Accessible Parking	Parking Space - Van	1	ground surface is/are not compliant.	Parking Lot 1	Washington	ADA 502.4, 502.5	\$11,300
239124	Peter Kirk Park	General Site	Exterior Access Route	Curb Ramp	1	A compliant parallel curb ramp is not provided.	Curb Ramp CR1	ADA	304, 406 WA Bldg Code 51-	\$1,750
239125	Peter Kirk Park	General Site	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway W1	State of Washington	50 WAC 1101.2.1; 403.3	\$1,982
									WA Bldg Code 51- 50 WAC 1101.2.1; ADA 406; 405.2	
239126	Peter Kirk Park	General Site	Exterior Access Route	Ramp	1	WASHINGTON: The clear width of the ramp is less than 44". The slope of the parking space is greater than	Ramp R1	State of Washington	thru 405.5; Table 405.2; 403.5.1	\$6,620
239128	Peter Kirk Park	General Site	Accessible Parking	Parking Space - Car	1	1:50 (2%). WASHINGTON: Signage is not located at the required height for the standard accessible	Parking Lot 2 - Stall P1	ADA	502.4 502.6; WA Bldg Code 51-50 WAC	\$6,300
239129	Peter Kirk Park	General Site	Accessible Parking	Parking Space - Car	1	space or access aisle. WASHINGTON: The car access aisle signage is	Parking Lot 2 - Stall P1 Parking Lot 2 - Aisle Between P1 &	ADA State of	1101.2.6 WA Bldg Code 51-	\$280
239130	Peter Kirk Park	General Site	Accessible Parking	Parking Space - Car	1	not compliant or not provided.	P2 Parking Lot 2 - Aisle Between P1 &	Washington	50 WAC 1101	\$280
239131	Peter Kirk Park	General Site	Accessible Parking	Parking Space - Car	1	The access aisle slope is greater than 1:50 (2%). The slope of the parking space is greater than	P2	ADA	502.4	\$5,000
239132	Peter Kirk Park	General Site	Accessible Parking	Parking Space - Car	1	1:50 (2%). WASHINGTON: Signage is not located at the required height for the standard accessible	Parking Lot 2 - Stall P2	ADA	502.4 502.6; WA Bldg Code 51-50 WAC	\$6,300
239133	Peter Kirk Park	General Site	Accessible Parking	Parking Space - Car	1	space or access aisle. WASHINGTON: The car access aisle signage is	Parking Lot 2 - Stall P2	ADA State of	1101.2.6 WA Bldg Code 51-	\$280
239134	Peter Kirk Park	General Site	Accessible Parking	Parking Space - Car	1	not compliant or not provided.	Parking Lot 2 - Aisle Adjacent to P2	Washington	50 WAC 1101	\$280
239135	Peter Kirk Park	General Site	Accessible Parking	Parking Space - Car	1	The access aisle slope is greater than 1:50 (2%). Sidewalk has areas of vertical level changes in	Parking Lot 2 - Aisle Adjacent to P2	ADA	502.4	\$5,000
239136	Peter Kirk Park	General Site	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped. The slope of the parking space is greater than	Walkway W2	ADA	303	\$198
239137	Peter Kirk Park	General Site	Accessible Parking	Parking Space - Car	1	1:50 (2%).	Parking Lot 2 - Stall P3 Parking Lot 2 - Aisle Between P3 &	ADA	502.4	\$6,300
239138	Peter Kirk Park	General Site	Accessible Parking	Parking Space - Van	1	The access aisle slope is greater than 1:50 (2%). WASHINGTON: The van access aisle signage is	P4 Parking Lot 2 - Aisle Between P3 &	ADA State of	502.4 WA Bldg Code 51-	\$5,000
239139	Peter Kirk Park	General Site	Accessible Parking	Parking Space - Van	1	not compliant or not provided. The parking space slope is greater than 1:50	P4	Washington	50 WAC 1101	\$280
239140	Peter Kirk Park	General Site	Accessible Parking	Parking Space - Van	1	(2%).	Parking Lot 2 - Stall P4	ADA	502.4	\$6,300

					Ph	ase 4				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
239141	Peter Kirk Park	General Site	Exterior Access Route	Curb Ramp	1	A curb ramp is not provided where the accessible route crosses a curb. The curb ramp landing is not level. The slope of	Parking Lot 2 - Aisle Between P3 & P4	ADA	406.2	\$1,750
239142	Peter Kirk Park	General Site	Exterior Access Route	Curb Ramp	1	the curb ramp landing exceeds the maximum allowable 1:48 (2.08%). The ramp does not have a level landing at the	Curb Ramp CR2	ADA	304; 406.4 405.7; 405.8;	\$1,289
239143	Peter Kirk Park	General Site	Exterior Access Route	Ramp	1	top and/or bottom of each run. The maneuvering clearance at the accessible	Ramp R2	ADA	405.9	\$3,490
239144	Peter Kirk Park	General Site	Entrance to Building	Building Entrance - Door	1	door is not level and clear. Handrails are not continuous and at a consistent	Community Center Entrance ENT1	ADA	305.2; 404.2	\$1,250
239145	Peter Kirk Park	General Site	Exterior Access Route	Ramp	1	height above ramp surface. The accessible route has areas of vertical level	Ramp R3	ADA	505.3, 505.4	\$163
239146	Peter Kirk Park	General Site	Exterior Access Route	Exterior Accessible Route	1	changes in excess of 1/4" that are not beveled or ramped.	Ramp R3	ADA	303 WA Bldg Code 51-	\$99
239147	Peter Kirk Park	General Site	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway W3	State of Washington	50 WAC 1101.2.1; 403.3	
239148	Peter Kirk Park	General Site	Exterior Access Route	Curb Ramp	1	A compliant parallel curb ramp is not provided. The slope of the parking space is greater than	Curb Ramp CR3	ADA	304, 406	\$1,750
239149	Peter Kirk Park	General Site	Accessible Parking	Parking Space - Car	1	1:50 (2%).	Parking Lot 2 - Stall P5	ADA	502.4	\$6,300
239150	Peter Kirk Park	General Site	Accessible Parking	Parking Space - Car	1	The access aisle slope is greater than 1:50 (2%).	Parking Lot 2 - Aisle Adjacent to P5	ADA	502.4	\$5,000
239152	Peter Kirk Park	General Site	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided.	Stair ST1	ADA	505	\$1,304
239153	Peter Kirk Park	General Site	Exterior Access Route	Curb Ramp	1	WASHINGTON: The slope of the curb ramp run is not compliant.	Curb Ramp CR4	State of Washington	WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2 thru 405.5; Table 405.2; 403.5.1 WA Bldg Code 51-	\$1,750
				*		WASHINGTON: The slope of the curb ramp run		State of	50 WAC 1101.6; ADA 406; 405.2 thru 405.5; Table	
239154	Peter Kirk Park	General Site	Exterior Access Route	Curb Ramp	1	is not compliant. Sidewalk has areas of vertical level changes in	Curb Ramp CR5	Washington	405.2; 403.5.1	\$1,750
239155	Peter Kirk Park	General Site	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Walkway W4	ADA	303 WA Bldg Code 51-	\$198
239156	Peter Kirk Park	General Site	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway W4	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$3,568
239157	Peter Kirk Park	General Site	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Crosswalk CR3 to CR5	State of Washington	50 WAC 1101.2.1; 403.3	

					Ph	ase 4				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
244337	Peter Kirk Park	General Site	Accessible Parking	Parking Spaces-General	1	The minimum number of accessible parking spaces is not provided. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the	Parking Lot 1	ADA	208.2 2009 ANSI A117.1	\$0
239151	Peter Kirk Park	General Site	Exterior Access Route	Stairs	3	remaining portion of the tread surface. A compliant turning space is not provided at a	Stair ST1	IBC	504.5.1	\$70
239401		Hazen Hills Park	Exterior Access Route	Exterior Accessible Route	1	change of direction. A compliant turning space is not provided at a	Picnic Area	ADA	304; 403.5.2	\$496
239403		Hazen Hills Park	Exterior Access Route	Exterior Accessible Route	1	change of direction.	Bench 2	ADA	304; 403.5.2 WA Bldg Code 51	\$496 -
239404		Hazen Hills Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. A compliant turning space is not provided at a	Bench 1	State of Washington	50 WAC 1101.2.1; 403.3	
239406		Hazen Hills Park	Exterior Access Route	Exterior Accessible Route	1	change of direction. WASHINGTON: A van stall, access aisle, and	Bench 1	ADA	304; 403.5.2 WA Bldg Code 51: 50 WAC 1101;	\$496 -
240240		Hazen Hills Park	Accessible Parking	Parking Space-Van	1	signage are not provided and the slope and/or ground surface is/are not compliant.	On-Street Parking	State of Washington	ADA 502.4, 502.5	\$11,300
									WA Bldg Code 51 50 WAC 1101.6; ADA 406; 405.2	-
240241		Hazen Hills Park	Exterior Access Route	Curb Ramp	1	WASHINGTON: The slope of the curb ramp run is not compliant.	Curb Ramp 1 (CR1)	State of Washington	thru 405.5; Table 405.2; 403.5.1 WA Bldg Code 51	
240242		Hazen Hills Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Sidewalk adjacent to Picnic Area	State of Washington	50 WAC 1101.2.1; 403.3	\$0
239400	Kirkland Teen Union	Hazen Hills Park	Exterior Access Route	Clear Space	3	Clear space is not provided at the operable part.	Dog Waste Bag	ADA	305; 309.2	\$238
253388	Building Kirkland Teen Union	INTERIOR	Interior Access Route	Ramp	1	The ramp running slope exceeds 1:12 (8.33%). Landings are not provided at the top and	Ramp R1	ADA	405.2	\$15,888
253389	Building Kirkland Teen Union	INTERIOR	Interior Access Route	Ramp	1	bottom of each ramp run. Handrails are not continuous or are not at a	Ramp R1	ADA	405.9; 405.10	\$0
253390		INTERIOR	Interior Access Route	Ramp	1	continuous height above the ramp surface.	Ramp R1	ADA	505.3 and 505.4	\$326
253391		INTERIOR	Interior Access Route	Ramp	1	A ramp is required but not provided.	Ramp R2 - Stage	ADA	405, 505	\$16,550
253392	Building	INTERIOR	Interior Access Route	Stairs	1	Handrails are not compliant. Protruding objects in the 27" to 80" range above finished floor protrude more than 4" into the	Stairs ST1	ADA	505	\$2,934
253414	Kirkland Teen Union Building	INTERIOR	Restroom	Protruding Object	1	circulation path along the interior accessible route.	Women's Restroom	ADA	307.2	\$728
253393	Kirkland Teen Union Building	INTERIOR	Common Areas	Reach Range	2	Items that require a forward reach motion require more than 48" height reach.	Stage Area	ADA	308	\$500

					Ph	ase 4				
Id	Facility	Building	Assembly	lvpe	Barrier Priority	Detail	Location Description	ADA	Ref. Number To	tal
253416	Kirkland Teen Union Building Kirkland Teen Union	INTERIOR	Interior Access Route	Reach Range	2	######################################	Reception Area	ADA	308, 309	\$500
253420	Building Kirkland Teen Union	INTERIOR	Kitchen	Sink	2	maximum above finished floor.	Kitchen	ADA	606.3	\$720
253422	Building Kirkland Teen Union	INTERIOR	Exterior Access Route	Reach Range	2	***************************************	Kitchen	ADA	308, 309	\$200
253423	Building	INTERIOR	Exterior Access Route	Reach Range	2	***************************************	Kitchen	ADA	308, 309	\$200
253424	Kirkland Teen Union Building Kirkland Teen Union	INTERIOR	Common Areas	Work Surface	2	The work surface height is not compliant. Knee and toe clearances are not provided. The sink rim is higher than 34", and does not have knee and toe clearance (does not apply to	Art Room	ADA	306, 902.1, 902.2, 902.3, 902.4	\$600
253425	Building	INTERIOR	Interior Access Route	Sink	2	mop basins, utility sinks, or bar sinks).	Art Room	ADA	306.2 and 606.3	\$720
253385	Kirkland Teen Union Building	INTERIOR	Restroom	Restroom/Bathroom - Signage	3	The restroom does not have compliant signage at the door with the International Symbol of Accessibility, raised characters, and Braille. The accessible door with door closer has a	Men's Restroom	ADA	216.2, 703.1, 703.2, 703.5, 703.6	\$55
253394	Kirkland Teen Union Building Kirkland Teen Union	INTERIOR	Restroom	Restroom/Bathroom - Door	3	sweep period of less than 5 seconds from 90 degrees to a position 12 degrees from latch. The force required to open the interior, hinged,	Men's Restroom	ADA	404.2.8	\$366
253395	Building Kirkland Teen Union	INTERIOR	Restroom	Restroom/Bathroom - Door Restroom/Bathroom -	3	non-fire door is more than 5 pounds. The lavatory is mounted higher than 34" to the	Men's Restroom	ADA	404.2.9	\$0
253396	Building Kirkland Teen Union	INTERIOR	Restroom	Lavatory Restroom/Bathroom -	3	higher of the rim or counter.	Men's Restroom	ADA	606.2 and 606.3	\$720
253397	Building Kirkland Teen Union	INTERIOR	Restroom	Lavatory	3	The lavatory faucet hardware is not compliant. The mirror is mounted higher than 40" above finish floor to the bottom of the reflective surface, where it is installed above a lavatory or	Men's Restroom	ADA	606.4; 309	\$555
253398	Building Kirkland Teen Union	INTERIOR	Restroom	Restroom/Bathroom - Mirror	3	counter.	Men's Restroom	ADA	213.3.5; 603.3	\$200
253399	Building Kirkland Teen Union	INTERIOR	Restroom	Restroom/Bathroom - Urinal	3	The urinal dimensions are not compliant. The flush control is located on the closed side and is more than 48" high, for an obstructed forward reach range of maximum 20"	Men's Restroom	ADA	605.2	\$935
253400	Building Kirkland Teen Union	INTERIOR	Restroom	Restroom/Bathroom - Urinal Restroom/Bathroom - Toilet	3	horizontally.	Men's Restroom	ADA	605.4; 309	\$313
253401	Building	INTERIOR	Restroom	Stall	3	The wheelchair stall door is not self-closing.	Men's Restroom	ADA	604.8.1.2 ADA 604.7, 609.3;	\$293
253402	Kirkland Teen Union Building	INTERIOR	Restroom	Restroom/Bathroom - Water Closet	3	WASHINGTON: The toilet paper dispenser location is not compliant.	Men's Restroom	State of Washington	2009 ANSI A117.1- 604.7	\$293

					Ph	ase 4				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
253404	Kirkland Teen Union Building	INTERIOR	Restroom	Restroom/Bathroom - Water Closet	3	The centerline of the toilet in the wheelchair stall is not 16" minimum to 18" maximum from the sidewall.	Men's Restroom	ADA	604.2	\$630
253405	5	INTERIOR	Restroom	Restroom/Bathroom - Signage	3	The restroom does not have compliant signage at the door with the International Symbol of Accessibility, raised characters, and Braille. The accessible door with door closer has a	Women's Restroom	ADA	216.2, 703.1, 703.2, 703.5, 703.6	\$55
253406	Kirkland Teen Union Building Kirkland Teen Union	INTERIOR	Restroom	Restroom/Bathroom - Door	3	sweep period of less than 5 seconds from 90 degrees to a position 12 degrees from latch. The force required to open the interior, hinged,	Women's Restroom	ADA	404.2.8	\$366
253407	Building Kirkland Teen Union	INTERIOR	Restroom	Restroom/Bathroom - Door Restroom/Bathroom -	3	non-fire door is more than 5 pounds. The lavatory is mounted higher than 34" to the	Women's Restroom	ADA	404.2.9	\$0
253409	Building Kirkland Teen Union	INTERIOR	Restroom	Lavatory	3	higher of the rim or counter. The mirror is mounted higher than 40" above finish floor to the bottom of the reflective	Women's Restroom	ADA	606.2 and 606.3	\$720
253410	Building	INTERIOR	Restroom	Restroom/Bathroom - Mirror	3	surface, where it is installed above a lavatory or counter. The wheelchair stall with a floor mounted water	Women's Restroom	ADA	213.3.5; 603.3	\$200
253411	Kirkland Teen Union Building Kirkland Teen Union	INTERIOR	Restroom	Restroom/Bathroom - Toilet Stall Restroom/Bathroom - Coat	3	closet, in a multi-stall restroom, is less than 60" wide and 59" deep. The coat hook is not within an allowable reach	Women's Restroom	ADA	604.8.1.1	\$1,368
253412	Building	INTERIOR	Restroom	Hook	3	range. A cle <mark>ar s</mark> pace is not positioned at the lower level	Women's Restroom	ADA	308	\$115
253415	Kirkland Teen Union Building	INTERIOR	Common Areas	Drinking Fountain/Water Cooler	4	drinking fountain for a forward approach and centered on the unit. A minimum 30" wide section of the counter is	Corridor-Adjacent to the Restrooms	ADA	602.2	\$0
253417	Kirkland Teen Union Building	INTERIOR	Kitchen	Kitchen- Counter In Publicly Used Kitchens	4	not a minimum height of 28" and maximum height of 34" with knee and toe clearance. The opening force required to open the	Kitchen	ADA	902	\$15,880
239072	Peter Kirk Park	Peter Kirk Community Center	Interior Access Route	Door	1	accessible, hinged, non-fire door is more than 5 pounds. The accessible door with door closer has a	Community Center Meeting Room	ADA	404.2.9	\$366
239073	Peter Kirk Park	Peter Kirk Community Center Peter Kirk Community	Interior Access Route	Door	1	sweep period of less than 5 seconds from 90 degrees to a position 12 degrees from latch. The interior accessible route has less than 36"	Community Center Meeting Room Community Center	ADA	404.2.8 403.5.1 thru	\$0
239098	Peter Kirk Park	Center Peter Kirk Community	Interior Access Route	Interior Accessible Route	1	clear width. Steps do not have uniform and compliant riser	Kitchenette/Dining	ADA	403.5.3	\$3,600
239104	Peter Kirk Park	Center Peter Kirk Community	Interior Access Route	Stairs	1	heights and/or tread depths.	Community Center Stage	ADA	504.2	\$3,060
239105	Peter Kirk Park	Center	Interior Access Route	Stairs	1	Handrails are not compliant. Handrails do not extend 12" horizontally beyond the top and better of rame russ above the	Community Center Stage	ADA	505	\$978
239106	Peter Kirk Park	Peter Kirk Community Center	Interior Access Route	Ramp	1	the top and bottom of ramp runs above the landing surface.	Community Center Stage	ADA	505.10.1	\$700

					Ph	ase 4				
Id	Facility	Building	Assembly	Type	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
239107	Peter Kirk Park	Peter Kirk Community Center	Common Areas	Assembly Area	1	A direct accessible route is not provided from the assembly seating area to a performance area. At least one each of shelves, clothes rod,	Community Center Stage	ADA	206.2.6	\$793
239074	Peter Kirk Park	Peter Kirk Community Center	Common Areas	Reach Range	2	drawer, hook, closets or cabinets are not within reach range. The sink rim is higher than 34", and does not	Community Center Meeting Room	ADA	225.2	\$400
239075	Peter Kirk Park	Peter Kirk Community Center	Common Areas	Sink	2	have knee and toe clearance (does not apply to mop basins, utility sinks, or bar sinks). Tactile means of egress signage is not provided at the latch side of the door. (Applies to	Community Center Meeting Room	ADA	306.2 and 606.3	\$720
239076	Peter Kirk Park	Peter Kirk Community Center	Interior Access Route	Door	2	designated egress stairways, exit doors, areas of refuge) The restroom circulation path is not free of objects protruding more than 4" from wall in the	Community Center Throughout Building	ADA	216.4, 703	\$385
239084	Peter Kirk Park	Peter Kirk Community Center	Restroom	Protruding Object	2	space between 27" and 80" height above finish floor.	Community Center Women's Restroom	ADA	307.2	\$200
239093	Peter Kirk Park	Peter Kirk Community Center	Interior Access Route	Signage	2	The existing signage is not mounted at the latch side of the door or at a compliant height. The sales or service counter does not have an	Community Center Throughout Building	ADA	703.4	\$1,430
239094	Peter Kirk Park	Peter Kirk Community Center	Common Areas	Counter	2	accessible portion with maximum 36" height surface above finish floor or ground. The dining or work surface does not have a	Community Center Reception Counter	ADA	904.4	\$1,805
239095	Peter Kirk Park	Peter Kirk Community Center	Common Areas	Dining And Work Surface	2	minimum 28" and maximum 34" height with knee and toe clearance. The sink rim is higher than 34", and does not	Community Center Kitchenette/Dining	ADA	902.3	\$2,382
239096	Peter Kirk Park	Peter Kirk Community Center	Common Areas	Sink	2	have knee and toe clearance (does not apply to mop basins, utility sinks, or bar sinks). Items requiring an unobstructed side reach motion are higher than 48" maximum and/or	Community Center Kitchenette/Dining	ADA	306.2 and 606.3	\$720
239097	Peter Kirk Park	Peter Kirk Community Center	Common Areas	Reach Range	2	lower than 15" minimum height above finish floor. The sink rim is higher than 34", and does not	Community Center Reception/Information Area	ADA	308, 309	\$250
239100	Peter Kirk Park	Peter Kirk Community Center	Common Areas	Sink	2	have knee and toe clearance (does not apply to mop basins, utility sinks, or bar sinks). The sink rim is higher than 34", and does not	Community Center Activity Room 3	ADA	306.2 and 606.3	\$720
239101	Peter Kirk Park	Peter Kirk Community Center Peter Kirk Community	Common Areas	Sink	2	have knee and toe clearance (does not apply to mop basins, utility sinks, or bar sinks). An assistive listening system is required, but not	Community Center Activity Room 4	ADA	306.2 and 606.3	\$720
239108	Peter Kirk Park	Center Rotor Kirk Community	Common Areas	Assembly Area	2	provided.	Community Center Stage	ADA	216.10; 219; 706	\$250
239109	Peter Kirk Park	Peter Kirk Community Center	Common Areas	Service Counter	2	***************************************	Community Center Kitchen	ADA	904.4	\$1,805

					Ph	ase 4				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
239111	Peter Kirk Park	Peter Kirk Community Center	Common Areas	Reach Range		At least one each of shelves, clothes rod, drawer, hook, closets or cabinets are not within reach range. The restroom circulation path is not free of objects protruding more than 4" from wall in the	Community Center Reception Area	ADA	225.2	\$400
239114	Peter Kirk Park	Peter Kirk Community Center	Restroom	Protruding Object	2	space between 27" and 80" height above finish floor. The dining or work surface does not have a	Community Center Employee Unisex Restroom	ADA	307.2	\$200
240050	Peter Kirk Park	Peter Kirk Community Center	Common Areas	Dining And Work Surface	2	minimum 28" and maximum 34" height with knee and toe clearance. The restroom circulation path is not free of objects protruding more than 4" from wall in the	Community Center Meeting Room	ADA	902.3	\$2,382
240053	Peter Kirk Park	Peter Kirk Community Center	Restroom	Protruding Object	2	space between 27" and 80" height above finish floor. The restroom circulation path is not free of objects protruding more than 4" from wall in the	Community Center Men's & Women's Restroom	ADA	307.2	\$0
240056	Peter Kirk Park	Peter Kirk Community Center	Restroom	Protruding Object	2	space between 27" and 80" height above finish floor. The dining or work surface does not have a	Community Center Men's & Women's Restroom	ADA	307.2	\$0
240057	Peter Kirk Park	Peter Kirk Community Center	Common Areas	Dining And Work Surface	2	minimum 28" and maximum 34" height with knee and toe clearance. The dining or work surface does not have a	Community Center Kitchenette/Dining	ADA	902.3	\$2,382
240058	Peter Kirk Park	Peter Kirk Community Center	Common Areas	Dining And Work Surface	2	minimum 28" and maximum 34" height with knee and toe clearance. The dining or work surface does not have a	Community Center Activity Room 3	ADA	902.3	\$2,382
240059	Peter Kirk Park	Peter Kirk Community Center	Common Areas	Dining And Work Surface	2	minimum 28" and maximum 34" height with knee and toe clearance.	Community Center Activity Room 4	ADA	902.3	\$2,382
239078	Peter Kirk Park	Peter Kirk Community Center Peter Kirk Community	Restroom	Restroom/Bathroom - Signage	3	The provided signage is not mounted at the latch side of the door or at a compliant height.	Community Center Men's & Women's Restroom Community Center Men's &	ADA	216.2,703.1, 703.2, 703.5	\$110
239080	Peter Kirk Park	Center Peter Kirk Community	Restroom	Restroom/Bathroom - Door	3	The door has less than 32" clear width.	Women's Restroom Community Center Men's &	ADA	404.2.3	\$2,248
239081	Peter Kirk Park	Center Peter Kirk Community	Restroom	Controls And Dispensers Restroom/Bathroom -	3	The height of controls are not compliant.	Women's Restroom Community Center Men's &	ADA	606.1; 309.3	\$400
239082	Peter Kirk Park	Center Peter Kirk Community	Restroom	Lavatory	3	Pipes are not insulated.	Women's Restroom Community Center Men's &	ADA	606.5	\$130
239083	Peter Kirk Park	Center Peter Kirk Community	Restroom	Controls And Dispensers Restroom/Bathroom - Coat	3	The height of controls are not compliant. The coat hook is not within an allowable reach	Women's Restroom Community Center Men's &	ADA	606.1; 309.3	\$400
239085	Peter Kirk Park	Center	Restroom	Hook	3	range.	Women's Restroom	ADA	308	\$230
239086	Peter Kirk Park	Peter Kirk Community Center	Restroom	Restroom/Bathroom - Toilet Stall	3	WASHINGTON: A vertical side grab bar is not present in the wheelchair stall.	Community Center Men's & Women's Restroom	ANSI A117.1	2009 ANSI A117.1 604.5.1 and A117.1-604.9.6	\$710

					Ph	ase 4				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
					,	The wheelchair stall with a floor mounted water				
		Peter Kirk Community		Restroom/Bathroom - Toilet		closet, in a multi-stall restroom, is less than 60"	Community Center Women's			
239087	Peter Kirk Park	Center	Restroom	Stall	3	wide and 59" deep.	Restroom	ADA	604.8.1.1	\$1,368
		Peter Kirk Community		Restroom/Bathroom - Toilet		The side grab bar is not compliant in the	Community Center Men's &			
239088	Peter Kirk Park	Center	Restroom	Stall	3	wheelchair stall.	Women's Restroom	ADA	604.5.1; 604.8.1.5	\$710
		Dotor Kirk Community		Restroom/Bathroom - Water		The space between the grab bar and projecting objects above the grab bar is less than 12"	Community Contar Mania 9			
239089	Peter Kirk Park	Peter Kirk Community Center	Restroom	Closet	3	minimum.	Community Center Men's & Women's Restroom	ADA	609.3	\$200
239069	reter Kirk raik	Peter Kirk Community	Restroom	Restroom/Bathroom - Toilet	3	The hardware at the wheelchair stall door is not	Community Center Men's &	ADA	309, 404.2.7,	\$200
239091	Peter Kirk Park	Center	Restroom	Stall	3	compliant.	Women's Restroom	ADA	604.8.1.2	\$586
233031	r eter kirk r urk	Peter Kirk Community	Restroom	Restroom/Bathroom - Toilet	3	Compilant	Community Center Men's &	7.67.	001.0.1.2	7300
239092	Peter Kirk Park	Center	Restroom	Stall	3	The wheelchair stall door is not self closing.	Women's Restroom	ADA	604.8.1.2	\$586
										,
		Peter Kirk Community		Restroom/Bathroom -		The provided signage is not mounted at the	Community Center Employee		216.2,703.1,	
239112	Peter Kirk Park	Center	Restroom	Signage	3	latch side of the door or at a compliant height.	Unisex Restroom	ADA	703.2, 703.5	\$55
		Peter Kirk Community				The force required to open the interior, hinged,	Community Center Employee			
239113	Peter Kirk Park	Center	Restroom	Restroom/Bathroom - Door	3	non-fire door is more than 5 pounds.	Unisex Restroom	ADA	404.2.9	\$366
		Peter Kirk Community		Restroom/Bathroom -			Community Center Employee			
239115	Peter Kirk Park	Center	Restroom	Lavatory	3	Pipes are not insulated.	Unisex Restroom	ADA	606.5	\$65
									ADA 604.7, 609.3	
		Peter Kirk Community		Restroom/Bathroom - Water		WASHINGTON: The toilet paper dispenser	Community Center Employee	State of	2009 ANSI A117.1	
239116	Peter Kirk Park	Center	Restroom	Closet	3	location is not compliant.	Unisex Restroom	Washington	604.7	\$293
		Peter Kirk Community	_	Restroom/Bathroom - Water		The flush control is located on the closed side	Community Center Employee			
239117	Peter Kirk Park	Center	Restroom	Closet	3	and/or is not within reach range.	Unisex Restroom	ADA	604.6	\$313
		Peter Kirk Community		Restroom/Bathroom - Water		The height of the water closet is not 17"	Community Center Employee			
239118	Peter Kirk Park	Center	Restroom	Closet	3	minimum to 19" maximum above finished floor.	Unisex Restroom	ADA	604.4	\$630
200110	· ctc· ······ · a···	Conto		S. SSC			Chisco hestroin	7.57.		γοσο
		Peter Kirk Community		Restroom/Bathroom - Water		The water closet in a single user / unisex	Community Center Employee			
239119	Peter Kirk Park	Center	Restroom	Closet	3	restroom does not have the required clearance.	Unisex Restroom	ADA	604	\$1,368
		Peter Kirk Community		Restroom/Bathroom - Water		The grab bars at the water closet are not	Community Center Employee			
239120	Peter Kirk Park	Center	Restroom	Closet	3	compliant.	Unisex Restroom	ADA	604.5.2	\$710
		Peter Kirk Community				The pull side of the accessible door does not	Community Center Employee		404.2; Table	
239122	Peter Kirk Park	Center	Restroom	Restroom/Bathroom - Door	3	have the required maneuvering clearances.	Unisex Restroom	ADA	404.2.4.1	\$1,250
									2009 ANSI A117.1	
242252	D	Peter Kirk Community		Restroom/Bathroom-Toilet	•	WASHINGTON: A vertical side grab bar is not	Community Center Employee		604.5.1 and	4055
240060	Peter Kirk Park	Center	Restroom	Stall	3	present in the wheelchair stall.	Unisex Restroom	ANSI A117.1	A117.1-604.9.6	\$355
						The minimum number of drinking fountains is				
						not provided. If the minimum number is				
		Peter Kirk Community		Drinking Fountain/Water		provided, two levels or a hi-lo are not provided. If more than 2 are provided, less than 50% are			211.1; 211.2; 602	
239077	Peter Kirk Park	Center	Interior Access Route	Cooler	4	high or less than 50% are low.	Community Center Entrance Lobby	ADA	309	; \$5,440
2330//	i etel kiik i aik	Peter Kirk Community	interior Access Noute	Coolei	7	Controls and/or dispensers are not within an	Community Center Activity Room 3	ADA	303	φ υ,++ 0
239102	Peter Kirk Park	Center	Common Areas	Controls And Dispensers	4	allowable reach range.	& 4	ADA	606.1; 308	\$2,196
233102	. 5.6	-3		TIME OF THE DISPERSOR	•	222			200.2, 000	72,130

					Ph	ase 4				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
239103	Peter Kirk Park	Peter Kirk Community Center Peter Kirk Community	Common Areas	Controls And Dispensers	4	Controls and/or dispensers are not within an allowable reach range. Controls and/or dispensers are not within an	Community Center Throughout Building	ADA	606.1; 308	\$7,686
239110	Peter Kirk Park	Center	Common Areas	Controls And Dispensers	4	allowable reach range.	Community Center Kitchen	ADA	606.1; 308 WA Bldg Code 51-	\$1,098
239158	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. Two accessible methods of entry into the standard swimming pool with 300 linear feet or	Walkway W4	State of Washington	50 WAC 1101.2.1; 403.3	\$2,676
239161	Peter Kirk Park	Peter Kirk Park	Swimming Pools	Pool Stairs	1	more of pool wall are not provided. A sloped entry into the wading pool is not	Swimming Pool	ADA	242.2; 1009	\$3,847
239162	Peter Kirk Park	Peter Kirk Park	Swimming Pools	Method Of Access - General	1	provided.	Wading Pool	ADA	242.3	\$4,140
239164	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Stairs	1	Handrail extensions are not compliant.	Stair ST2	ADA	505.1	\$326
						WASHINGTON: The slopes of the ramp are not		State of	WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2 thru 405.5; Table	,
239182	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Ramp	1	compliant. WASHINGTON: Handrails are not provided where the ramp rises more than 6" or are not	Ramp R4	Washington State of	405.2; 403.5.1 ADA 505.6; WA Bldg Code 51-50	\$18,536
239183	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Ramp	1	compliant. Sidewalk has areas of vertical level changes in	Ramp R4	Washington	WAC 1101.2.1	\$4,564
239184	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Walkway W4	ADA	303 WA Bldg Code 51-	\$198 -
						WASHINGTON: The slopes of the exterior		State of	50 WAC 1101.2.1;	
239185	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant. Sidewalk has areas of vertical level changes in	Walkway W5	Washington	403.3	\$2,378
239186	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped. Sidewalk has areas of vertical level changes in	Walkway W5	ADA	303	\$317
239187	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Walkway W5	ADA	303 WA Bldg Code 51-	\$159 -
239188	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway W5	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$5,391
239189	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway W6	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$14,270
239190	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway W7	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$8,919
239191	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway W8	State of Washington	50 WAC 1101.2.1; 403.3	

					Ph	ase 4				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
					·			_	WA Bldg Code 51-	
						WASHINGTON: The slopes of the exterior		State of	50 WAC 1101.2.1;	4
239192	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Walkway W9	Washington	403.3 404; 404.2.3,	\$1,982
239193	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Clear Space	1	The gate maneuvering clearance area is not compliant.	Gate G1	ADA	404.2.4	\$568
233133	reter kirk rark	Teter Kirk Furk	Exterior Access Noute	cicai space	-	compilant.	Gute G1	ADA	WA Bldg Code 51-	7500
						WASHINGTON: The slopes of the exterior		State of	50 WAC 1101.2.1;	
239196	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Walkway W10	Washington	403.3	\$5,946
						The accessible route has areas of vertical level				
						changes in excess of 1/4" that are not beveled or				
239203	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Exterior Accessible Route	1	ramped.	Playground	ADA	303	\$119
						A compliant accessible route is not provided				4
239204	Peter Kirk Park	Peter Kirk Park	Picnic Area	Exterior Accessible Route	1	from the public access to the amenity.	Picnic Area PA1	ADA	206; 206.2.2	\$1,254
						WASHINGTON: The slopes of the exterior		State of	WA Bldg Code 51- 50 WAC 1101.2.1;	
239205	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Walkway W11	Washington	403.3	\$4,757
239203	retel Klik raik	reter Kirk raik	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Walkway WII	wasiiiigtoii	403.3	J4,/J/
239214	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided.	Stair ST4	ADA	505	\$3,260
						A compliant accessible route is not provided				. ,
239216	Peter Kirk Park	Peter Kirk Park	Baseball/Softball Field	Exterior Accessible Route	1	from the public access to the amenity.	Ball Field	ADA	206; 206.2.2	\$30,000
239218	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Stairs	1	Handrails are not compliant.	Stair ST7	ADA	505	\$3,260
239219	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Stairs	1	Handrails are not compliant.	Stair ST6	ADA	505	\$1,630
239221	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Stairs	1	Handrails are not compliant.	Stair ST3	ADA	505	\$6,520
239224	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Stairs	1	Hand <mark>rail</mark> s are not compliant.	Stair ST5	ADA	505	\$1,630
239159	Peter Kirk Park	Peter Kirk Park	Common Areas	Service Counter	2		Swimming Pool Ticket Window	ADA	904.4	\$238
						The sales or service counter does not have an				
220160	Dotor Kirk Dork	Dotor Kirk Dork	Futorior Assess Bouts	Country	2	accessible portion with maximum 36" height	Suimming Dool Tisket Window	A.D.A	904.4	¢2.000
239160	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Counter	2	surface above finish floor or ground. The gate does not have a smooth surface within	Swimming Pool Ticket Window	ADA	904.4	\$3,000
239194	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Gate	2	10" of the ground.	Gate G1	ADA	404.2.10	\$160
233134	reter Kirk raik	reter Kirk rark	Exterior Access Noute	date	2	The ground surface has not been inspected and	Gate G1	ADA	404.2.10	7100
239198	Peter Kirk Park	Peter Kirk Park	Playground	Ground Surface - Fibar	2	maintained regularly.	Playground	ADA	1008.2	\$1,482
			,8			The side of the transfer platform used for				7-7:
239199	Peter Kirk Park	Peter Kirk Park	Playground	Transfer System	2	transfer is obstructed.	Playground	ADA	1008.3.1.3	\$500
						The elevated route connecting elevated play			1008.2.1,	
				Elevated Route - Accessed by		components accessed by a transfer system is			1008.2.4.2	
239201	Peter Kirk Park	Peter Kirk Park	Playground	Transfer System	2	less than 24" wide.	Playground	ADA	Exception 2	\$25,000
						A wheelchair space is not provided at each team				
239215	Peter Kirk Park	Peter Kirk Park	Baseball/Softball Field	Player Seating	2	bench area at the ball field.	Ball Field	ADA	221.2.1.4; 802.1	\$131
						The required number of wheelchair spaces is				
239223	Dator Kirk Dark	Datas Kirk Dark	Deschall/Cofthall Field	Diagram Coating	2	not provided at the bleacher seating for the ball field.	Ball Field	ADA	221, 002 2, 002 2	ຕ່ວດວ
239223	Peter Kirk Park Peter Kirk Park	Peter Kirk Park Peter Kirk Park	Baseball/Softball Field Concession Stand	Bleacher Seating Service Counter	2 2	######################################		ADA ADA	221; 802.2; 802.3 904.4	\$393 \$238
239225	FELEI NIIK PAIK	FELEI NIIK PAIK	Concession stand	Service Counter	2	***************************************	Dail Field Collessions	ADA	JU4.4	3238

					Ph	ase 4				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
239163	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Stairs	3	WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the remaining portion of the tread surface.	Stair ST2	IBC	2009 ANSI A117.1 504.5.1	\$70
239197	Peter Kirk Park	Peter Kirk Park	Basketball Court	Exterior Accessible Route	3	The amenity is not located on an accessible route.	Basketball Court	ADA	402.2	\$12,000
239197	retei kiik raik	retei Kiik raik	Basketball Coult	Exterior Accessible route	3	WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the	basketball Court	ADA	2009 ANSI A117.1	
239200	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Stairs	3	remaining portion of the tread surface. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Playground	IBC	504.5.1	\$598
239213	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Stair ST4	IBC	2009 ANSI A117.1 504.5.1	\$211
239217	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Stair ST7	IBC	2009 ANSI A117.1 504.5.1	\$211
239222	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Stairs Drinking Fountain/Water	3	on the leading 2" of the tread from the remaining portion of the tread surface. The minimum number and types of drinking	Stair ST3	IBC	2009 ANSI A117.1 504.5.1	\$422
239181	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Cooler Drinking Fountain/Water	4	fountains are not provided. The minimum number and types of drinking	Drinking Fountain DF1	ADA	211.2; 602; 309	\$8,000
239195	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Cooler Drinking Fountain/Water	4	fountains are not provided. Knee and toe clearance is not provided at the	Drinking Fountain DF2	ADA	211.2; 602; 309	\$8,000
240063	Peter Kirk Park	Peter Kirk Park	Exterior Access Route	Cooler	4	lower level fountain.	Drinking Fountain DF1	ADA	306.3, 602.2 WA Bldg Code 51-	\$2,505
241150	McAuliffe Park	Play Area	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. WASHINGTON: A van stall, access aisle, and	Walkway to Amenities from Parking	J	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$2,867
241152	McAuliffe Park	Play Area	Accessible Parking	Parking Space-Van	1	signage are not provided and the slope and/or ground surface is/are not compliant. The picnic table does not allow a clear space for	Parking Lot at Play Area	State of Washington	50 WAC 1101; ADA 502.4, 502.5	\$11,300
241153	McAuliffe Park	Play Area	Picnic Area	Picnic Table	2	forward wheelchair approach with knee and toe clearance. An accessible route to at least one of each type	Picnic Table at Grass Area	ADA	902.2; 902.4	\$1,300
241154	McAuliffe Park	Play Area	Playground	Exterior Accessible Route	2	of ground component within the play area has not been provided. The ground curface has not been inspected and	Playground	ADA	240.2.1.1	\$79
241155	McAuliffe Park	Play Area	Playground	Ground Surface-Fibar	2	The ground surface has not been inspected and maintained regularly. A turning space is not provided at a school-age	Playground	ADA	1008.2	\$1,400
241156	McAuliffe Park	Play Area	Playground	Play Component - Swing	2	swing.	Swings	ADA	1008.4.1	\$0

					Ph	ase 4				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
241157	McAuliffe Park	Play Area	Playground	Play Component	2	The entry points to a play component requiring transfer to entry points or seats is lower than 11" and higher than 24". The picnic table does not allow a clear space for forward wheelchair approach with knee and toe	Swings	ADA	1008.4.4	\$400
241163	McAuliffe Park	Play Area	Picnic Area	Picnic Table	2	clearance.	Picnic Table at Play Area	ADA	902.2; 902.4	\$1,300
239167	Peter Kirk Park	Restrooms	Restroom	Restroom/Bathroom	2	Items requiring an unobstructed side reach motion are higher than 48" maximum and/or lower than 15" minimum height above finish floor. The restroom circulation path is not free of objects protruding more than 4" from wall in the	Restrooms 2 - Men's & Women's	ADA	308, 309	\$100
239174	Peter Kirk Park	Restrooms	Restroom	Protruding Object	2	space between 27" and 80" height above finish floor.	Restrooms 2 - Women's	ADA	307.2	\$400
				0 /		The restroom circulation path is not free of objects protruding more than 4" from wall in the space between 27" and 80" height above finish				·
239179	Peter Kirk Park	Restrooms	Restroom	Protruding Object	2	floor. The restroom circulation path is not free of	Restrooms 2 - Men's & Women's	ADA	307.2	\$2,400
						objects protruding more than 4" from wall in the space between 27" and 80" height above finish				
239207	Peter Kirk Park	Restrooms	Restroom	Protruding Object	2	floor. The locker area does not have accessible	Restrooms 1 - Men's & Women's	ADA	307.2	\$400
239165	Peter Kirk Park	Restrooms	Restroom	Restroom/Bathroom - Locker	3	lockers. The locker area does not have a compliant	Restrooms 2 - Women's	ADA	225.21	\$660
239166	Peter Kirk Park	Restrooms	Restroom	Restroom/Bathroom - Locker	3	bench.	Restrooms 2 - Women's	ADA	903	\$500
									2009 ANSI A117.1	L-
				Restroom/Bathroom - Toilet		WASHINGTON: A vertical side grab bar is not			604.5.1 and	
239168	Peter Kirk Park	Restrooms	Restroom	Stall Restroom/Bathroom - Coat	3	present in the wheelchair stall. The coat hook is not within an allowable reach	Restrooms 2 - Men's & Women's	ANSI A117.1	A117.1-604.9.6	\$710
239169	Peter Kirk Park	Restrooms	Restroom	Hook	3	range. The hardware at the wheelchair stall door is not	Restrooms 2 - Men's & Women's	ADA	308 309, 404.2.7,	\$230
239170	Peter Kirk Park	Restrooms	Restroom	Restroom/Bathroom-Door Restroom/Bathroom -	3	compliant.	Restrooms 2 - Men's & Women's	ADA	604.8.1.2	\$586
239171	Peter Kirk Park	Restrooms	Restroom	Lavatory	3	Pipes are not insulated.	Restrooms 2 - Men's & Women's	ADA	606.5	\$130
239172	Peter Kirk Park	Restrooms	Restroom	Controls And Dispensers	3	The height of controls are not compliant.	Restrooms 2 - Men's & Women's	ADA	606.1; 309.3	\$400
239173	Peter Kirk Park	Restrooms	Restroom	Controls And Dispensers	3	The height of controls are not compliant.	Restrooms 2 - Women's	ADA	606.1; 309.3	\$200
239175	Peter Kirk Park	Restrooms	Restroom	Restroom/Bathroom - Coat Hook	3	The coat hook is not within an allowable reach range.	Restrooms 2 - Men's & Women's	ADA	308 ADA 608; 2009 ANSI A117.1- 608.3, 609; WA	\$230
				Restroom/Bathroom -		WASHINGTON: The transfer shower stall is not			Bldg Code 51-50	
239176	Peter Kirk Park	Restrooms	Restroom	Transfer Shower Stall	3	compliant.	Restrooms 2 - Men's & Women's	IBC	WAC 1101.2.4	\$14,362

					Ph	ase 4				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
239177	Peter Kirk Park	Restrooms	Restroom	Restroom/Bathroom - Locker	3	The locker area does not have accessible lockers. The locker area does not have a compliant	Restrooms 2 - Men's	ADA	225.21	\$660
239178	Peter Kirk Park	Restrooms	Restroom	Restroom/Bathroom - Locker	3	bench. The mirror is mounted higher than 35" above finish floor to the bottom of the reflective surface, where it is not installed above a lavatory	Restrooms 2 - Men's	ADA	903	\$500
239180	Peter Kirk Park	Restrooms	Restroom	Restroom/Bathroom - Mirror	3	or counter.	Restrooms 2 - Men's & Women's	ADA	213.3.5; 603.3	\$400
239206	Peter Kirk Park	Restrooms	Restroom	Restroom/Bathroom - Signage	3	The provided signage is not mounted at the latch side of the door or at a compliant height.	Restrooms 1 - Men's & Women's	ADA	216.2,703.1, 703.2, 703.5	\$110
239208	Peter Kirk Park	Restrooms	Restroom	Controls And Dispensers	3	The height of controls are not compliant. The clear floor space at the urinal is less than	Restrooms 1 - Men's & Women's	ADA	606.1; 309.3	\$400
239209	Peter Kirk Park	Restrooms	Restroom	Restroom/Bathroom - Urinal Restroom/Bathroom - Toilet	3	minimum 30" by minimum 48".	Restrooms 1 - Men's	ADA	605.3; 305	\$1,100
239210	Peter Kirk Park	Restrooms	Restroom	Stall Restroom/Bathroom - Toilet	3	The wheelchair stall door is not self closing. The hardware at the wheelchair stall door is not	Restrooms 1 - Men's & Women's	ADA	604.8.1.2 309, 404.2.7,	\$586
239211	Peter Kirk Park	Restrooms	Restroom	Stall Restroom/Bathroom - Toilet	3	compliant. The side grab bar is not compliant in the	Restrooms 1 - Men's & Women's	ADA	604.8.1.2	\$586
239212	Peter Kirk Park	Restrooms	Restroom	Stall	3	wheelchair stall.	Restrooms 1 - Men's & Women's	ADA	604.5.1; 604.8.1.5 WA Bldg Code 51-	•
240554		Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. WASHINGTON: Signage is not located at the required height for the van accessible space or	Walkway to Portable Restroom (RR1) at Parking Lot	State of Washington	50 WAC 1101.2.1; 403.3 502.6; WA Bldg Code 51-50 WAC	\$1,200
240555		Rose Hill Meadows	Accessible Parking	Parking Space - Van	1	access aisle. The parking space slope is greater than 1:50	Accessible Parking Space 1 (P1)	ADA	1101.2.6	\$280
240556		Rose Hill Meadows	Accessible Parking	Parking Space - Van	1	(2%).	Accessible Parking Space 1 (P1)	ADA	502.4	\$6,300
240557		Rose Hill Meadows	Accessible Parking	Parking Space - Van	1	The access aisle slope is greater than 1:50 (2%). WASHINGTON: The van access aisle signage is	Access Aisle Serving P1	ADA State of	502.4 WA Bldg Code 51-	\$5,000
240558		Rose Hill Meadows	Accessible Parking	Parking Space - Van	1	not compliant or not provided. Sidewalk has areas of vertical level changes in	Access Aisle Serving P1	Washington	50 WAC 1101	\$280
240560		Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Walkway from Parking Lot	ADA	303 WA Bldg Code 51-	
240561		Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. Signage indicating the accessible route to the	Walkway from Parking Lot	State of Washington	50 WAC 1101.2.1; 403.3	\$1,600
240562		Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	amenity is not provided.	Stairs 1 (ST1)	ADA	216.6	\$280
240563		Rose Hill Meadows	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided. The accessible route does not have 80" vertical	Stairs 1 (ST1)	ADA	505	\$2,608
240565		Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	clearance. Signage indicating the accessible route to the	Stairs 1 (ST1) West Entrance Walkway from 124th	ADA	307.4	\$200
240566		Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	amenity is not provided.	Ave NE	ADA	216.6	\$280

				Pł	nase 4				
Id Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
240567	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	West Entrance Walkway from 124th Ave NE	State of Washington	WA Bldg Code 51 50 WAC 1101.2.1; 403.3 WA Bldg Code 51	; \$2,000
240568	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route does not have 80" vertical	Walkway from West Entrance to Loop Walk Walkway from West Entrance to	State of Washington	50 WAC 1101.2.1; 403.3	
240569	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	clearance.	Loop Walk	ADA	307.4	\$200
240570	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	West Loop Walk	State of Washington	WA Bldg Code 51 50 WAC 1101.2.1; 403.3 WA Bldg Code 51	; \$4,032
240571	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	West Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	; \$250
240572	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route does not have 80" vertical	South Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3	
240574	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	clearance.	South Loop Walk	ADA	307.4 WA Bldg Code 51	\$400
240575	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	South Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	; \$1,200
240576	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	South Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$1,800
240577	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	East Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$1,500
240578	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route has gaps in the surface	Walkway from Walk Loop to NE 181st Dr Walkway from Walk Loop to NE	State of Washington	50 WAC 1101.2.1; 403.3	; \$8,000
240579	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide.	181st Dr	ADA	302.3 WA Bldg Code 51	\$0
240580	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The clear width of the exterior accessible route is less than 44".	Walkway from Walk Loop to NE 181st Dr	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$500
240581	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway from Walk Loop to NE 181st Dr	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$2,400
240582	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	North Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$800
240583	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	North Loop Walk	State of Washington	50 WAC 1101.2.1; 403.3	; \$250

				Ph	nase 4				
Id Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
240584	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	Sidewalk has areas of vertical level changes in excess of 1/4" that are not ramped.	Picnic Tables at Loop Walk	ADA	303 WA Bldg Code 51-	\$70
240586	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route does not have 80" vertical	North Loop Walk West Entrance Walkway from 124th	State of Washington	50 WAC 1101.2.1; 403.3	
240588	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	clearance.	Ave NE	ADA	307.4	\$200
240589	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	The accessible route does not have 80" vertical clearance.	Walkway to Play Area	ADA	307.4 WA Bldg Code 51-	\$200
240590	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route does not have 80" vertical	Walkway to Play Area	State of Washington	50 WAC 1101.2.1; 403.3	\$800
240591	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	clearance.	Walkway to Play Area	ADA	307.4 WA Bldg Code 51-	\$200
240592	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway to Play Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$400
240593	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route does not have 80" vertical	Walkway at Elevated Play Component Walkway at Elevated Play	State of Washington	50 WAC 1101.2.1; 403.3	
240594	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	clearance.	Component	ADA	307.4	\$200
								WA Bldg Code 51- 50 WAC 1101.6.6; ADA 406; 405.2	
240595	Rose Hill Meadows	Exterior Access Route	Curb Ramp	1	WASHINGTON: The curb ramp width is less than 44".	Curb Ramp 1 (CR1)	State of Washington	thru 405.5; Table 405.2; 403.5.1 WA Bldg Code 51-	\$1,750 -
240601	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The curb ramp landing is not level. The slope of the curb ramp landing exceeds the maximum.	Walkway to From CR 1 to CR 2	State of Washington	50 WAC 1101.2.1; 403.3	\$600
240602	Rose Hill Meadows	Exterior Access Route	Curb Ramp	1	the curb ramp landing exceeds the maximum allowable 1:48 (2.08%). WASHINGTON: The clear width of the exterior accessible route is less than 44".	Curb Ramp 2 (CR2)	ADA	304; 406.4, WA Bldg Code 51-50 WAC 1101.2.1; 403.3	\$1,289
240602	Rose Hill Meadows	Exterior Access Route	Сиго катр	1	iess than 44 .	curb kamp z (ckz)	ADA		
					WASHINGTON: The curb ramp width is less than		State of	WA Bldg Code 51- 50 WAC 1101.6.6; ADA 406; 405.2 thru 405.5; Table	
240603	Rose Hill Meadows	Exterior Access Route	Curb Ramp	1	44".	Curb Ramp 2 (CR2)	Washington	405.2; 403.5.1	\$1,750
240604	Rose Hill Meadows	Exterior Access Route	Curb Ramp	1	The curb ramp surface has vertical height changes greater than 1/4" that are not ramped.	Curb Ramp 2 (CR2)	ADA	303, 403.4	\$0

				Pł	nase 4				
Id Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
								WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2	-
240605	Rose Hill Meadows	Exterior Access Route	Curb Ramp	1	WASHINGTON: The slope of the curb ramp run is not compliant.	Curb Ramp 2 (CR2)	State of Washington	thru 405.5; Table 405.2; 403.5.1 WA Bldg Code 51	\$0 -
240610	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route does not have 80" vertical	Walkway to Covered Picnic Area Walkway Loop at Covered Picnic	State of Washington	50 WAC 1101.2.1; 403.3	\$1,200
240611	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	clearance.	Area	ADA	307.4 WA Bldg Code 51	
240612	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route does not have 80" vertical	Walkway Loop at Covered Picnic Area Walkway Loop at Covered Picnic	State of Washington	50 WAC 1101.2.1; 403.3	\$480
240613	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	clearance.	Area	ADA	307.4 WA Bldg Code 51	
240614	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway Loop at Covered Picnic Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$480
240615	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route does not have 80" vertical	Walkway Loop at Covered Picnic Area Walkway Loop at Covered Picnic	State of Washington	50 WAC 1101.2.1; 403.3	\$3,300
240618	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	clear <mark>anc</mark> e.	Area	ADA	307.4 WA Bldg Code 51	\$200
240619	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route does not have 80" vertical	Walkway Loop at Covered Picnic Area Walkway Loop at Covered Picnic	State of Washington	50 WAC 1101.2.1; 403.3	\$2,400
240620	Rose Hill Meadows	Exterior Access Route	Exterior Accessible Route	1	clearance. The picnic table does not allow a clear space for	Area	ADA	307.4	\$20
240585	Rose Hill Meadows	Picnic Area	Picnic Table Trash Receptacle Without	2	forward wheelchair approach with knee and toe clearance. A trash receptacle is not located on an	Picnic Tables at Loop Walk West Entrance Walkway from 124th	ADA	902.2; 902.4	\$1,300
240587	Rose Hill Meadows	Site Furnishings	Operable Lid	2	accessible route and within reach range. The ground surface has not been inspected and	Ave NE	ADA	228.1, 308	\$115
240597	Rose Hill Meadows	Playground	Ground Surface-Fibar	2	maintained regularly.	Playground	ADA	1008.2	\$200
240599	Rose Hill Meadows	Playground	Transfer System	2	A transfer space is not provided at the platform The ground surface within the use zone does	. Playground	ADA	1008.3.1.3	\$0
240607	Rose Hill Meadows	Playground	Ground Surface	2	not comply with ASTM F 1292. A turning space is not provided at a preschool	Playground - Swings	ADA	105.2.3; 1008.2.6	\$1,400
240608	Rose Hill Meadows	Playground	Play Component-Swing	2	swing. The picnic table does not allow a clear space for		ADA	1008.4.1	\$0
240617	Rose Hill Meadows	Picnic Area	Picnic Table	2	forward wheelchair approach with knee and toe clearance.	Walkway Loop at Covered Picnic Area	ADA	902.2; 902.4	\$1,300

	Phase 4									
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
240559		Rose Hill Meadows	Portable Restroom	Portable Restroom	3	An ADA portable restroom is not provided. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the	Portable Restroom at Parking Lot (RR1)	ADA	213.2; 402.2 2009 ANSI A117.:	\$3,000
240564		Rose Hill Meadows	Exterior Access Route	Stairs	3	remaining portion of the tread surface.	Stairs 1 (ST1)	IBC	504.5.1	\$211
240573		Rose Hill Meadows	Picnic Area	Picnic Table	4	A compliant picnic table is not provided. The play component which has manipulative or interactive features that require reaching is not	Picnic Tables at Loop Walk	ADA	902	\$1,250
240598		Rose Hill Meadows	Playground	Play Component	4	within the child's reach range.	Playground Walkway Loop at Covered Picnic	ADA	Advisory 1008.4.2	2 \$5,000
240616		Rose Hill Meadows	Picnic Area	Picnic Table	4	A compliant picnic table is not provided. WASHINGTON: A van stall, access aisle, and	Area	ADA	902 WA Bldg Code 51	\$1,250 -
241187	McAuliffe Park	West Community Garden	Accessible Parking	Parking Space-Van	1	signage are not provided and the slope and/or ground surface is/are not compliant.	Garden Parking Lot	State of Washington	50 WAC 1101; ADA 502.4, 502.5 WA Bldg Code 51	
		West Community				WASHINGTON: An exterior accessible route is		State of	50 WAC 1101.2.1;	
241188	McAuliffe Park	Garden West Community	Exterior Access Route	Exterior Accessible Route	1	not provided. The gate maneuvering clearance area is not	Walkway to Small Garden	Washington	403.3 404; 404.2.3,	\$1,075
241189	McAuliffe Park	Garden	Exterior Access Route	Gate	1	compliant.	Small Garden	ADA	404.2.4 WA Bldg Code 51	\$568 -
		West Community				WASHINGTON: An exterior accessible route is		State of	50 WAC 1101.2.1;	
241191	McAuliffe Park	Garden West Community	Exterior Access Route	Exterior Accessible Route	1	not provided. The gate does not have a smooth surface within	Small Garden	Washington	403.3	\$896
241190	McAuliffe Park	Garden	Exterior Access Route	Gate	2	10" of the ground.	Small Garden	ADA	404.2.10	\$160

\$770,713

					Ph	ase 5				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
254168		2nd Avenue South Doc	k Boating and Fishing	Boarding Pier	1	A gangway system for a boarding pier with less than 25 boat slips is not provided. The edge protection is higher than 4" maximum	Boat Dock	ADA	1003.2.1	\$16,800
254169		2nd Avenue South Doc	k Boating and Fishing	Boarding Pier	1	and/or wider than 2" maximum. The linear pier edge at boarding areas does not have a 60" wide clear openings for each 10 LF	Boat Dock	ADA	1003.3.2	\$133,660
254170		2nd Avenue South Doc	k Boating and Fishing	Boarding Pier	1	maximum length of boarding area.	Boat Dock	ADA	1003.3.2 California Building Code Chap 11B-502.2,	\$0
25.4472				5 11 6 W		CALIFORNIA: A van space and adjacent van aisle		California	502.3, 502.4,	444.500
254172		2nd Avenue South Doc	K Accessible Parking	Parking Space-Van	1	are not provided.	Parking Stall P1	Accessibility Code	502.6 California	\$11,500
						CALIFORNIA: The exterior accessible route has slopes in excess of maximum 1:20 (5%) running		California	Building Code Chap 11B-403.3,	
254173		2nd Avenue South Doc	k Exterior Access Route	Exterior Accessible Route	1	slope and/or maximum 1:48 (2.08)% cross slope.	Access From Public Sidewalk	Accessibility Code	California	\$11,099
						CALIFORNIA: The exterior accessible route has slopes in excess of maximum 1:20 (5%) running	Accessible Route from Parking to	California	Building Code Chap 11B-403.3,	
254174		2nd Avenue South Doc	k Exterior Access Route	Exterior Accessible Route	1	slope and/or maximum 1:48 (2.08)% cross slope. The accessible route has gaps in the surface	•	Accessibility Code		\$1,600
254222		2nd Avenue South Doc	k Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide. Sidewalk has areas of vertical level changes in	Boat Dock	ADA	302.3	\$198
254223		2nd Avenue South Doc	k Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped. The boat slip facility does not have the required	Access From Public Sidewalk	ADA	303	\$991
254166		2nd Avenue South Doc	k Boating and Fishing	Boat Slip	2	number of accessible boat slips. WASHINGTON: A van stall, access aisle, and	Boat Dock	ADA	235.2 WA Bldg Code 51	\$16,730 1-
		Doris Cooper Houghton				signage are not provided and the slope and/or		State of	50 WAC 1101;	
241243		Beach Park Doris Cooper Houghtor	Accessible Parking	Parking Space - Van	1	ground surface is/are not compliant. The slope of the parking space is greater than	Parking Lot 1	Washington	ADA 502.4, 502.5	\$11,300
241244		Beach Park Doris Cooper Houghtor	Accessible Parking	Parking Space - Car	1	1:50 (2%).	Parking Stall 1 (P1)	ADA	502.4	\$6,300
241245		Beach Park Doris Cooper Houghton	Accessible Parking	Parking Space - Car	1	The access aisle slope is greater than 1:50 (2%).	Parking Stall 1 & 2 (P1 & P2)	ADA	502.4	\$5,000
241246		Beach Park Doris Cooper Houghton	Accessible Parking	Parking Space - Car	1	The access aisle is less than 60" wide. The slope of the parking space is greater than	Parking Stall 1 & 2 (P1 & P2)	ADA	502.3.1	\$0
241247		Beach Park	Accessible Parking	Parking Space - Car	1	1:50 (2%).	Parking Stall 2 (P2)	ADA	502.4	\$6,300
241248		Doris Cooper Houghtor Beach Park	n Exterior Access Route	Curb Ramp	1	A compliant parallel curb ramp is not provided. Washington: The curb ramp width is less than 44"	Curb Ramp 1 (CR1)	ADA	WA Bldg Code 51 50 WAC 1101.6.6; ADA 304, 406	
241256		Doris Cooper Houghtor Beach Park	ı Picnic Area	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Picnic Area 1 (PA1)	State of Washington	WA Bldg Code 51 50 WAC 1101.2.1; 403.3	
					_		, -/			T

					Pł	nase 5				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
241257		Doris Cooper Houghton Beach Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Playground (PG)	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3	
241262		Doris Cooper Houghtor Beach Park Doris Cooper Houghtor	Exterior Access Route	Stairs	1	Steps do not have uniform and compliant riser heights and/or tread depths.	Stair 1 (ST1)	ADA	504.2	\$7,650
241263		Beach Park Doris Cooper Houghton	Exterior Access Route	Stairs	1	Handrail extensions are not compliant. An accessible route does not directly connect	Stair 1 (ST1)	ADA	505.1	\$489
241266		Beach Park	Exterior Access Route	Volleyball Court	1	each side of the court outside the play lines.	Volleyball Court	ADA	206.2.12; 403 WA Bldg Code 51-	\$1,906
241267		Doris Cooper Houghtor Beach Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkways Into & Throughout the Park	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$257,700
241276		Doris Cooper Houghtor Beach Park Doris Cooper Houghtor	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. WASHINGTON: The car access aisle signage is	Picnic Area 2 (PA2)	State of Washington State of	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$788
241280		Beach Park	Accessible Parking	Parking Space - Car	1	not compliant or not provided.	Parking Stall 1 & 2 (P1 & P2)	Washington	50 WAC 1101 WA Bldg Code 51-	\$280 -
241686		Doris Cooper Houghtor Beach Park Doris Cooper Houghtor	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. The service counter height is greater than 36" and/or the counter length is less than 36", where	Concession Stand (CS)	State of Washington	50 WAC 1101.2.1; 403.3	\$496
241250		Beach Park	Concession Stand	Service Counter	2	a parallel approach is present. The restroom circulation path is not free of objects protruding more than 4" from wall in the	Concession Stand (CS)	ADA	305; 904.4.1	\$1,805
241254		Doris Cooper Houghton Beach Park	Restroom	Protruding Object	2	space between 27" and 80" height above finish floor.	Men's Restroom (MRR)	ADA	307.2	\$250
241258		Doris Cooper Houghtor Beach Park Doris Cooper Houghtor	Playground	Ground Surface - Fibar	2	The ground surface has not been inspected and maintained regularly. The side of the transfer platform used for	Playground (PG)	ADA	1008.2	\$1,833
241260		Beach Park	Playground	Transfer System	2	transfer is obstructed. The restroom circulation path is not free of objects protruding more than 4" from wall in the	Playground (PG)	ADA	1008.3.1.3	\$500
241284		Doris Cooper Houghtor Beach Park	n Restroom	Protruding Object	2	space between 27" and 80" height above finish floor.	Women's Restroom (WRR)	ADA	307.2	\$250
241249		Doris Cooper Houghton Beach Park	Restroom	Restroom/Bathroom - Signage	3	The provided signage is not mounted at the latch side of the door or at a compliant height.	Men's & Women's Restroom (MRR & WRR)	ADA	216.2,703.1, 703.2, 703.5	\$110
241252		Doris Cooper Houghton Beach Park	Restroom	Restroom/Bathroom - Lavatory	3	The lavatory does not have the required knee clearance.	Men's Restroom (MRR)	ADA	606; 306	\$720
241253		Doris Cooper Houghtor Beach Park	Restroom	Restroom/Bathroom - Lavatory	3	Pipes are not insulated.	Men's Restroom (MRR)	ADA	606.5	\$65

				Ph	nase 5				
Id Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
				,				309, 404.2.7, 604.5.1, 604.6, 604.7, 604.8.1.1, 604.8.1.2,	
	Doris Cooper Houghton	١	Restroom/Bathroom - Toilet		A wheelchair stall is not provided in a multi-user			604.8.1.5, 604.9,	
241255	Beach Park	Restroom	Stall	3	restroom. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Men's Restroom (MRR)	ADA	609.3	\$2,750
	Doris Cooper Houghton	1			on the leading 2" of the tread from the			2009 ANSI A117.1	
241259	Beach Park	Exterior Access Route	Stairs	3	remaining portion of the tread surface. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Playground (PG)	IBC	504.5.1	\$317
	Doris Cooper Houghton				on the leading 2" of the tread from the			2009 ANSI A117.1	
241261	Beach Park	Exterior Access Route	Stairs	3	remaining portion of the tread surface. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Stair 1 (ST1)	IBC	504.5.1	\$176
	Doris Cooper Houghton				on the leading 2" of the tread from the			2009 ANSI A117.1	
241265	Beach Park Doris Cooper Houghtor	Exterior Access Route	Stairs Restroom/Bathroom -	3	remaining portion of the tread surface.	Stair 2 (ST2)	IBC	504.5.1	\$211
241281	Beach Park Doris Cooper Houghtor	Restroom 1	Lavatory	3	Pipes are not insulated. The lavatory does not have the required knee	Women's Restroom (WRR)	ADA	606.5	\$65
241282	Beach Park Doris Cooper Houghtor	Restroom	Restroom/Bathroom-Lavatory Restroom/Bathroom -	3	clearance. The lavatory is mounted higher than 34" to the	Women's Restroom (WRR)	ADA	606; 306	\$720
241283	Beach Park	Restroom	Lavatory	3	higher of the rim or counter.	Women's Restroom (WRR)	ADA	606.2 and 606.3 309, 404.2.7, 604.5.1, 604.6, 604.7, 604.8.1.1, 604.8.1.2,	\$720
	Doris Cooper Houghtor	ı	Restroom/Bathroom - Toilet		A wheelchair stall is not provided in a multi-user			604.8.1.5, 604.9,	
241285	Beach Park	Restroom	Stall	3	restroom.	Women's Restroom (WRR)	ADA	609.3	\$2,750
254119	Heronfield Wetlands	Amenity Not Evaluated	Amenity Not Evaluated	0	The amenity is not regulated by the ADA.	Trails	ADA	None WA Bldg Code 51	\$0 -
254120	Heronfield Wetlands	Exterior Access Route	Exterior Accessible Route Drinking Fountain/Water	5	WASHINGTON: An exterior accessible route is not provided. The minimum number and types of drinking	Jasper's Dog Park	State of Washington	50 WAC 1101.2.1; 403.3	\$58,300
254121	Heronfield Wetlands	Site Furnishings	Cooler	5	fountains are not provided. A clear space is not positioned at the lower level	Drinking Fountain	ADA	211.2; 602; 309	\$8,000
254122	Heronfield Wetlands	Site Furnishings	Drinking Fountain/Water Cooler	5	drinking fountain for a forward approach and centered on the unit. The picnic table does not allow a clear space for forward wheelsheld paragraph with large and taken the control of the	Drinking Fountain	ADA	602.2	\$240
254123	Heronfield Wetlands	Site Furnishings	Picnic Table	5	forward wheelchair approach with knee and toe clearance.	Picnic Table	ADA	902.2; 902.4	\$1,300

				Ph	ase 5				
Id Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
05.110	the Calaborate	According to	D. H. Cover Cover I	·	An accessible parking space is not provided where an off-street parking facility is not	44204 A . N.S. O. N.S. 42204 Circuit	454	Federal 28 CFR Part 35 Subpart D- Program	
254124	Heronfield Wetlands	Accessible Parking	Parking Space-General	5	provided. The gate maneuvering clearance area is not	113th Ave NE & NE 120th Street	ADA	Accessibility 404; 404.2.3,	\$1,120
254125	Heronfield Wetlands	Exterior Access Route	Gate	5	compliant. The gate does not have a smooth surface within	Dog Park Gates	ADA	404.2.4	\$2,272
254162	Heronfield Wetlands	Exterior Access Route	Gate	5	10" of the ground.	Dog Park Gates	ADA	404.2.10 WA Bldg Code 51-	\$640
242958	Highlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. WASHINGTON: A van stall, access aisle, and signage are not provided and the slope and/or	Walkway to Play Area	State of Washington State of	50 WAC 1101.2.1; 403.3 WA Bldg Code 51- 50 WAC 1101;	\$287
242959	Highlands Park	Accessible Parking	Parking Space-Van	1	ground surface is/are not compliant.	On-Street Parking	Washington	ADA 502.4, 502.5 WA Bldg Code 51-	\$11,300
242960	Highlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway to Play Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$1,982
242964	Highlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway to Play Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$991
242965	Highlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway to Play Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$1,586
242972	Highlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway to from Basketball Court to Swings	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$2,478
242977	Highlands Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. The picnic table does not allow a clear space for	Softball Field	State of Washington	50 WAC 1101.2.1; 403.3	\$4,301
242967	Highlands Park	Site Furnishings	Picnic Table	2	forward wheelchair approach with knee and toe clearance.	Picnic Table at Play Area	ADA	902.2; 902.4	\$1,300
242970	Highlands Park	Playground	Transfer System	2	A transfer space is not provided at the platform. The ground surface has not been inspected and	Play Area	ADA	1008.3.1.3	\$5,000
242971	Highlands Park	Playground	Ground Surface-Fibar	2	maintained regularly.	Play Area	ADA	1008.2	\$800
242974	Highlands Park	Playground	Ground Surface-Fibar	2	The ground surface has not been inspected and maintained regularly. The entry points to a play component requiring transfer to entry points are scate is lower than	Swings	ADA	1008.2	\$600
242975	Highlands Park	Playground	Play Component	2	transfer to entry points or seats is lower than 11" and higher than 24". A turning space is not provided at a school-age.	Swings	ADA	1008.4.4	\$400
242976	Highlands Park	Playground	Play Component - Swing Drinking Fountain/Water	2	A turning space is not provided at a school-age swing. The minimum number and types of drinking	Swings	ADA	1008.4.1	\$0
242961	Highlands Park	Site Furnishings	Cooler	4	fountains are not provided.	Drinking Fountain 1 (DF1)	ADA	211.2; 602; 309	\$8,000

				Pł	nase 5				
Id Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
			Drinking Fountain/Water	,	A clear space is not positioned at the lower leved drinking fountain for a forward approach and	el .			
242962	Highlands Park	Site Furnishings	Cooler	4	centered on the unit.	Drinking Fountain 1 (DF1)	ADA	602.2	\$52
242963	Highlands Park	Site Furnishings	Drinking Fountain/Water Cooler	4	The spout height is higher than 36" at the lower/wheelchair level drinking fountain.	Drinking Fountain 1 (DF1)	ADA	602.4	\$8,000
					A curb ramp is not provided where the	Walkway from NE 129th St to Play		WA Bldg Code 51 50 WAC 1101.6;	
239409	Josten Park	Exterior Access Route	Curb Ramp	1	accessible route crosses a curb.	Area	ADA	406.2 WA Bldg Code 51	\$1,750 -
239410	Josten Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Walkway from NE 129th St to Play Area	State of Washington	50 WAC 1101.2.1; 403.3	\$10,035
	Joseph and	Exterior Access Notice		-	The accessible route does not have 80" vertical	Walkway from NE 129th St to Play	J		
239411	Josten Park	Exterior Access Route	Exterior Accessible Route	1	clearance.	Area	ADA	307.4 WA Bldg Code 51	\$500 -
					WASHINGTON: The slopes of the exterior	Walkway from 12th Ave to Play	State of	50 WAC 1101.2.1;	
239412	Josten Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Area	Washington	403.3	\$496
								WA Bldg Code 51 50 WAC 1101.6; ADA 406; 405.2	-
					WASHINGTON: The slope of the curb ramp run		State of	thru 405.5; Table	
239413	Josten Park	Exterior Access Route	Curb Ramp	1	is not compliant. The curb ramp has openings in the ground	Curb Ramp 1 (CR1)	Washington	405.2; 403.5.1	\$1,750
239414	Josten Park	Exterior Access Route	Curb Ramp	1	surface greater than 1/2" wide.	Curb Ramp 1 (CR1)	ADA	302.3 WA Bldg Code 51	\$0 -
22245	Laster Bard	E de de la Accessa De de	5 to de Association Barto	4	WASHINGTON: The slopes of the exterior	Walkway from 12th Ave to Play	State of	50 WAC 1101.2.1;	
239415	Josten Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Area	Washington	403.3 WA Bldg Code 51	\$1,189 -
22244			5		WASHINGTON: The clear width of the exterior	Walkway from 12th Ave to Play	State of	50 WAC 1101.2.1;	
239416	Josten Park	Exterior Access Route	Exterior Accessible Route	1	accessible route is less than 44".	Area	Washington	403.3 WA Bldg Code 51	\$250 -
					WASHINGTON: The slopes of the exterior	Walkway from 12th Ave to Play	State of	50 WAC 1101.2.1;	
239417	Josten Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant. Sidewalk has areas of vertical level changes in	Area Walkway from 12th Ave to Play	Washington	403.3	\$991
239418	Josten Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Area	ADA	303	\$0
					WASHINGTON: An exterior accessible route is	Walkway from 12th Ave to Play	State of	WA Bldg Code 51 50 WAC 1101.2.1;	
239419	Josten Park	Exterior Access Route	Exterior Accessible Route	1	not provided.	Area	Washington	403.3	\$1,075
239420	Josten Park	Exterior Access Route	Exterior Accessible Route	1	A compliant turning space is not provided at a change of direction.	Picnic Area	ADA	304; 403.5.2 WA Bldg Code 51	\$496
239422	Josten Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Playground	State of Washington	50 WAC 1101.2.1; 403.3	
233722	JOSECHIAIK	Exterior Access noute	Exterior Accessible Noute	1	not provided.	i idygi Ouliu	vv asiiiigtoii	- 103.3	J030

					Ph	ase 5				
Id I	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
					,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,			S	WA Bldg Code 51-	
239426		Josten Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is	Dlayground Bonch	State of Washington	50 WAC 1101.2.1; 403.3	\$0
239420		Josten Park	exterior Access Route	Exterior Accessible Route	1	not provided. Sidewalk has areas of vertical level changes in	Playground Bench	wasnington	403.3	Ş U
239427		Josten Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Playground Bench	ADA	303	\$99
						WASHINGTON: A van stall, access aisle, and		6	WA Bldg Code 51-	
240245		Josten Park	Accessible Parking	Parking Space-Van	1	signage are not provided and the slope and/or ground surface is/are not compliant.	On-Street Parking along NE 129th St	State of	50 WAC 1101; ADA 502.4, 502.5	\$11,300
240243		JOSTEILLAIK	Accessible Parking	Parking Space-Van	1	Clear ground space is not provided at each	OII-Street Parking along NE 129th St	wasiiiigtoii	ADA 302.4, 302.3	\$11,500
						ground play component, and each elevated play	Playground - Ground Play			
239423		Josten Park	Playground	Play Component	2	component connected by a ramp.	Components	ADA	1008.4.2	\$0
						A turning space is not provided at a school-age				
239424		Josten Park	Playground	Play Component - Swing	2	swing.	Playground	ADA	1008.4.1	\$0
220425		Jacton Dark	Dlaygraund	Exterior Associals Douts	2	An accessible route within the play area has not	Dlaugraund	ADA	206.2.17.1;	ຕ່າວ ຄວດ
239425		Josten Park	Playground	Exterior Accessible Route	2	been provided. The entry points to a play component requiring	Playground	ADA	1008.2	\$23,820
						transfer to entry points or seats is lower than				
239429		Josten Park	Playground	Play Component	2	11" and higher than 24".	Playground	ADA	1008.4.4	\$400
243860		Josten Park	Picnic Area	Picnic Table	4	A compliant picnic table is not provided.	Picnic Area	ADA	902	\$1,300
						WASHINGTON: A van stall, access aisle, and			WA Bldg Code 51-	
						signage are not provided and the slope and/or		State of	50 WAC 1101;	
240924		Juanita Heights Park	Accessible Parking	Parking Space - Van	1	ground surface is/are not compliant.	Parking Lot 1	Washington	ADA 502.4, 502.5 WA Bldg Code 51-	\$11,300
						WASHINGTON: An exterior accessible route is		State of	50 WAC 1101.2.1;	
240925		Juanita Heights Park	Exterior Access Route	Exterior Accessible Route	1	not provided.	Parking Lot 1 to Stair 1	Washington	403.3	\$519
240926		Juanita Heights Park	Exterior Access Route	Stairs	1	Handrails are not compliant.	Stair 1 (ST1)	ADA	505	\$10,432
239465		Kingsgate Park	Amenity Not Evaluated	Amenity Not Evaluated	0	The amenity is not regulated by the ADA.	Trails	ADA	None	\$0
									WA Bldg Code 51-	
									50 WAC 1101.6;	
									ADA 406; 405.2	
						WASHINGTON: The slope of the curb ramp run		State of	thru 405.5; Table	4
239457		Kingsgate Park	Exterior Access Route	Curb Ramp	1	is not compliant.	Curb Ramp 1 (CR1)	Washington	405.2; 403.5.1	\$1,750
						WASHINGTON: A van stall, access aisle, and signage are not provided and the slope and/or		State of	WA Bldg Code 51- 50 WAC 1101;	
239458		Kingsgate Park	Accessible Parking	Parking Space-Van	1	ground surface is/are not compliant.	On-Street Parking	Washington	ADA 502.4, 502.5	\$11,300
		6-8		6 - Prese	_	8. co			,	+==/
						The curb ramp surface has vertical height				4-
239459		Kingsgate Park	Exterior Access Route	Curb Ramp	1	changes greater than 1/4" that are not ramped.	Curb Ramp 1 (CR1)	ADA	303, 403.4 WA Bldg Code 51-	\$0
									50 WAC 1101.6;	
									ADA 303, 403.4,	
									406; 405.2 thru	
						WASHINGTON: The slope of the curb ramp run		State of	405.5; Table	
239461		Kingsgate Park	Exterior Access Route	Curb Ramp	1	is not compliant.	Curb Ramp 2 (CR2)	Washington	405.2; 403.5.1	\$1,750

					Ph	ase 5				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
					,			S	WA Bldg Code 51	
220462		Vingagata Dark	Exterior Assess Douts	Futorior Accessible Boute	1	WASHINGTON: An exterior accessible route is	Dayly Entrance	State of	50 WAC 1101.2.1;	
239463 240326		Kingsgate Park Kingsgate Park	Exterior Access Route Exterior Access Route	Exterior Accessible Route Gate	1 1	not provided. The gate hardware is not compliant.	Park Entrance Trail Entrance Gate	Washington ADA	403.3 309, 404, 404.2.7	\$717 \$200
240320		Kiligsgate Falk	Exterior Access Route	Gate	1	The gate maneuvering clearance area is not	Trail Littratice Gate	ADA	404; 404.2.3,	3200
240327		Kingsgate Park	Exterior Access Route	Gate	1	compliant.	Trail Entrance Gate	ADA	404.2.4	\$568
						The gate does not have a smooth surface within				,,,,,
240325		Kingsgate Park	Exterior Access Route	Gate	2	10" of the ground.	Trail Entrance Gate	ADA	404.2.10	\$160
						WASHINGTON: A van stall, access aisle, and			WA Bldg Code 51	-
						signage are not provided and the slope and/or		State of	50 WAC 1101;	
240928		Kiwanis Park	Accessible Parking	Parking Space - Van	1	ground surface is/are not compliant.	Parking Lot 1	Washington	ADA 502.4, 502.5	\$11,580
									WA Bldg Code 51	
240020		IV D I	5 1 - 2 - 1 A B - 1 -	E to do a A considir Do to	4	WASHINGTON: An exterior accessible route is	Bissis Assault (DA4)	State of	50 WAC 1101.2.1;	
240929		Kiwanis Park	Exterior Access Route	Exterior Accessible Route	1	not provided. A minimum of 5% ADA compliant dining seating	Picnic Area 1 (PA1)	Washington	403.3	\$1,183
243856		Kiwanis Park	Common Areas	Dining And Work Surface	2	and standing spaces are not provided.	Picnic Area	ADA	226.1	\$1,000
243030		Riwains Lark	Common Arcus	Dining And Work Surface	_	WASHINGTON: A van stall, access aisle, and	Tiente Area	ADA	WA Bldg Code 51	
		Lake Ave W Street End				signage are not provided and the slope and/or		State of	50 WAC 1101;	
239233		Park	Accessible Parking	Parking Space - Van	1	ground surface is/are not compliant.	Parking Lot	Washington	ADA 502.4, 502.5	\$11,300
									WA Bldg Code 51	-
		Lake Ave W Street End				WASHINGTON: An exterior accessible route is		State of	50 WAC 1101.2.1;	
239234		Park	Exterior Access Route	Exterior Accessible Route	1	not provided.	Park Site	Washington	403.3	\$2,043
		Lake Ave W Street End				The minimum number of accessible parking				
243874		Park	Accessible Parking	Parking Spaces-General	1	spaces is not provided.	Parking Lot	ADA	208.2	\$0
239236		Marina Park	Accessible Parking	Parking Spaces-General	1	The minimum number of accessible parking	Parking Lot 1	ADA	208.2	\$0
239230		IVIdIIIId Paik	Accessible Parking	Parking Spaces-General	1	spaces is not provided.	Parking Lot 1	ADA	206.2	ŞU
239237		Marina Park	Exterior Access Route	Curb Ramp	1	A compliant parallel curb ramp is not provided.	Curb Ramp CR1	ADA	304, 406	\$1,750
									WA Bldg Code 51	-
									50 WAC 1101.6.6;	
									ADA 406; 405.2	
						WASHINGTON: The curb ramp width is less than		State of	thru 405.5; Table	
239238		Marina Park	Exterior Access Route	Curb Ramp	1	44".	Curb Ramp CR2	Washington	405.2; 403.5.1	\$1,750
									WA Bldg Code 51	
						WASHINGTON: An exterior accessible route is		State of	50 WAC 1101.2.1;	
239239		Marina Park	Exterior Access Route	Exterior Accessible Route	1	not provided.	Boat Launch BL	Washington	403.3	\$3,746
						WASHINGTON, The closes of the extension		Ctata af	WA Bldg Code 51	
239242		Marina Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway W1	State of Washington	50 WAC 1101.2.1; 403.3	\$10,465
237242		iviai ii la i al K	EXTERIOR ACCESS NOTICE	Exterior Accessible Route	1	Accessible boat slips are not dispersed among	VVGINVVGY VVI	wasiiiigtoii	403.3	710,403
239243		Marina Park	Boating and Fishing	Boat Slip	1	the total number of boat slips at the facility.	Boat Slips BS	ADA	235.2.1	\$450
			5 - 0	,		WASHINGTON: A van stall, access aisle, and	•		WA Bldg Code 51	
						signage are not provided and the slope and/or		State of	50 WAC 1101;	
239252		Marina Park	Accessible Parking	Parking Space - Van	1	ground surface is/are not compliant.	Parking Lot 2	Washington	ADA 502.4, 502.5	\$0

					Ph	ase 5				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
239253		Marina Park	Accessible Parking	Parking Space - Car	1	An access aisle is not provided. The slope of the parking space is greater than	Parking Lot 2 - Stall P1	ADA	502.3; 502.4; 502.5	\$420
239254		Marina Park	Accessible Parking	Parking Space - Car	1	1:50 (2%). The slope of the parking space is greater than	Parking Lot 2 - Stall P1	ADA	502.4	\$6,300
239255 239256		Marina Park Marina Park	Accessible Parking Accessible Parking	Parking Space - Car Parking Space - Car	1 1	1:50 (2%). The access aisle is less than 60" wide.	Parking Lot 2 - Stall P2 Parking Lot 2 - Stall P2	ADA ADA	502.4 502.3.1	\$6,300 \$0
239257		Marina Park	Exterior Access Route	Curb Ramp	1	WASHINGTON: The curb ramp width is less than 44".	Curb Ramp CR3	State of Washington	WA Bldg Code 51- 50 WAC 1101.6.6; ADA 406; 405.2 thru 405.5; Table 405.2; 403.5.1	\$1,750
239258		Marina Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. WASHINGTON: Handrails are not provided	Walkway W2	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3 ADA 505.6; WA	\$10,108
239259		Marina Park	Exterior Access Route	Ramp	1	where the ramp rises more than 6" or are not compliant.	Ramp R1	State of Washington	Bldg Code 51-50 WAC 1101.2.1	\$4,564
239261		Marina Park	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided.	Stair ST2	ADA	505	\$1,141
239262		Marina Park	Exterior Access Route	Curb Ramp	1	WASHINGTON: The slope of the curb ramp run is not compliant.	Curb Ramp CR4	State of Washington	WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2 thru 405.5; Table 405.2; 403.5.1	\$1,750
239263		Marina Park	Exterior Access Route	Curb Ramp	1	WASHINGTON: The curb ramp width is less than 44".	Curb Ramp CR5	State of Washington	WA Bldg Code 51- 50 WAC 1101.6.6; ADA 406; 405.2 thru 405.5; Table 405.2; 403.5.1	\$1,750
239264		Marina Park	Exterior Access Route	Curb Ramp	1	WASHINGTON: The curb ramp width is less than 44".	Curb Ramp CR6	State of Washington	WA Bldg Code 51- 50 WAC 1101.6.6; ADA 406; 405.2 thru 405.5; Table 405.2; 403.5.1	\$1,750
240072		Marina Park	Exterior Access Route	Curb Ramp	1	WASHINGTON: The slope of the curb ramp run is not compliant.	Curb Ramp CR2	State of Washington	WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2 thru 405.5; Table 405.2; 403.5.1	\$0

				Pł	nase 5				
ld Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
240073	Marina Park	Accessible Parking	Parking Space-Car	1	The access aisle slope is greater than 1:50 (2%). WASHINGTON: The car access aisle signage is	Parking Lot 2 - Stall P2	ADA State of	502.4 WA Bldg Code 51	\$5,000
240074	Marina Park	Accessible Parking	Parking Space-Car	1	not compliant or not provided.	Parking Lot 2 - Stall P2	Washington	50 WAC 1101	\$280
								WA Bldg Code 51 50 WAC 1101.6.6; ADA 406; 405.2	;
					WASHINGTON: The curb ramp width is less than		State of	thru 405.5; Table	
240076	Marina Park	Exterior Access Route	Curb Ramp	1	44". The adjacent surfaces at transitions to adjoining walks, gutters and streets at the curb ramp are	Curb Ramp CR4	Washington	405.2; 403.5.1	\$0
240077	Marina Park	Exterior Access Route	Curb Ramp	1	not at the same level. The adjacent surfaces at transitions to adjoining walks, gutters and streets at the curb ramp are	Curb Ramp CR4	ADA	303; 406.2	\$0
240078	Marina Park	Exterior Access Route	Curb Ramp	1	not at the same level. A compliant accessible route is not provided	Curb Ramp CR5	ADA	303; 406.2	\$0
240079	Marina Park	Exterior Access Route	Exterior Accessible Route	1	from the public access to the amenity.	Beach	ADA	206; 206.2.2 228.1; 305; 308;	\$9,500
239244	Marina Park	Exterior Access Route	Vending Machine	2	The vending machines are not accessible. The restroom circulation path is not free of objects protruding more than 4" from wall in the space between 27" and 80" height above finish	Vending Machine VM	ADA	309	\$3,254
239246	Marina Park	Restroom	Protruding Object	2	floor. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the	Men's & Women's Restroom	ADA	307.2 2009 ANSI A117.1	\$800
239241	Marina Park	Exterior Access Route	Stairs Restroom/Bathroom -	3	remaining portion of the tread surface.	Stair ST1	IBC	504.5.1	\$141
239245	Marina Park	Restroom	Lavatory	3	Pipes are not insulated.	Men's & Women's Restroom	ADA	606.5	\$130
			Restroom/Bathroom - Toilet		WASHINGTON: A vertical side grab bar is not			2009 ANSI A117.1 604.5.1 and	1-
239247	Marina Park	Restroom	Stall Restroom/Bathroom - Toilet	3	present in the wheelchair stall. The side grab bar is not compliant in the	Men's & Women's Restroom	ANSI A117.1	A117.1-604.9.6	\$710
239248	Marina Park	Restroom	Stall Restroom/Bathroom - Toilet	3	wheelchair stall.	Men's & Women's Restroom	ADA	604.5.1; 604.8.1.5	5 \$710
239249	Marina Park	Restroom	Stall Restroom/Bathroom - Toilet	3	The wheelchair stall door is not self closing. The hardware at the wheelchair stall door is not	Men's & Women's Restroom	ADA	604.8.1.2 309, 404.2.7,	\$586
239250	Marina Park	Restroom	Stall	3	compliant. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Men's & Women's Restroom	ADA	604.8.1.2	\$586
239260	Marina Park	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface.	Stair ST2	IBC	2009 ANSI A117.1 504.5.1	1- \$141

					Ph	ase 5				
Id Fa	acility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
239251		Marina Park Phyllis A. Needy	Exterior Access Route	Drinking Fountain/Water Cooler	4	The minimum number and types of drinking fountains are not provided.	Drinking Fountain DF1	ADA	211.2; 602; 309 WA Bldg Code 51-	\$8,000
243167		Houghton Neighborhood Phyllis A. Needy	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 1 (W1)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$1,023
243168		Houghton Neighborhood Phyllis A. Needy	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 2 (W2)	State of Washington	50 WAC 1101.2.1; 403.3	\$6,754
243169		Houghton Neighborhood Phyllis A. Needy	Exterior Access Route	Exterior Accessible Route	1	The accessible route has gaps in the surface greater than 1/2" wide.	Walkway 2 (W2)	ADA	302.3	\$450
243171		Houghton Neighborhood Phyllis A. Needy	Restroom	Restroom/Bathroom - Door	1	The maneuvering clearance at the accessible door is not level and clear.	Unisex Restroom (URR)	ADA	305.2; 404.2 WA Bldg Code 51-	\$1,250
243179		Houghton Neighborhood Phyllis A. Needy	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 3 (W3)	State of Washington	50 WAC 1101.2.1; 403.3	\$37,521
243180		Houghton Neighborhood Phyllis A. Needy	Exterior Access Route	Exterior Accessible Route	1	The sidewalk does not have 80" vertical clearance.	Walkway 3 (W3)	ADA	307.4 WA Bldg Code 51-	\$500
243181		Houghton Neighborhood Phyllis A. Needy	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Playground 1 (PG1)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$317
243185		Houghton Neighborhood Phyllis A. Needy	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Playground 2 (PG2)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$788
243187		Houghton Neighborhood Phyllis A. Needy	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Playground 3 (PG3)	State of Washington	50 WAC 1101.2.1; 403.3	\$591
243166		Houghton Neighborhood	Exterior Access Route	Gate	2	The gate does not have a smooth surface within 10" of the ground. The restroom circulation path is not free of	Gate 1 (G1)	ADA	404.2.10	\$160
243175		Phyllis A. Needy Houghton Neighborhood	Restroom	Protruding Object	2	objects protruding more than 4" from wall in the space between 27" and 80" height above finish floor.	Unisex Restroom (URR)	ADA	307.2	\$200
243182		Phyllis A. Needy Houghton Neighborhood	Playground	Ground Surface - Fibar	2	The ground surface has not been inspected and maintained regularly.	Playground 1 (PG1)	ADA	1008.2	\$1,296
243184		Phyllis A. Needy Houghton Neighborhood	Playground	Transfer System	2	A means of support is not provided at the transfer platform and/or transfer steps.	Playground 1 (PG1)	ADA	1008.3.1.4, 1008.3.2.3	\$495
243186		Phyllis A. Needy Houghton Neighborhood	Playground	Ground Surface - Fibar	2	The ground surface has not been inspected and maintained regularly.	Playground 2 (PG2)	ADA	1008.2	\$640

					Ph	ase 5				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
		Phyllis A. Needy Houghton		Restroom/Bathroom -						
243172	!	Neighborhood	Restroom	Lavatory	3	Pipes are not insulated. The mirror is mounted higher than 40" above	Unisex Restroom (URR)	ADA	606.5	\$65
		Phyllis A. Needy Houghton				finish floor to the bottom of the reflective surface, where it is installed above a lavatory or				
243174	,	Neighborhood Phyllis A. Needy	Restroom	Restroom/Bathroom - Mirror	3	counter.	Unisex Restroom (URR)	ADA	213.3.5; 603.3	\$200
243176	;	Houghton Neighborhood	Restroom	Restroom/Bathroom - Water Closet	3	The flush control is located on the closed side and/or is not within reach range.	Unisex Restroom (URR)	ADA	604.6	\$313
		Phyllis A. Needy Houghton				The accessible door with door closer has a sweep period of less than 5 seconds from 90				
243178	}	Neighborhood	Restroom	Restroom/Bathroom - Door	3	degrees to a position 12 degrees from latch. WASHINGTON: The stair treads do not have	Unisex Restroom (URR)	ADA	404.2.8	\$366
		Phyllis A. Needy Houghton				visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the			2009 ANSI A117.1-	
243183	1	Neighborhood	Exterior Access Route	Stairs	3	remaining portion of the tread surface.	Playground 1 (PG1)	IBC	504.5.1	\$246
		Phyllis A. Needy Houghton		Restroom/Bathroom - Toilet		WASHINGTON: A vertical side grab bar is not			2009 ANSI A117.1- 604.5.1 and	
243188	}	Neighborhood	Restroom	Stall	3	present in the wheelchair stall.	Unisex Restroom (URR)	ANSI A117.1	A117.1-604.9.6	\$355
		Phyllis A. Needy Houghton		Drinking Fountain/Water		The minimum number and types of drinking				
243170		Neighborhood	Site Furnishings	Cooler	4	fountains are not provided.	Drinking Fountain 1 (DF1)	ADA	211.2; 602; 309	\$8,000

\$892,895

					Ph	ase 6				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
254015 253616 253639	O. O. Denny Park O. O. Denny Park	Cotton Hill Park EXTERIOR EXTERIOR	Amenity Not Evaluated Amenity Not Evaluated Amenity Not Evaluated	Amenity Not Evaluated Amenity Not Evaluated Amenity Not Evaluated	0 0 0	The amenity is not regulated by the ADA. The amenity is not regulated by the ADA. The amenity is not regulated by the ADA. WASHINGTON: A van stall, access aisle, and signage are not provided and the slope and/or	Cotton Hill Park Denny Creek Trail Access to Water Front	ADA ADA ADA State of	None None None WA Bldg Code 51- 50 WAC 1101;	\$0 \$0 \$0
253609	O. O. Denny Park	EXTERIOR	Accessible Parking	Parking Space-Van	1	ground surface is/are not compliant. WASHINGTON: A car stall, access aisle, and signage are not provided and the slope and/or	Parking Lot 1	Washington State of	ADA 502.4, 502.5 WA Bldg Code 51- 50 WAC 1101;	\$11,300
253611	O. O. Denny Park	EXTERIOR	Accessible Parking	Parking Space-Car	1	ground surface is/are not compliant. The slope of the parking space is greater than	Parking Lot 1	Washington	ADA 502.4, 502.5	\$11,300
253617	O. O. Denny Park	EXTERIOR	Accessible Parking	Parking Space - Car	1	1:50 (2%). WASHINGTON: Compliant signage is not	Parking Lot 2 - Stall P1	ADA	502.4 502.6; WA Bldg Code 51-50 WAC	\$6,300
253618	O. O. Denny Park	EXTERIOR	Accessible Parking	Parking Space - Car	1	provided at the standard space or access aisle.	Parking Lot 2 - Stall P1 / P2 Aisle	ADA	1101.2.6	\$280
253619	O. O. Denny Park	EXTERIOR	Accessible Parking	Parking Space - Car	1	The access aisle slope is greater than 1:50 (2%). The slope of the parking space is greater than	Parking Lot 2 - Stall P1 / P2 Aisle	ADA	502.4	\$5,000
253620	O. O. Denny Park	EXTERIOR	Accessible Parking	Parking Space - Car	1	1:50 (2%). The slope of the parking space is greater than	Parking Lot 2 - Stall P2	ADA	502.4	\$6,300
253621	O. O. Denny Park	EXTERIOR	Accessible Parking	Parking Space - Van	1	1:50 (2%).	Parking Lot 2 - Stall P3	ADA	502.4	\$6,300
253622	O. O. Denny Park	EXTERIOR	Accessible Parking	Parking Space - Van	1	The access aisle slope is greater than 1:50 (2%). WASHINGTON: Compliant signage is not	Parking Lot 2 - Stall P3 / P4 Aisle	ADA	502.4 502.6; WA Bldg Code 51-50 WAC	\$5,000
253623	O. O. Denny Park	EXTERIOR	Accessible Parking	Parking Space - Car	1	provided at the standard space or access aisle. The slope of the parking space is greater than	Parking Lot 2 - Stall P4	ADA	1101.2.6	\$280
253624	O. O. Denny Park	EXTERIOR	Accessible Parking	Parking Space - Car	1	1:50 (2%).	Parking Lot 2 - Stall P4	ADA	502.4	\$6,300
						WASHINGTON: The slope of the curb ramp run		State of	WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2 thru 405.5; Table	
253625	O. O. Denny Park	EXTERIOR	Exterior Access Route	Curb Ramp	1	is not compliant. The landing at the top of the curb ramp is not a	Curb Ramp CR1	Washington	405.2; 403.5.1	\$1,750
253626	O. O. Denny Park	EXTERIOR	Exterior Access Route	Curb Ramp	1	compliant size.	Curb Ramp CR1	ADA	406.4	\$1,289
						WACHINGTON: The place of the conference		Change of	WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2	
253627	O. O. Denny Park	EXTERIOR	Exterior Access Route	Curb Ramp	1	WASHINGTON: The slope of the curb ramp run is not compliant. The landing at the top of the curb ramp is not a	Curb Ramp CR2	State of Washington	thru 405.5; Table 405.2; 403.5.1	\$1,750
253628	O. O. Denny Park	EXTERIOR	Exterior Access Route	Curb Ramp	1	compliant size.	Curb Ramp CR2	ADA	406.4	\$1,289

					Ph	ase 6				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
253629	O. O. Denny Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The clear width of the exterior accessible route is less than 44".	Access from Parking Lot 2 toward Restrooms	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$1,586
253630	O. O. Denny Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Wooden Bridge	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$2,973
253631	O. O. Denny Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Access Route AR1 - Route from P1 into The Park	State of Washington	50 WAC 1101.2.1; 403.3	\$2,400
						WASHINGTON: The clear width of the ramp is		State of	WA Bldg Code 51- 50 WAC 1101.2.1; ADA 406; 405.2 thru 405.5; Table	
253633	O. O. Denny Park	EXTERIOR	Exterior Access Route	Ramp	1	less than 44". WASHINGTON: The clear width of the exterior	Playground Ramp	Washington State of	405.2; 403.5.1 WA Bldg Code 51- 50 WAC 1101.2.1;	\$3,310
253642	O. O. Denny Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	accessible route is less than 44". WASHINGTON: A van stall, access aisle, and signage are not provided and the slope and/or	Park Entrance	Washington State of	403.3 WA Bldg Code 51- 50 WAC 1101;	\$238
243204	Terrace Park	EXTERIOR	Accessible Parking	Parking Space - Van	1	ground surface is/are not compliant. An accessible route to the portable restroom	Parking Lot 1	Washington	ADA 502.4, 502.5	\$11,860
243206	Terrace Park	EXTERIOR	Portable Restroom	Portable Restroom	1	has not been provided.	Portable Restroom PRR	ADA	402, 404	\$1,120
									WA Bldg Code 51- 50 WAC 1101.6; ADA 406; 405.2	
243207	Terrace Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the ramp are not compliant.	Playground	State of Washington	thru 405.5; Table 405.2; 403.5.1 WA Bldg Code 51-	\$2,648
243212	Terrace Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Basketball Practice & Ball Field	State of Washington	50 WAC 1101.2.1; 403.3	\$5,976
243214	Terrace Park	EXTERIOR	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided. Steps do not have uniform and compliant riser	Stair ST1	ADA	505	\$15,648
243216	Terrace Park	EXTERIOR	Exterior Access Route	Stairs	1	heights and/or tread depths.	Stair ST1	ADA	504.2	\$29,376
243217	Terrace Park	EXTERIOR	Exterior Access Route	Curb Ramp	1	A compliant parallel curb ramp is not provided.	Curb Ramp CR1	ADA	304, 406	\$4,328
243218	Terrace Park	EXTERIOR	Exterior Access Route	Curb Ramp	1	A compliant parallel curb ramp is not provided.	Curb Ramp CR2	ADA	304, 406	\$4,328
243219	Terrace Park	EXTERIOR	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway W1	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3	\$1,982

					Ph	ase 6				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
253632	O. O. Denny Park	EXTERIOR	Picnic Shelter	Picnic Table	2	The picnic table does not allow a clear space for forward wheelchair approach with knee and toe clearance.	Picnic Shelter	ADA	802.1; 902.2; 902.4	\$1,300
253634	O. O. Denny Park	EXTERIOR	Playground	Ground Surface-Fibar	2	The ground surface has not been inspected and maintained regularly. The entry points to a play component requiring transfer to entry points or seats is lower than	Playground	ADA	1008.2	\$625
253637	O. O. Denny Park	EXTERIOR	Playground	Play Component	2	11" and higher than 24". The ground surface has not been inspected and	Playground	ADA	1008.4.4	\$800
243208	Terrace Park	EXTERIOR	Playground	Ground Surface - Fibar	2	maintained regularly. The side of the transfer platform used for	Playground	ADA	1008.2	\$7,566
243209	Terrace Park	EXTERIOR	Playground	Transfer System	2	transfer is obstructed. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark on the leading 2" of the tread from the	Playground	ADA	1008.3.1.3 2009 ANSI A117.1	\$500
253635	O. O. Denny Park	EXTERIOR	Exterior Access Route	Stairs	3	remaining portion of the tread surface.	Playground	IBC	504.5.1	\$387
243205	Terrace Park	EXTERIOR	Portable Restroom	Portable Restroom	3	An ADA portable restroom is not provided. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Portable Restroom PRR	ADA	213.2; 402.2	\$3,000
243215	Terrace Park	EXTERIOR	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface.	Stair ST1	IBC	2009 ANSI A117.1 504.5.1 WA Bldg Code 51	\$1,091 -
241217		Marsh Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. Sidewalk has areas of vertical level changes in	Walkways Into & Throughout the Park	State of Washington	50 WAC 1101.2.1; 403.3	\$44,780
241222		Marsh Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped. WASHINGTON: A van stall, access aisle, and	Drinking Fountain 1 (DF1)	ADA State of	303 WA Bldg Code 51	\$357 -
241223		Marsh Park	Accessible Parking	Parking Space - Van	1	signage are not provided and the slope and/or ground surface is/are not compliant. The slope of the parking space is greater than	Parking Lot 1	State of Washington	50 WAC 1101; ADA 502.4, 502.5	\$11,300
241224		Marsh Park	Accessible Parking	Parking Space - Car	1	1:50 (2%).	Parking Stall 1 (P1)	ADA	502.4	\$6,300
241225		Marsh Park	Accessible Parking	Parking Space - Car	1	The access aisle slope is greater than 1:50 (2%).	Parking Stall 1 (P1)	ADA	502.4	\$5,000
						WASHINGTON: The curb ramp width is less than		State of	WA Bldg Code 51- 50 WAC 1101.6.6; ADA 406; 405.2 thru 405.5; Table	
241226		Marsh Park	Exterior Access Route	Curb Ramp	1	44". WASHINGTON: The car access aisle signage is	Curb Ramp 1 (CR1)	Washington State of	405.2; 403.5.1 WA Bldg Code 51	\$0 -
241227		Marsh Park	Accessible Parking	Parking Space - Car	1	not compliant or not provided.	Parking Stall 1 (P1)	Washington	50 WAC 1101 WA Bldg Code 51	\$280
241228		Marsh Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 1 (W1)	State of Washington	50 WAC 1101.2.1; 403.3	\$3,900

				Ph	nase 6				
ld Facility	Building	Assembly	Туре	Barrier Priority		Location Description	ADA	Ref. Number	Total
241230	Marsh Park	Exterior Access Route	Stairs	1	Handrails are not compliant or are not provided.	. Stair 1 (ST1)	ADA	505	\$4,238
241236	Marsh Park	Exterior Access Route	Stairs	1	Handrails are not compliant.	Stair 2 (ST2)	ADA	505	\$1,956
241240	Marsh Park	Exterior Access Route	Stairs	1	Handrails are not compliant.	Stair 3 (ST3)	ADA	505	\$3,260
					Steps do not have uniform and compliant riser				
241241	Marsh Park	Exterior Access Route	Stairs	1	heights and/or tread depths.	Stair 3 (ST3)	ADA	504.2	\$4,590
241685	Marsh Park	Exterior Access Route	Curb Ramp	1	WASHINGTON: The slope of the curb ramp run is not compliant.	Curb Ramp 1 (CR1)	State of Washington	WA Bldg Code 51 50 WAC 1101.6; ADA 406; 405.2 thru 405.5; Table 405.2; 403.5.1	 \$1,750
			·		Protruding objects in the 27" to 80" range above finished floor protrude more than 4" into the		ū		
244347	Marsh Park	Exterior Access Route	Protruding Object	1	circulation path along the accessible route. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Drinking Fountain 2 (DF2)	ADA	307.2	\$728
					on the leading 2" of the tread from the			2009 ANSI A117.1	
241229	Marsh Park	Exterior Access Route	Stairs	3	remaining portion of the tread surface.	Stair 1 (ST1)	IBC	504.5.1 309, 404.2.7, 604.5.1, 604.6, 604.7, 604.8.1.1, 604.8.1.2,	\$317
			Restroom/Bathroom - Toilet		A wheelchair stall is not provided in a multi-user	Men's & Women's Restroom (MRR		604.8.1.5, 604.9,	
241231	Marsh Park	Restroom	Stall Restroom/B <mark>athroom</mark> -	3	restroom.	& WRR) Men's & Women's Restroom (MRR	ADA	609.3	\$5,500
241232	Marsh Park	Restroom	Lavatory Restroom/Bathroom -	3	Pipes are not insulated. The lavatory does not have the required knee	& WRR) Men's & Women's Restroom (MRR	ADA	606.5	\$130
241233	Marsh Park	Restroom	Lavatory Restroom/Bathroom -	3	clearance.	& WRR)	ADA	606; 306	\$1,440
241234	Marsh Park	Restroom	Lavatory	3	Faucets are not compliant WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Women's Restroom (WRR)	ADA	606.4; 309	\$555
241235	Marsh Park	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Stair 2 (ST2)	IBC	2009 ANSI A117.1 504.5.1	\$141
241239	Marsh Park	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface. A clear space is not positioned at the lower level diplains for a forward approach and	Stair 3 (ST3)	IBC	2009 ANSI A117.1 504.5.1	1- \$246
241220	Marsh Park	Exterior Access Route	Drinking Fountain/Water Cooler Drinking Fountain/Water	4	drinking fountain for a forward approach and centered on the unit.	Drinking Fountain 1 (DF1)	ADA	602.2	\$238
241221	Marsh Park	Site Furnishings	Drinking Fountain/Water Cooler	4	The minimum number and types of drinking fountains are not provided.	Drinking Fountain 1 (DF1)	ADA	211.2; 602; 309	\$8,000

Phase 6										
Id Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total	
241237	Marsh Park	Site Furnishings	Drinking Fountain/Water Cooler	4	The minimum number and types of drinking fountains are not provided. A clear space is not positioned at the lower level	Drinking Fountain 2 (DF2)	ADA	211.2; 602; 309	\$8,000	
241238	Marsh Park	Site Furnishings	Drinking Fountain/Water Cooler	4	drinking fountain for a forward approach and centered on the unit. WASHINGTON: A van stall, access aisle, and	Drinking Fountain 2 (DF2)	ADA	602.2 WA Bldg Code 51	\$120 I-	
243221	Ohde Avenue Pea Patch Ohde Avenue Pea	Accessible Parking	Parking Space - Van	1	signage are not provided and the slope and/or ground surface is/are not compliant. An accessible route to the portable restroom	Parking Lot 1	State of Washington	50 WAC 1101; ADA 502.4, 502.5	\$11,300	
243223	Patch	Portable Restroom	Portable Restroom	1	has not been provided.	Portable Restroom (PRR)	ADA	402, 404 WA Bldg Code 51	\$986 L-	
243224	Ohde Avenue Pea Patch Ohde Avenue Pea	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Community Garden	State of Washington	50 WAC 1101.2.1 403.3	; \$5,914	
243222	Patch	Portable Restroom	Portable Restroom	3	An ADA portable restroom is not provided. WASHINGTON: The slopes of the exterior	Portable Restroom (PRR)	ADA State of	213.2; 402.2 WA Bldg Code 51 50 WAC 1101.2.1		
243136	Reservoir Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant. WASHINGTON: A van stall, access aisle, and	Trash Receptacles	Washington	403.3 WA Bldg Code 51	\$991	
243137	Reservoir Park	Accessible Parking	Parking Space-Van	1	signage are not provided and the slope and/or ground surface is/are not compliant.	Parking Lot	State of Washington	50 WAC 1101; ADA 502.4, 502.5 WA Bldg Code 51		
243138	Reservoir Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. Sidewalk has areas of vertical level changes in	Walkway from 15th Ave to Park	State of Washington	50 WAC 1101.2.1 403.3	; \$9,910	
243139	Reservoir Park	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Walkway from 15th Ave to Park	ADA	303 WA Bldg Code 51	\$198 L-	
243140	Reservoir Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The clear width of the exterior accessible route is less than 44".	Walkway from 15th Ave to Park	State of Washington	50 WAC 1101.2.1 403.3 WA Bldg Code 51	\$476	
243141	Reservoir Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway to Play Area	State of Washington	50 WAC 1101.2.1 403.3 WA Bldg Code 51	\$317	
243142	Reservoir Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Walkway to Picnic Table	State of Washington	50 WAC 1101.2.1 403.3		
243250	Reservoir Park	Exterior Access Route	Exterior Accessible Route	1	In areas along the route there are level changes of 1/2" or greater that are not ramped.	Walkway to Play Area	ADA	303.4, 405, 406	\$99	
243145	Reservoir Park	Playground	Ground Surface-Fibar	2	The ground surface has not been inspected and maintained regularly.	Play Area	ADA	1008.2	\$1,350	
243146	Reservoir Park	Playground	Transfer System	2	A transfer space is not provided at the platform.	Play Area	ADA	1008.3.1.3	\$0	
243147	Reservoir Park	Playground	Transfer System	2	The transfer platform for connecting to elevated play elements has non-compliant dimensions.	i Play Area	ADA	1008.3.1.1	\$23,909	

					Ph	ase 6				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243149		Reservoir Park	Playground	Play Component - Swing	2	A turning space is not provided at a school-age swing. The entry points to a play component requiring transfer to entry points or seats is lower than	Play Area	ADA	1008.4.1	\$0
243150		Reservoir Park	Playground	Play Component	2	11" and higher than 24".	Play Area	ADA	1008.4.4	\$400
243148		Reservoir Park	Picnic Area	Picnic Table	4	A compliant picnic table is not provided. The opening force of the fire door is more than the minimum allowable by the appropriate	Picnic Table	ADA	902	\$1,300
253594	O. O. Denny Park	RESTROOMS	Entrance to Building	Building Entrance - Door	1	administrative authority.	Men's Restroom	ADA	404.2.9	\$366
253607	O. O. Denny Park	RESTROOMS	Exterior Access Route	Protruding Object	1	Protruding objects in the 27" to 80" range above the finished floor protrude more than 4" into the circulation path along the accessible route. The swinging door does not have a smooth surface within 10" of the ground measured vertically on the push side extending the full		ADA	307.2	\$728
253601	O. O. Denny Park	RESTROOMS	Exterior Access Route	Door	2	width of the door.	Women's Restroom	ADA	404.2.10	\$200
252502	O. O. Dawey, Bark	DECEDOOMS	Destruction	Darker and /Dakk up and Circum	2	The restroom does not have compliant signage at the door with the International Symbol of	Marile Deather are	454	216.2, 703.1, 703.2, 703.5,	ć
253593	O. O. Denny Park	RESTROOMS	Restroom	Restroom/Bathroom-Signage Restroom/Bathroom -	3	Accessibility, raised characters, and Braille.	Men's Restroom	ADA	703.6	\$55
253596	O. O. Denny Park	RESTROOMS	Restroom	Lavatory	3	Pip <mark>es a</mark> re not insulated.	Men's Restroom	ADA	606.5	\$65
253598	O. O. Denny Park	RESTROOMS	Restroom	Controls And Dispensers	3	The height of controls are not compliant. The wheelchair stall with a wall-mounted water	Men's Restroom	ADA	606.1; 309.3	\$200
253599	O. O. Denny Park	RESTROOMS	Restroom	Restroom/Bathroom - Toilet Stall	3	closet, in a multi-stall restroom, is less than 60" wide and 56" deep.	Men's Restroom	ADA	604.8.1.1	\$1,368
						The restroom does not have compliant signage at the door with the International Symbol of			216.2, 703.1, 703.2, 703.5,	
253602	O. O. Denny Park	RESTROOMS	Restroom	Restroom/Bathroom-Signage Restroom/Bathroom -	3	Accessibility, raised characters, and Braille.	Women's Restroom	ADA	703.6	\$55
253603	O. O. Denny Park	RESTROOMS	Restroom	Lavatory	3	Pipes are not insulated.	Women's Restroom	ADA	606.5	\$65
253604	O. O. Denny Park	RESTROOMS	Restroom	Controls And Dispensers Restroom/Bathroom - Toilet	3	The height of controls is not compliant.	Women's Restroom	ADA	606.1; 309.3	\$200
253605	O. O. Denny Park	RESTROOMS	Restroom	Stall	3	The wheelchair stall door is not self-closing. The wheelchair stall with a wall-mounted water	Women's Restroom	ADA	604.8.1.2	\$293
253606	O. O. Denny Park	RESTROOMS	Restroom	Restroom/Bathroom - Toilet Stall	3	closet, in a multi-stall restroom, is less than 60" wide and 56" deep. The minimum number of drinking fountains is not provided. If the minimum number is provided, two levels or a hi-lo are not provided.	Women's Restroom	ADA	604.8.1.1	\$1,368
				Drinking Fountain/Water		If more than 2 are provided, less than 50% are			211.1; 211.2; 602	-,
253608	O. O. Denny Park	RESTROOMS	Site Furnishings	Cooler	4	high or less than 50% are low.	Restrooms Building	ADA	309	\$5,440

				Ph	ase 6				
Id Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
241212	Settler's Landing	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	PROW to Park Entrance (PE)	State of Washington	WA Bldg Code 51- 50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$5,153
241213	Settler's Landing	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway 1 (W1)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$2,973
241214	Settler's Landing	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The boarding pier has vertical changes in level between 1/4" and 1/2" that are not beveled,	Walkway 2 (W2)	State of Washington	50 WAC 1101.2.1; 403.3 1003.2.2,	
241215 243249	Settler's Landing Snyders Corner	Boating and Fishing Amenity Not Evaluated	Boarding Pier Amenity Not Evaluated	1 0	and/or greater than 1/2" that are not ramped. The amenity does not exist. A curb ramp is not provided where the	Boarding Pier (BP) Snyder's Corner Site	ADA ADA	Exception 1 None	\$576 \$0
239468	South Norway Hill Park	Exterior Access Route	Curb Ramp	1	accessible route crosses a curb. WASHINGTON: A van stall, access aisle, and signage are not provided and the slope and/or	NW Entrance from 122nd Ave NE	ADA State of	406.2 WA Bldg Code 51- 50 WAC 1101;	\$1,750 -
239469	South Norway Hill Park	Accessible Parking	Parking Space-Van	1	ground surface is/are not compliant. WASHINGTON: An exterior accessible route is	On-Street Parking	Washington State of	ADA 502.4, 502.5 WA Bldg Code 51- 50 WAC 1101.2.1;	
239471 240328	•	Exterior Access Route Amenity Not Evaluated	Exterior Accessible Route Amenity Not Evaluated	1 5	not provided. The amenity is not regulated by the ADA. The maneuvering clearance at the accessible	NW Entrance from 122nd Ave NE Trails	Washington ADA	403.3 None	\$538 \$0
243235	South Rose Hill Park	Restroom	Restroom/Bathroom - Door	1	door is not level and clear. Accessible parking spaces are not at the nearest	Unisex Restroom (URR)	ADA	305.2; 404.2	\$1,250
243236	South Rose Hill Park	Accessible Parking	Parking Space - General	1	accessible entrance.	Parking Lot 1	ADA	208.3 WA Bldg Code 51-	\$0 -
243237	South Rose Hill Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Picnic Area 1 (PA1)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$986
243238	South Rose Hill Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Playground 1 (PG1)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$238
243241	South Rose Hill Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Playground 2 (PG2)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$238
243243	South Rose Hill Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. WASHINGTON: A van stall, access aisle, and	Walkway 1 (W1)	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51-	\$5,946
243245	South Rose Hill Park	Accessible Parking	Parking Space-Van	1	signage are not provided and the slope and/or ground surface is/are not compliant. The gate does not have a smooth surface within	Parking Lot 1 - Stall P1	State of Washington	50 WAC 1101; ADA 502.4, 502.5	\$11,300
243226	South Rose Hill Park	Exterior Access Route	Gate	2	10" of the ground.	Gate 1 (G1)	ADA	404.2.10	\$160

					Ph	ase 6				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
						The restroom circulation path is not free of objects protruding more than 4" from wall in the				
						space between 27" and 80" height above finish				
243231		South Rose Hill Park	Restroom	Protruding Object	2	floor.	Unisex Restroom (URR)	ADA	307.2	\$250
243239		South Rose Hill Park	Playground	Ground Surface - Fibar	2	The ground surface has not been inspected and maintained regularly.	Playground 1 (PG1)	ADA	1008.2	\$1,950
					_	The ground surface has not been inspected and	,8 = (,			
243240		South Rose Hill Park	Playground	Ground Surface - Fibar Restroom/Bathroom -	2	maintained regularly.	Playground 2 (PG2)	ADA	1008.2	\$3,400
243229		South Rose Hill Park	Restroom	Lavatory	3	Pipes are not insulated.	Unisex Restroom (URR)	ADA	606.5	\$65
						The restroom does not have compliant signage			216.2, 703.1,	
				Restroom/Bathroom -		at the door with the International Symbol of			703.2, 703.5,	
243232		South Rose Hill Park	Restroom	Signage	3	Accessibility, raised characters, and Braille. The accessible door with door closer has a	Unisex Restroom (URR)	ADA	703.6	\$55
						sweep period of less than 5 seconds from 90				
243233		South Rose Hill Park	Restroom	Restroom/Bathroom - Door	3	degrees to a position 12 degrees from latch. WASHINGTON: The stair treads do not have	Unisex Restroom (URR)	ADA	404.2.8	\$366
						visual contrast of dark-on-light or light-on-dark				
242242		South Rose Hill Park	Exterior Assess Douts	Chaire	3	on the leading 2" of the tread from the	Distance and 2 (DC2)	IBC	2009 ANSI A117.1 504.5.1	 \$176
243242		South Rose Hill Park	Exterior Access Route	Stairs	3	remaining portion of the tread surface.	Playground 2 (PG2)	IBC	504.5.1	\$176
				Budana (Bulliana Talla)		MACHINETON A suitabile subbasis su			2009 ANSI A117.1	
243246		South Rose Hill Park	Restroom	Restroom/Bathroom - Toilet Stall	3	WASHINGTON: A vertical side grab bar is not present in the wheelchair stall.	Unisex Restroom (URR)	ANSI A117.1	604.5.1 and A117.1-604.9.6	\$355
				Drinking Fountain/Water		The minimum number and types of drinking				
243227		South Rose Hill Park	Site Furnishings	Cooler	4	fountains are not provided. A clear space is not positioned at the lower level	Drinking Fountain 1 (DF1)	ADA	211.2; 602; 309	\$8,000
				Drinking Fountain/Water		drinking fountain for a forward approach and				
243228		South Rose Hill Park	Site Furnishings	Cooler	4	centered on the unit.	Drinking Fountain 1 (DF1)	ADA	602.2 WA Bldg Code 51	\$238 -
						WASHINGTON: An exterior accessible route is		State of	50 WAC 1101.2.1;	
239266		Street End Park	Exterior Access Route	Exterior Accessible Route	1	not provided.	Public Right Of Way to Park	Washington	403.3 WA Bldg Code 51	\$2,400 -
						WASHINGTON: An exterior accessible route is		State of	50 WAC 1101.2.1;	
243251		Tot Lot & Pea Patch	Exterior Access Route	Exterior Accessible Route	1	not provided.	Walkway to Community Garden	Washington	403.3 WA Bldg Code 51	\$134
						WASHINGTON: A van stall, access aisle, and		State of	50 WAC 1101;	
243252		Tot Lot & Pea Patch	Accessible Parking	Parking Space-Van	1	signage are not provided.	On-Street Parking	Washington	ADA 502.4, 502.5	\$11,300
243253		Tot Lot & Pea Patch	Entrance to Building	Building Entrance - Door	1	The maneuvering clearance at the accessible gate is not level and clear.	Community Garden Entrance Gate	ADA	305.2; 404.2	\$1,250
						WASHINGTON: An exterior accessible route is		Ctata of	WA Bldg Code 51	
243255		Tot Lot & Pea Patch	Exterior Access Route	Exterior Accessible Route	1	not provided.	Community Garden	State of Washington	50 WAC 1101.2.1; 403.3	\$7,168
							•	=		

					Ph	ase 6				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243256		Tot Lot & Pea Patch	Exterior Access Route	Exterior Accessible Route	1	Sidewalk has areas of vertical level changes in excess of 1/4" that are not ramped. The maneuvering clearance at the accessible	Community Garden	ADA	303	\$300
243261		Tot Lot & Pea Patch	Entrance to Amenity	Building Entrance - Door	1	gate is not level and clear. Accessible entries are not identified with the	Park Entrance Gate 2	ADA	305.2; 404.2	\$1,250
243262		Tot Lot & Pea Patch	Entrance to Building	Building Entrance - Door	1	International Symbol of Accessibility, where not all entrances are accessible. Sidewalk has areas of vertical level changes in	Park Entrance Gate 2	ADA	216.6	\$120
243264		Tot Lot & Pea Patch	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Park Entrance Gate 2	ADA	303 WA Bldg Code 51	\$36 -
243265		Tot Lot & Pea Patch	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The clear width of the exterior accessible route is less than 44".	Walkway to Picnic Area	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$2,378
243266		Tot Lot & Pea Patch	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. Sidewalk has areas of vertical level changes in	Walkway to Picnic Area	State of Washington	50 WAC 1101.2.1; 403.3	\$0
243267		Tot Lot & Pea Patch	Exterior Access Route	Exterior Accessible Route	1	excess of 1/4" that are not ramped.	Walkway to Picnic Area	ADA	303 WA Bldg Code 51	
243269		Tot Lot & Pea Patch	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided. An accessible route to the portable restroom	Access to Playground	State of Washington	50 WAC 1101.2.1; 403.3	\$2,150
243272		Tot Lot & Pea Patch	Portable Restroom	Portable Restroom	1	has not been provided. The accessible route does not have 80" vertical	Portable Restroom 1 (RR1)	ADA	402, 404	\$896
243283		Tot Lot & Pea Patch	Exterior Access Route	Exterior Accessible Route	1	clearance. The gate does not have a smooth surface within	Walkway to Picnic Area	ADA	307.4	\$250
243254		Tot Lot & Pea Patch	Exterior Access Route	Gate	2	10" of the ground. The gate does not have a smooth surface within	Community Garden Entrance Gate	ADA	404.2.10	\$160
243263		Tot Lot & Pea Patch	Exterior Access Route	Gate	2	10" of the ground. One of each type of ground level component is	Park Entrance Gate 2	ADA	404.2.10	\$160
243270		Tot Lot & Pea Patch	Playground	Play Component	2	not on an accessible route. Clear ground space is not provided at each	Ground Play Components	ADA	240.2.1.1	\$5,376
243271		Tot Lot & Pea Patch	Playground	Play Component	2	ground play component, and each elevated play component connected by a ramp. The entry points to a play component requiring	Vehicle Ground Play Components	ADA	1008.4.2	\$192
243275		Tot Lot & Pea Patch	Playground	Play Component	2	transfer to entry points or seats is lower than 11" and higher than 24". A compliant turning space is not provided at a	Ground Play Components	ADA	1008.4.4	\$800
243276		Tot Lot & Pea Patch	Playground	Play Component - Swing	2	school-age swing. The ground surface has not been inspected and	Ground Play Components Playground surfacing- engineered	ADA	1008.4.1	\$50
243277		Tot Lot & Pea Patch	Playground	Ground Surface-Fibar	2	maintained regularly.	wood fibar	ADA	1008.2	\$1,600
243279		Tot Lot & Pea Patch	Playground	Transfer System	2	A transfer space is not provided at the platform. An accessible sand table is not provided at the	Elevated Play Component Ground Play Components- Ages 2-5	ADA	1008.3.1.3	\$5,000
244746		Tot Lot & Pea Patch	Playground	Play Component	2	sand play area for ages 2-5.	Sand Area	ADA	240.2.1.1, 1008.4.3	\$5,000

					Ph	ase 6				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
243257		Tot Lot & Pea Patch	Exterior Access Route	Clear Space	3	Clear space is not provided at the operable part. Clear space is not provided at the operable	Community Garden Trash Receptacle with lid adjacent	ADA	305; 309.2	\$108
243258		Tot Lot & Pea Patch	Exterior Access Route	Clear Space	3	part/lid of trash receptacle.	to the Public Sidewalk	ADA	305; 309.2	\$215
243273		Tot Lot & Pea Patch	Portable Restroom	Portable Restroom	3	An ADA portable restroom is not provided. Directional signage indicating the accessible path of travel is not provided, where existing path of travels are both accessible and non-	Portable Restroom 1 (RR1)	ADA	213.2; 402.2	\$3,000
243259		Tot Lot & Pea Patch	Exterior Access Route	Signage	4	accessible. WASHINGTON: The slopes of the exterior	Park Entrance Gate 1	ADA State of	216.3, 703 WA Bldg Code 51- 50 WAC 1101.2.1;	\$280
239475		Totem Lake Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Walkway to Upper Park	Washington	403.3	\$793
239476		Totem Lake Park	Exterior Access Route	Stairs	1	Handrails are not compliant. The curb ramp surface has vertical height	Stair 1 (ST1)	ADA	505	\$652
239479		Totem Lake Park	Exterior Access Route	Curb Ramp	1	changes greater than 1/4" that are not ramped.	Curb Ramp (CR1)	ADA	303, 403.4 WA Bldg Code 51-	\$1,750
239480		Totem Lake Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route has gaps in the surface	Walkway to Playground from Public Right-of-Way Walkway to Playground from	State of Washington	50 WAC 1101.2.1; 403.3	\$640
239481		Totem Lake Park	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide.	Parking Lot	ADA	302.3	\$300
239482		Totem Lake Park	Exterior Access Route	Stairs	1	Handrails are not compliant.	Stair 2 (ST2)	ADA State of	505 WA Bldg Code 51-	\$3,260
239503		Totem Lake Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. The accessible route has gaps in the surface	Walkway to Bridge	Washington	50 WAC 1101.2.1; 403.3	\$840
239504		Totem Lake Park	Exterior Access Route	Exterior Accessible Route	1	greater than 1/2" wide. The slope of the parking space is greater than	Walkway to Bridge	ADA	302.3	\$500
243942		Totem Lake Park	Accessible Parking	Parking Space - Car	1	1:50 (2%).	Accessible Parking Space 1 (P1)	ADA	502.4	\$6,300
243943		Totem Lake Park	Accessible Parking	Parking Space - Car	1	The access aisle slope is greater than 1:50 (2%). WASHINGTON: The car access aisle signage is	Accessible Aisle serving P1	ADA State of	502.4 WA Bldg Code 51-	
243944		Totem Lake Park	Accessible Parking	Parking Space - Car	1	not compliant or not provided. The standard car stall and/or access aisle has openings in ground surfaces greater than 1/2"	Accessible Aisle serving P1	Washington	50 WAC 1101	\$280
243945		Totem Lake Park	Accessible Parking	Parking Space - Car	1	wide. The slope of the parking space is greater than	Accessible Aisle serving P1	ADA	302.3	\$0
243946		Totem Lake Park	Accessible Parking	Parking Space - Car	1	1:50 (2%).	Van Accessible Parking Space 2 (P2)	ADA	502.4	\$6,300
243947		Totem Lake Park	Accessible Parking	Parking Space - Car	1	The access aisle slope is greater than 1:50 (2%). WASHINGTON: The car access aisle signage is	Accessible Aisle serving P2/P3	ADA State of	502.4 WA Bldg Code 51-	\$5,000
243948		Totem Lake Park	Accessible Parking	Parking Space - Car	1	not compliant or not provided. The slope of the parking space is greater than	Accessible Aisle serving P2/P3	Washington	50 WAC 1101	\$280
243949		Totem Lake Park	Accessible Parking	Parking Space - Car	1	1:50 (2%).	Accessible Parking Space 3 (P3)	ADA	502.4	\$6,300

					Ph	ase 6				
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
						Protruding objects in the 27" to 80" range above finished floor protrude more than 4" into the				
243951		Totem Lake Park	Exterior Access Route	Protruding Object	1	circulation path along the accessible route. The accessible route does not have 80" vertical	Walkway at Restroom	ADA	307.2	\$728
243952		Totem Lake Park	Exterior Access Route	Exterior Accessible Route	1	clearance. The ground surface within the use zone does	Walkway at Restroom	ADA	307.4	\$186
239500		Totem Lake Park	Playground	Ground Surface	2	not comply with ASTM F 1292.	Playground	ADA	105.2.3; 1008.2.6	\$0
239501		Totem Lake Park	Playground	Play Component	2	50% or more of the elevated play components are not on an accessible route. The elevated play structure does not have a transfer platform. The restroom circulation path is not free of objects protruding more than 4" from wall in the space between 27" and 80" height above finish	Playground	ADA	240.2.2, 1008.3.1 1008.3.1.2	, \$25,000
243956		Totem Lake Park	Restroom	Protruding Object	2	floor. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Unisex Restroom 3 (RR3)	ADA	307.2	\$93
239477		Totem Lake Park	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Stair 1 (ST1)	IBC	2009 ANSI A117.1 504.5.1	1- \$176
239483		Totem Lake Park	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface.	Stair 2 (ST2)	IBC	2009 ANSI A117.1 504.5.1	L- \$352
						The force required to open the interior, hinged,				
239486		Totem Lake Park	Restroom	Restroom/Bathroom - Door	3	non-fire door is more than 5 pounds. The accessible door with door closer has a sweep period of less than 5 seconds from 90	Unisex Restroom 1 (RR1)	ADA	404.2.9	\$0
239487		Totem Lake Park	Restroom	Restroom/Bathroom - Door Restroom/Bathroom -	3	degrees to a position 12 degrees from latch. The lavatory is mounted higher than 34" to the	Unisex Restroom 1 (RR1)	ADA	404.2.8	\$366
239489		Totem Lake Park	Restroom	Lavatory	3	higher of the rim or counter. The mirror is mounted higher than 40" above finish floor to the bottom of the reflective surface, where it is installed above a lavatory or	Unisex Restroom 1 (RR1)	ADA	606.2 and 606.3	\$720
239490		Totem Lake Park	Restroom	Restroom/Bathroom - Mirror	3	counter. The force required to open the interior, hinged,	Unisex Restroom 1 (RR1)	ADA	213.3.5; 603.3	\$200
239493		Totem Lake Park	Restroom	Restroom/Bathroom - Door	3	non-fire door is more than 5 pounds. The accessible door with door closer has a sweep period of less than 5 seconds from 90	Unisex Restroom 2 (RR2)	ADA	404.2.9	\$0
239494		Totem Lake Park	Restroom	Restroom/Bathroom - Door Restroom/Bathroom -	3	degrees to a position 12 degrees from latch. The lavatory is mounted higher than 34" to the	Unisex Restroom 2 (RR2)	ADA	404.2.8	\$366
239496		Totem Lake Park	Restroom	Lavatory	3	higher of the rim or counter.	Unisex Restroom 2 (RR2)	ADA	606.2 and 606.3	\$720

				Pł	nase 6				
Id Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
239497	Totem Lake Park	Restroom	Restroom/Bathroom - Mirror	3	The mirror is mounted higher than 40" above finish floor to the bottom of the reflective surface, where it is installed above a lavatory or counter.	Unisex Restroom 2 (RR2)	ADA	213.3.5; 603.3	\$200
			Restroom/Bathroom - Water		The centerline of the toilet in the wheelchair stall is not 16" minimum to 18" maximum from				
239499	Totem Lake Park	Restroom	Closet	3	the sidewall. The force required to open the interior, hinged,	Unisex Restroom 2 (RR2)	ADA	604.2	\$630
243953	Totem Lake Park	Restroom	Restroom/Bathroom-Door	3	non-fire door is more than <mark>5 po</mark> unds. The push side of the do <mark>or do</mark> es not have the	Unisex Restroom 3 (RR3)	ADA	404.2.9	\$366
243954	Totem Lake Park	Restroom	Restroom/Bathroom - Door	3	required maneuvering clearances. The mirror is mounted higher than 40" above finish floor to the bottom of the reflective surface, where it is installed above a lavatory or	Unisex Restroom 3 (RR3)	ADA	404.2.4	\$100
243955	Totem Lake Park	Restroom	Restroom/Bathroom - Mirror	3	counter.	Unisex Restroom 3 (RR3)	ADA	213.3.5; 603.3 WA Bldg Code 51	\$200
243152	Van Aalst Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Walkway to Tennis Court/Half Basketball Court	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$2,867
243153	Van Aalst Park	Accessible Parking	Parking Space-Van	1	WASHINGTON: A van stall, access aisle, and signage are not provided.	On-Street Parking	State of Washington	50 WAC 1101; ADA 502.4, 502.5 WA Bldg Code 51	\$11,300
243154	Van Aalst Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Walkway to Playground	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$1,792
243155	Van Aalst Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Playground	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$36
243164	Van Aalst Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Walkway to Playground	State of Washington	50 WAC 1101.2.1; 403.3	\$2,150
243157	Van Aalst Park		Ground Surface-Fibar	2	The ground surface has not been inspected and	, , , , , ,	ADA	1008.2	\$1,750
245157	Vall Adist Park	Playground	Ground Surface-Fibal	2	maintained regularly.	Playground	ADA	1008.2	\$1,750
243158 243159	Van Aalst Park Van Aalst Park	Playground Playground	Transfer System Transfer System	2 2	A transfer space is not provided at the platform. The transfer steps are less than 24" wide.	Playground Playground	ADA ADA	1008.3.1.3 1008.3.2.1	\$5,000 \$13,020
243133	van Austran	ridyground	Transier System	_	The slope of the turning space at the school-age		ADA	1000.3.2.1	\$13,020
243161	Van Aalst Park	Playground	Play Component - Swing	2	swing is not level. The entry points to a play component requiring transfer to entry points or seats is lower than	Playground	ADA	304, 1008.4.1	\$750
243162	Van Aalst Park	Playground	Play Component	2	11" and higher than 24". The play component which has manipulative or interactive features that require reaching is not	Playground	ADA	1008.4.4	\$400
243160	Van Aalst Park	Playground	Play Component	4	within the child's reach range.	Playground	ADA	Advisory 1008.4.2	2 \$5,000
243163	Van Aalst Park	Picnic Area	Picnic Table	4	A compliant picnic table is not provided.	Picnic Table	ADA	902	\$1,300
254117	Watershed Park	Amenity Not Evaluated	Amenity Not Evaluated	0	The amenity is not regulated by the ADA.	Watershed Park	ADA	None	\$0

Phase 6										
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total
239297		Waverly Beach Park	Accessible Parking	Parking Space - Van	1	WASHINGTON: A van stall, access aisle, and signage are not provided and the slope and/or ground surface is/are not compliant. The slope of the parking space is greater than	Parking Lot	State of Washington	WA Bldg Code 51 50 WAC 1101; ADA 502.4, 502.5	\$11,300
239298		Waverly Beach Park	Accessible Parking	Parking Space - Car	1	1:50 (2%).	Parking Lot - Stall P1	ADA	502.4	\$6,300
239299 239302		Waverly Beach Park Waverly Beach Park	Accessible Parking Exterior Access Route	Parking Space - Car Stairs	1 1	The access aisle slope is greater than 1:50 (2%). Handrail extensions are not compliant.	Parking Lot - Stall P1 Stair ST1	ADA ADA	502.4 505.1 WA Bldg Code 51	\$5,000 \$326 -
239303		Waverly Beach Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant. WASHINGTON: The slopes of the exterior	Walkway W1	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$2,141 -
239304		Waverly Beach Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Walkway W2	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$3,171 -
239305		Waverly Beach Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: An exterior accessible route is not provided.	Beach	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$2,378 -
239306		Waverly Beach Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway W3	State of Washington	50 WAC 1101.2.1; 403.3 WA Bldg Code 51	\$20,613 -
239307		Waverly Beach Park	Exterior Access Route	Exterior Accessible Route	1	WASHINGTON: The slopes of the exterior accessible route are not compliant.	Walkway W4	State of Washington	50 WAC 1101.2.1; 403.3	\$3,568
239312		Waverly Beach Park	Playground	Exterior Accessible Route	1	Handrails are not compliant or are not provided.	Stair ST2	ADA	505	\$1,630
239315		Waverly Beach Park	Playground	Play Component	1	Handrails are not compliant or are not provided. WASHINGTON: The car access aisle signage is	Stair ST3	ADA State of	505 WA Bldg Code 51	\$3,260
239316		Waverly Beach Park	Accessible Parking	Parking Space - Car	1	not compliant or not provided. The minimum number of accessible parking	Parking Lot - Stall P1	Washington	50 WAC 1101	\$280
243873		Waverly Beach Park	Accessible Parking	Parking Spaces-General	1	spaces is not provided. The restroom circulation path is not free of objects protruding more than 4" from wall in the space between 27" and 80" height above finish	Parking Lot	ADA	208.2	\$0
239287		Waverly Beach Park	Restroom	Protruding Object	2	floor. The ground surface has not been inspected and	Men's & Women's Restroom	ADA	307.2	\$186
239309		Waverly Beach Park	Playground	Ground Surface - Fibar	2	maintained regularly. The side of the transfer platform used for	Playground	ADA	1008.2	\$1,250
239311		Waverly Beach Park	Playground	Transfer System	2	transfer is obstructed.	Playground	ADA	1008.3.1.3	\$500
239284		Waverly Beach Park	Restroom	Restroom/Bathroom - Signage Restroom/Bathroom -	3	The provided signage is not mounted at the latch side of the door or at a compliant height.	Men's & Women's Restroom	ADA	216.2,703.1, 703.2, 703.5	\$110
239285		Waverly Beach Park	Restroom	Lavatory	3	Pipes are not insulated.	Men's & Women's Restroom	ADA	606.5	\$130

Phase 6										
Id Facility	Building	Assembly	Туре	Barrier Priority		Location Description	ADA	Ref. Number	Total	
239286	Waverly Beach Park	Restroom	Restroom/Bathroom - Lavatory Restroom/Bathroom - Toilet	3	The lavatory is mounted higher than 34" to the higher of the rim or counter.	Men's Restroom	ADA	606.2 and 606.3	\$720	
239288	Waverly Beach Park	Restroom	Stall Restroom/Bathroom - Toilet	3	The wheelchair stall door is not self closing. The hardware at the wheelchair stall door is not	Men's & Women's Restroom	ADA	604.8.1.2 309, 404.2.7,	\$586	
239289	Waverly Beach Park	Restroom	Stall	3	compliant.	Men's & Women's Restroom	ADA	604.8.1.2	\$586	
239290	Waverly Beach Park	Restroom	Restroom/Bathroom - Toilet Stall	3	WASHINGTON: A vertical side grab bar is not present in the wheelchair stall. The centerline of the toilet in the wheelchair	Men's & Women's Restroom	ANSI A117.1	2009 ANSI A117.1 604.5.1 and A117.1-604.9.6	 \$710	
239291	Waverly Beach Park	Restroom	Restroom/Bathroom - Water Closet	3	stall is not 16" minimum to 18" maximum from the sidewall.	Men's & Women's Restroom	ADA	604.2	\$1,260	
239292	Waverly Beach Park	Restroom	Restroom/Bathroom - Water Closet Restroom/Bathroom - Water	3	The height of the water closet is not 17" minimum to 19" maximum above finished floor. The side grab bar at the water closet is not	Men's & Women's Restroom	ADA	604.4	\$1,260	
239293	Waverly Beach Park	Restroom	Closet Restroom/Bathroom - Water	3	compliant. The flush control is located on the closed side	Men's & Women's Restroom	ADA	604.5.1	\$710	
239294	Waverly Beach Park	Restroom	Closet	3	and/or is not within reach range.	Men's & Women's Restroom	ADA	604.6 ADA 604.7, 609.3	\$626	
239295	Waverly Beach Park	Restroom	Restroom/Bathroom - Water Closet	3	WASHINGTON: The toilet paper dispenser location is not compliant. The mirror is mounted higher than 40" above finish floor to the bottom of the reflective	Men's & Women's Restroom	State of Washington	2009 ANSI A117.1 604.7		
239296	Waverly Beach Park	Restroom	Restroom/Bathroom - Mirror	3	surface, where it is installed above a lavatory or counter. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Women's Restroom	ADA	213.3.5; 603.3	\$200	
239301	Waverly Beach Park	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Stair ST1	IBC	2009 ANSI A117.1 504.5.1	 \$1,091	
239313	Waverly Beach Park	Exterior Access Route	Stairs	3	on the leading 2" of the tread from the remaining portion of the tread surface. WASHINGTON: The stair treads do not have visual contrast of dark-on-light or light-on-dark	Stair ST2	IBC	2009 ANSI A117.1 504.5.1	 \$211	
239314	Waverly Beach Park	Exterior Access Route	Stairs Drinking Fountain/Water	3	on the leading 2" of the tread from the remaining portion of the tread surface. The minimum number and types of drinking	Stair ST3	IBC	2009 ANSI A117.1 504.5.1	 \$493	
239283	Waverly Beach Park	Exterior Access Route	Cooler	4	fountains are not provided.	Drinking Fountain DF1	ADA	211.2; 602; 309	\$8,000	
239448	Windsor Vista Park	Amenity Not Evaluated	Amenity Not Evaluated	0	The amenity is not regulated by the ADA. A curb ramp is not provided where the	Trails	ADA	None	\$0	
239430	Windsor Vista Park	Exterior Access Route	Curb Ramp	1	accessible route crosses a curb.	Entrance to Park (Proposed Parking)	ADA	406.2	\$1,750	

	Phase 6										
Id	Facility	Building	Assembly	Туре	Barrier Priority	Detail	Location Description	ADA	Ref. Number	Total	
						WASHINGTON: A van stall, access aisle, and signage are not provided and the slope and/or		State of	WA Bldg Code 51- 50 WAC 1101;		
239431		Windsor Vista Park	Accessible Parking	Parking Space-Van	1	ground surface is/are not compliant.	On-Street Parking	Washington	ADA 502.4, 502.5 WA Bldg Code 51-	\$11,300	
						WASHINGTON: The slopes of the exterior		State of	50 WAC 1101.2.1;	4	
239432		Windsor Vista Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Walkway to Playground	Washington	403.3 WA Bldg Code 51-	\$1,586	
						WASHINGTON: The slopes of the exterior		State of	50 WAC 1101.2.1;	4	
239433		Windsor Vista Park	Exterior Access Route	Exterior Accessible Route	1	accessible route are not compliant.	Walkway to Playground	Washington	403.3 WA Bldg Code 51-	\$317	
						WASHINGTON: An exterior accessible route is		State of	50 WAC 1101.2.1;		
239439		Windsor Vista Park	Exterior Access Route	Exterior Accessible Route	1	not provided.	Picnic Table	Washington	403.3 WA Bldg Code 51-	\$717 -	
						WASHINGTON: An exterior accessible route is		State of	50 WAC 1101.2.1;		
239440		Windsor Vista Park	Exterior Access Route	Exterior Accessible Route	1	not prov <mark>ided</mark> .	Bench	Washington	403.3 WA Bldg Code 51-	\$538	
						WASHINGTON: An exterior accessible route is		State of	50 WAC 1101.2.1;		
239443		Windsor Vista Park	Exterior Access Route	Exterior Accessible Route	1	not provided. The ground surface has not been inspected and	Garden	Washington	403.3	\$5,376	
239435		Windsor Vista Park	Playground	Ground Surface-Fibar	2	maintained regularly. A turning space is not provided at a school-age	Playground	ADA	1008.2	\$2,000	
239436		Windsor Vista Park	Playground	Play Component - Swing	2	swing. The entry points to a play component requiring	Playground	ADA	1008.4.1	\$0	
						transfer to entry points or seats is lower than					
239437		Windsor Vista Park	Playground	Play Component	2	11" and higher than 24".	Playground	ADA	1008.4.4	\$400	
239438		Windsor Vista Park	Playground	Transfer System	2	A transfer space is not provided at the platform.	Playground	ADA	1008.3.1.3	\$0	
254118		Yarrow Bay Wetlands	Amenity Not Evaluated	Amenity Not Evaluated	0	The amenity is not regulated by the ADA.	Yarrow Bay Wetlands	ADA	None	\$0	

\$689,316



Human Services Commission Meeting: 2/22/2022 Agenda: Old Business Item#:7a

MEMORANDUM

To: Human Services Commission

From: Lynn Zwaagstra, Director

Leslie R. Miller, Human Services Supervisor

Date: February 17, 2022

Subject: COMMUNITY DEVELOPMENT BLOCK GRANT CV-3 RECOMMENDATIONS

RECOMMENDATION:

That the Human Services Commission review a draft list of recommendations for allocating the third and largest traunch of CDBG CV funds.

BACKGROUND DISCUSSION:

The primary objective of the federal Community Development Block Grant (CDBG) program is to support the development of viable urban communities by providing decent housing, a suitable living environment via community facilities and public infrastructure, and expanded economic opportunities, principally for persons of low and moderate income. Funds are distributed to communities nationwide on a formula basis.

The City of Kirkland was allocated \$426,945 for the third and final traunch of CDBG-CV funds. Staff recommends that all of the funds be made available to non-profit agencies to serve the community through a Request for Proposal (RFP) process. Commissioners are asked to respond to the following proposed breakdown:

- \$226,945 to support mental health providers
- \$100,000 to address food insecurity
- \$100,000 to support case management, mental health support and emergency financial aid to Spanish and Portuguese community members

Human Services Commission Meeting: 2/22/2022 Agenda: Old Business Item#:7b



CITY OF KIRKLAND Department of Parks & Community Services 123 5th Avenue, Kirkland, WA 98033 425.587.3300 www.kirklandwa.gov

MEMORANDUM

To: Human Services Commission

From: Lynn Zwaagstra, Director

Leslie R. Miller, Human Services Supervisor

Date: February 17, 2022

Subject: 2023-2024 HUMAN SERVICES GRANT APPLICATION CALENDAR DISCUSSION

RECOMMENDATION:

That the Human Services Commission continue its discussion of the calendar for the 2023-2024 human services grant application.

BACKGROUND DISCUSSION:

Human services grants are allocated as part of the City's biannual budget process. The Human Services Commission will be recommending funding for 2023-2024 grants to City Council in the fall of next year. The Commission began a discussion of the calendar for the application review process last month. The Commission will complete this discussion at this month's meeting.